

New SRF Facility at KEK

H. Hayano, KEK, 10072014

Outline of proposed Program

2012 supplementary budget,
Industry-University cooperation, **Center Of Innovation (COI)** program

Targeting 10-20 years future social needs, innovative technology development center based on Industry-University cooperation is to be facilitated.

KEK and industries proposed:

- (1) Pollution removal with electricity generation technology,
- (2) International electricity network,
- (3) New alternative resource material generation,
- (4) Ozone layer generator,

Energy
Environment
Resource

In the future. To make innovation to solve above subject,
Seed technologies are;

- (a) superconducting accelerator technologies
- (b) technologies of quantum-beam utilization
- (c) cryo-technologies

SC accelerator


Industrialization of, compact sized of, SC accelerator

=

ILC


Overall view of proposal

Earth Cleaner



Ozone layer generator


International Energy Network



Compact material analyzer for new resource material

New SRF facility : promotion of superconducting accelerator utilization

New building (80m x 30m) is under construction at North of STF
Superconducting Accelerator Development Hall




SC cavity inspection & process, vertical test, cryomodule assembly, cryomodule test⁴

Satellite View of new building location



Building location detail



Construction status of new building



Construction completion will be end of Jan. 2015




List of new device to be installed

- (1) A large size clean room for ILC cryomodule assembly
- (2) EP facility to develop industrial EP
- (3) 4-cavities Vertical test stand
- (4) ILC Cryomodule assembly tools
- (5) Helium Cryogenics
- (6) Cryomodule test stand (to be installed later)

with

- (1) Center control room
- (2) KEK researcher room
- (3) Industry room
- (4) Small meeting room
- (5) Exhibition space


ISO4 & ISO6 Clean Rooms for ILC cryomodule assembly




ISO-4, ISO-6 clean rooms, with dual cavity rail

Flat-floor Clean Room, ventilating to side wall

For easy floor cleaning, easy rail dip cleaning






Block diagram of vertical EP system (VEP)



Vertical EP (VEP) Cavity mount stage

Mounting at horizontal,
Electrode insertion in vertical,
EP at vertical.




VEP

Cavity vertical position
during electrode insertion and EP



Cavity horizontal position
during cavity and EP header installation



Use as a horizontal EP is also possible.

VEP

VEP Electrode Insertion





HPR (Nozzle rotation type)




HPR (High Pressure water Rinsing)

Cavity: no rotation, but up and down
Water nozzle: rotation

Front view from EP floor



Clean
Room
side




Vertical Test

Under Building 4-cavity Vertical Test Stand, following DESY AMTF

DESY AMTF




KEK new vertical test cryostat




Vertical Test

Hanging 4 cavities with jacket and pipe




TESLA cavity with jacket




TESLA cavity w/o jacket

Cryomodule assembly tool



Cryomodule Assembly tools, following to DESY/Saclay XFEL facility

Cryomodule assembly tool



Cryomodule Assembly tools, following to DESY/Saclay XFEL facility

Cryomodule Assembly tools, following to DESY/Saclay XFEL facility



Experiment Hall




South half-side
7t crane
View from control room



North half-side
15t crane
View from east to west

Resident space




1st floor, exhibition space and stairs,
view from entrance

2nd floor, open space and control room



Plan of Start-up schedule



End of Slide