

Managed by Fermi Research Alliance, LLC for the U.S. Department of Energy Office of Science

CM-2 Status

E. Harms Accelerator: SRF Working Group 08 October 2014



Outline

- Introduction
- Current situation
- Single cavity results
- Unit results
- Issues and lessons
- Conclusions & summary



• CM-2 is

Introduction

- Type 3+ ILC type Cryomodule
- 8 cavities (1.3 GHz) built by industry
- Vertical and Horizontal tests at JLab & Fermilab (good to 35 MV/m)
- Cryomodule assembled at Fermilab
- first ILC type cryomodule which may(?) reach average gradient specification of 31.5 MV/m
- Designed for pulsed operation
- Main accelerating device for ASTA
- Expect beam tests in FY2015







CM-2 Current situation



- CM-2 achieved an average cavity gradient of 31.5 MV/m this past Friday (3 October) with all 8 cavities powered simultaneously
- 1.6 millisecond pulse width, 5 Hz repetition rate
- Lorentz Force Detuning Compensation (LFDC) on and 'adapting'
- Peak accelerating voltage = 252 MV



How did we get here - timeline

- Cryomodule installed in NML/ASTA April 2013,
- Warm coupler conditioning (one cavity at a time) 9 May to 18 June 2013
- Cooldown 23 October to 11 November 2013
- Begin cold operation, Cavity 1 only 13 November 2013
- Cavity 1 complete (13 November 30 January)
- Cavity 2 complete (31 January 15 February, 16 days)
- Cavity 3 complete (24 February 4 March, 9 days)
- Cavity 4 complete (4 10 March, 6 days)
- Cavity 5 complete (18 26 March, 9 days)
- Cavity 6 complete (28 March 3 April, 7 days)
- Cavity 7 complete (4 April 7 May, mostly done by 8 April, coupler vacuum)
- Cavity 8 complete (23 May 6 June) warm coupler vacuum issue
- Revisit cavities 6 & 1 (1 -14 July)
- Cavity 1 7 unit test (25 July 26 August)
- Revisit Cavity 8 warm coupler vacuum (26 August 9 September)
- Complete unit, 8 cavities, test (9 September present)

🛠 Fermilab



Single cavity results

- Once cold, each cavity individually powered to determine performance characteristics
 - Tune cavity to resonance
 - Map out and set $\rm Q_L$
 - System calibrations, calculate gradient, k
 - On-resonance conditioning
 - Determine peak performance
 - Final (high power) LLRF calibration
 - Lorentz Force Detuning Compensation set-up
 - Document dark current, x-rays vs. gradient
 - Dynamic Heat Load measurements (Q₀)



Single cavity results

- Operating conditions
 - 2 Kelvin (23 Torr)
 - Pulsed operation
 - 1.6 ms pulse
 - 590 μ s fill + 969 μ s flattop
 - 5 Hz repetition rate
 - Q_L set to 3.5 E6, variable coupling
 - LFDC active
- Results
 - 7/8 cavities achieve 31.5 MV/m (administrative limit)
 - Cavity #6 quenches at 30.5 MV/m







Single cavity results – DHL/Q₀





courtesy Andy Hocker, TD



Cavity 8

TB9AES008

08/10/2014

Single cavity – field emission, dark current





at end end of cryomodule



Field Emission measured by 'chipmunk' placed below cavity under test





08/10/2014

Unit results



- Warm coupler vacuum issues prompted with cavity #8 prompted initial unit test powering only 1-7 initially
- Leak checking, nitrogen purge, luck? finally allowed full unit operation
- 5 days of coupler conditioning was required before high power testing was possible – cavity 8 vacuum and warm window field emission
- Peak gradient limited by cavity #6 (hard) quench (30.5 31 MV/m)





Unit test – DHL/Q₀





Q₀ for cavities 1-7 powered together (1-8 results under analysis)

courtesy Andy Hocker, TD



08/10/2014

Unit test – field emission (scarecrows)

- No response below ~19 MV/m from any cavity
- Varied results from cavity to cavity
- More response from end detector (~X5)
- Saturation (needs investigating)







07-0CT-2014 07:00:00

Unit test – field emission (FOX detector)

- Fermilab detector (propane-filled ion chamber) designed to be more sensitive to xrays
- Placed at middle of cryomodule
- More analysis needed, correlate with scarecrow





🚰 Fermilab



Unit test – field emission (TLM's)



- TLM = Total Loss Monitor
 - proposed alternate
 detector to Fermilab
 'chipmunk' ion
 chamber
 - ArCO₂ filled heliax
 - length at user discretion
 - 4 installed under CM2
 - 2nd two read out in sum
 - 1 cpm ~ 160
 mrem/hour





Unit test – dark current



08/10/2014

- No response < 20 MV/m
- Greatest response at upstream end



Short term plans



- Operate LLRF in closed loop only limited work on this so far
- Ongoing LFDC investigations
- Cavity 6 coupler temperature can interlock limit be raised (-98 C)?
- Dark current energy spectrum
- Internal radiation detectors
- Long-term (reliability) testing
- Adjust VTO's to lower cavity 6 power, determine peak gradients
- Room temperature thermal cycle
 - repair/replace warm coupler vacuum
 - investigate Q0
 - cryogenics & electrical maintenance



Issues & Lessons



- Reliability ok
 - 3+ days continuous operation at moderate gradient
- Cavity 8 warm coupler vacuum
- Cavity 6 cold window temperature
 - limits high gradient operation to ~ 2 hours
- Radiation detection
 - TLM's
 - Commission & investigate detectors installed within CM-2
- Issues not as numerous as encountered with CM1
 - failed slow tuner
 - failed piezo
 - 3 cavities with 'soft quench' limits



Conclusions & Summary



- This is a team accomplishment
- Thank you and congratulations to our many international partners!







thank you for your attention



Back up slides



20 Presenter | Presentation Title

Cavity 8 warm coupler vacuum



‡ Fermilab