
Large TPC Prototype Field Cage

LCTPC Collaboration Meeting – 01.07.2014 R. Diener, Ole Bach, Bernd Beyer, Volker Prahl

New Fieldcage



- Second version of LP field cage in progress
- This time build in-house
 - To reach needed precision
 - To gain experience (also aimed towards ILD TPC)
- Design changed only marginally







Tests of Materials and Gluing



copper shielding

- Several wall sample pieces:
 - Honeycomb/GRP and honeycomb/Nomex paper
 - Different epoxy glues and thicknesses
 - Vacuum box:



E	Ī	T	П	Π	П	Τ	П	Τ	GRP aramid paper
25 mr									aramid honeycomb
•									GRP high-voltage insulation field shaping bands

Glue	Viscosity [mPa*s]	Hardener	Viscosity [mPa*s]
Spabond 125	2600000	Standard	
Ay 130-1	20.0-35.0	Hy 991	20.0-60.0
Aw106	30.0-50.0	Hy 953	1.9-2.2
Epoxid L	700	Hardener L	320


- Tests of sample pieces
 - Optical inspection of gluing (hollow seams)
 - Layer tear off strength, bending stability
 - HV tests




Sample Piece Tests



- To test mechanical strength of sample pieces a bending tool has been built
- Force is applied by air pressure pump via two rolls onto the piece under test
- Bending measured by micrometer meters








Radiation Length



 For LP - Goal: 1% X₀ per wall, current: ~1.25% X₀
 (or more?: honeycomb not only Nomex but covered with phenolic resin, estimation of glue thicknesses optimistic)



 Possible improvement: replace GRP by Nomex paper

• GRP:
$$X_0 = ~13-15 \text{ cm} \rightarrow 0.4\% X_0$$
 (for 600µm layer)

• Nomex:
$$X_0 = ~30 \text{ cm} \rightarrow 0.1\% X_0$$
 (for 300µm layer)

Mechanical Stability?

• Minimal glue to minimize radiation length (epoxy $X_0 \sim 30\text{-}40\text{cm} \rightarrow \sim 0.03\% \ X_0 / 0.1\text{mm}$)




Radiation Length




- Replace steel inserts and screws in field cage end flange by Torlon
- Save radiation length:
 - Stainless steel: $X_0 = 1-2$ cm
 - Torlon (4301): $X_0 = 28-29$ cm
- Strength tests ongoing
- Outgassing? (not too important since outside gas volume)










Mandrel & Tooling




- Old mandrel not reusable
- New one needs to be designed
- Design not yet finally decided



• Planning for production tools, i.e. gluing station








Space-Frame Endplate (U Cornell)




- Current LP1 endplate
 - Delivers precision but not material budget:
 16.9% X₀ (~2x too large, goal: 8%)
- New LP1.5 space-frame design
 - 7.5% X₀ material budget
 - Same stability
- Has been measured in survey department
- Equipping with termination plates including HV connectors and plugs done ($10M\Omega$ resistors included)
- Missing: gas connectors and HV connectors for 1st/7th strip

 A new holding ring has to be build: current one too wide for new design










Module Mounting Tool



- First real use in February testbeam
 - In general: positive reactions
 - Few things to improve:
 - Horizontal movement range
 - Stability of boom (bending by module weight)
 - Adjustment to space-frame endplate (so far seems possible without too many modifications)
 - Debris?





Debris in LP







