

# *The Joint ANL/FNAL Superconducting Cavity Surface Processing Facility (SCSPF)*

Speaker: Mike Kelly

August 3, 2006





## *Purpose of the SCSPF*

---

- I. Provide ***local (ANL/FNAL) hands-on experience*** with EP/BCP of ILC 9-cell cavities
- II. Substantially expand the existing ANL/ILC-Americas cavity processing capability; EP and/or BCP multiple cavities per week
- III. Focus on **vendors/industrialization**; contribute to R&D if needed

(see “Kephart working group” document; Kephart\_Working\_Group.doc)



## *Scope of Activities*

---

***Single-cavity* chemical processing,  
HPR, clean assembly, (testing?)**

*Not a cryomodule test or assembly area*



# Safety

**FY06: 700 man-hours, \$20 K M&S (>\$100 K Total)**

**June 2006: Completed ANL Physics Division Safety Committee Review for Operations in the ANL portion of the SCSPF; 13 Committee members; 3+ scientists/engineers**

## Subject

- Addendum to ANL/FNAL MOU  
(unsigned)

- Safety Analysis

- Training

- Emergency Procedures

- Hazards Analysis

- HF First Aid

- Ventilation Analysis

**Covering  
ANL &  
FNAL  
operations**

## document

SCSPF\_MOU.doc

SCSPF\_SAR.doc

SCSPF\_Train.doc

SCSPF\_Emerg.doc

SCSPF\_HA.P03.doc

HFfirstAid.ppt, HFfirstAid2.doc

Ventilation, Noise....pdf

- ANL Chem. Procedures

SCSPF\_ANL\_Chem\_Proc.doc


- Checklists (EP, BCP, Parts etch, etc.)

SCSPF\_ANL\_BCPchecklist.doc

# *FY06-07 Program for ANL Portion of SCSPF*

- I. EP+light BCP of six ANL quarter-wave cavities  
**6 weeks in Sept/Oct of 2006**
- II. EP or BCP two prototype spoke cavities for HINS  
**2-3 weeks in FY07**
- III. Construct and commission 9-cell EP system; perform 18 EP procedures  
**9-10 months in FY07**

*FY06-07 Activities:  
ANL Portion of  
SCSPF*





# *FY06-07 ILC SRF Program at ANL*

---

## *Ongoing FY06 activities:*

- ANL-FNAL-GDE MOU, including EP specification
- Engineering design of the physical EP apparatus
- Review design and initiate procurement

## *FY07 activities:*

- Assemble and commission an EP system by the middle of FY07 (0.75 FTE, \$65 K M&S)
- Electropolish ILC cavities in the second half of FY07 (0.75 FTE, **\$110 K for eighteen EP procedures**)
- Design and construction of an HPR system at the joint facility for rinsing after EP (1 FTE, \$200 K M&S)
- Interface with U.S. EP vendors/develop and optimize hardware suitable for large-scale EP (1 FTE)





# *FY08-09 ILC SRF Program at ANL*

---

## *Proposed FY08 activities:*

- **Electropolish 12 ILC cavities** assuming 5 EP procedures/cavity (1.5 FTE, \$225 K M&S)
- Installation of a PLC-based control system for EP (1 FTE, \$75 K)
- Interface with U.S. EP vendors/develop and optimize hardware suitable for large-scale EP (1 FTE)


## *Proposed FY09 activities:*

- **Electropolish 50 ILC cavities** with up to 5 procedures/cavity (4 FTE, \$750 K M&S)
- Operations of an HPR system at the joint facility for rinsing after EP (1 FTE, \$50 K M&S)
- Interface with U.S. EP vendors/develop and optimize hardware suitable for large-scale EP (1 FTE)



# SCSPF Layout

## Location: Argonne Building 208






# ANL/FNAL (New) Shared Infrastructure



**Air Scrubber (\$100 K)**



**DI Water System (\$50 K)**



**Chiller/EP Supply (\$25 K)**



# ***ANL/FNAL Shared antechamber - class 1000***

***(value ~\$100 K)***



# ***ANL Chemistry Room – Oct. 2005***

***(showing multi-use infrastructure for EP/BCP)***



# *Complete Simulation using Water – July 2006*

*ANL ATLAS Upgrade  
Cavities for EP in  
Sept./Oct. 2006*



# *An EP Specification for the ANL Portion of the SCSPF*

4-page document based upon the parameters discussed at the TTC meeting December 5-7, 2005 at Frascati.


## Features

- I. **Horizontal EP**
- II. **Direct Water Cooling of Cavity**
- III. **Cleanable – no sulfur buildup**
- IV. **Aluminum heat exchanger**
- V. **Fast fill/empty**
- VI. **Direct experience for FNAL/ANL personnel**

SPECIFICATIONS  
FOR  
AN ELECTROPOLISHING SYSTEM  
FOR THE ANL/FNAL/GDE COLLABORATION  
IN THE ANL CHEMISTRY ROOM,  
JOINT SUPERCONDUCTING CAVITY SURFACE PROCESSING FACILITY  
BUILDING 208, ROOM B-101  
DATED  
April 6, 2006



# Horizontal EP at the SCSPF: Shown with existing vents/framework



**Working On:**  
**Vertical loading cathode**  
**Direct water cooling**  
**Teflon lip seal for acid seal**  
**Manufactured electrical slip ring for electrical connection**





## *Upcoming Activities*

---

- **August 3-8:** Design review with DESY visitors for EP system in the ANL chemistry area
- **September 25-28:** TTC meeting at KEK; Design review will be arranged with KEK and DESY personnel

