







# LCC report



CLIC SCHEMATIC (not to scale)




ILC SCHEMATIC





# ILC in Linear Collider Collaboration

As of April, 2015





# Key points


The ILC and CLIC accelerator studies are organised under the leadership of the Linear Collider Collaboration with goals:

- Strongly support the Japanese initiative to construct a linear collider as a staged project in Japan
- Prepare CLIC machine and detectors as an option for a future high-energy linear collider at CERN
- Further improve collaboration between CLIC and ILC machine experts
- Beyond the significant progress on the basic RF studies, increased and successful effort on system-studies of various types (FACET, ATF, etc)
- Many common challenges with 3<sup>rd</sup> generation light sources and FELs, the latter providing very important industrial/lab production experiences

Comprehensive physics studies – and in parallel technical detector R&D and concept studies – demonstrate the realism and unique impact of LC e+e- measurements and searches at energy scales from 250 to 3 TeV

The on-going process in Japan for ILC is nevertheless (by some margin) the most central activity right now

# ILC Accelerator in TDR







# Technical Highlights in 2014


- Nano-beam
  - **ATF2**: reached 44 nm at the final focus, closing the primary goal of 37 nm
    - Corresponding to 7 nm at the ILC energy (250 GeV/beam) with the goal of 6 nm
- SRF
  - **EXFEL**: exceeded 50 % ( 400/800) cavity production, and 10 % (10/100 ) cryomodule assembly and test
  - **Fermilab**-ASTA: reached the ILC specification gradient
  - **SLAC**-LCLS: started the project in consortium with the US SRF laboratories
  - **KEK**-STF2: completed CM1+CM2a installation into the beam line
- Accelerator Design and Integration (ADI)
  - **LCC**: processed Post-TDR design update with a model-site assumption
    - Common L\* for both detectors of ILD and SiD
    - Vertical access at Detector Hall at IR points
    - Extension of ML tunnel for optimizing e+e- collision timing and for redundancy of ML SRF cavity gradient integration
  - **LCC**: is continuing to seek for potential cost saving in balance to necessary increase



# Progress in Beam Size at ATF2



Beam Size **44 nm** observed,  
(Goal : **37 nm**  
corresponding to **6 nm** at  
ILC)





# CM2 reached $<31.5 \text{ MV/m}>$ at Fermilab in 2014

CERN Courier December 2014


## ACCELERATORS

### ILC-type cryomodule makes the grade

For the first time, the gradient specification of the International Linear Collider (ILC)

design study of 31.5 MV/m has been achieved on average across an entire ILC-type cryomodule made of ILC-grade cavities. A team at Fermilab reached the milestone in early October. The cryomodule, called CM2, was developed to advance superconducting radio-frequency technology and infrastructure at laboratories in the Americas

region, and was assembled and installed at Fermilab after initial vertical testing of the cavities at Jefferson Lab. The milestone – an achievement for scientists at Fermilab, Jefferson Lab, and their domestic and international partners in superconducting radio-frequency (SRF) technologies – has been nearly a decade in the making, from



CM2 in its home at Fermilab's NML building, as part of the future Advanced Superconducting Test Accelerator. (Image credit: Fermilab.)

Cavity	Gradient (MV/m)
1	31.9
2	30.8
3	31.8
4	31.7
5	31.5
6	31.3
7	31.6
8	31.4

Cryomodule test at Fermilab reached  $< 3.15 >$  MV/m, exceeding ILC specification





# KEK-STF2 is to be a SRF Beam Accelerator Facility

## Objective

- High Gradient (31.5 MV/m)
- => Demonstration of full cryomodule
- Pulse and CW operation (for effective R&D)
- Better efficiency power sources
- SRF electron gun
- Training for next generation s

## Plan:


- Multiple Cryomodule for system study
- In-house Cavity to be installed in cooperation with industry
- Wide range application including Photon Science







# SRF Facilities anticipated for Hub/Consortium



*AMTF @ DESY/E-XFEL, CM*

*STF-CFF @ KEK*

*ASTA @ FNAL, TEDF @ JLab*




# Cryomodule System Tests

## DESY: FLASH

- ❖ 1.25 GeV linac (TESLA-Like tech.)
- ❖ ILC-like bunch trains:
- ❖ 600 ms, **9 mA** beam (2009); ← Demonstrated
- ❖ 800 ms 4.5 mA (2012)
- ❖ RF-cryomodule string with beam → PXFEL1 operational at FLASH



XFEL Prototype at PXFEL1




## KEK: STF/STF2

- ❖ S1-Global: completed (2010)
- ❖ Quantum Beam Accelerator (Inverse Laser Compton): 6.7 mA, **1 ms** ← Demonstrated
- ❖ CM1 test with beam (2014 ~2015)
- ❖ STF-COI: Facility to demonstrate CM assembly/test in near future



S1 Global Cryomodule at STF:




## FNAL: ASTA

- (Advanced Superconducting Test Accelerator)
- ❖ CM1 test complete
  - ❖ CM2 operation (2013)
  - ❖ CM2 with beam (soon)



CM2 at NML Facility:





# FEL and advanced linacs with SCRF modules



Largest deployment of this technology to date

- 100 cryomodules
- 800 cavities
- 17.5 GeV (pulsed)

Kitakami proposed site

TRIUMF FNAL/ANL

SLAC



Cornell  
JLab



LCLS-II

US infrastructure for  
- 35 cryomodules  
- 280 cavities




LAL  
Saclay  
CERN

DESY

IHEP  
PKU

KEKO



Year	Capable Industry
2006	2 ACCEL, ZANON
2011	4 RI, ZANON, AES, MHI
2012	5 RI, ZANON, AES, MHI, Hitachi

Production and  
of ILC components

# ILC Site Candidate Location in Japan: Kitakami

4

Proposed by JHEP community  
 Endorsed by LCC  
 To be authorized by Government

High-way

Oshu

Express-Rail


Ofunato

Ichinoseki

Kesen-numa

IP Region

Sendai






# ILC Global Accelerator Organization

**ILC Director: M. Harrison, Deputies: N. Walker and H. Hayano**

Sub-Group	<u>Global Leader</u> <u>Deputy/Contact p.</u>	Sub-Group	<u>Global Leader</u> <u>Deputy/Contact P.</u>
Acc. Design Integr.	<u>N. Walker (DESY)</u> K. Yokoya(KEK)	SRF	<u>H. Hayano (KEK)</u> C. Ginsburg (Fermi), E. Montesinos (CERN)
Sources (e-, e+)	<u>W. Gai (ANL)</u> M. Kuriki (Hiroshima U.)	RF Power & Cntl	<u>S. Michizono (KEK)</u> TBD (AMs , EU)
Damping Ring	<u>D. Rubin (Cornell)</u> N. Terunuma(KEK)	Cryogenics (incl. HP gas safety)	<u>H. Nakai: KEK</u> T. Peterson (Fermi), D. Delikaris (CERN)
RTML	<u>S. Kuroda (KEK)</u> A. Latina (CERN)	CFS	<u>V. Kuchler (Fermi)</u> , M. Miyahara J. Osborne (CERN),
Main Linac	<u>N. Solyak (Fermi)</u> K. Kubo (KEK)	Radiation Safety	<u>T. Sanami (KEK)</u> S. Roesler (CERN) TBD (Ams,)
BDS	<u>G. White (SLAC)</u> , R. Tomas (Cern), T. Okugi(KEK)	Electrical Support (P. Supply etc.)	TBD
MDI	<u>K. Buesser (DESY)</u> T. Tauchi (KEK)	Mechanical S. (Vac. & others)	TBD

# ILC being studied in Japan





# JFY2014, Commissioned Survey

*- deliverable given in a public report -*

- **Technical/economical benefits from ILC**
  - ILC, General plan and technical features
  - Current, technical status and subjects for further development
  - Prospects for industrial applications and benefits
  - Analysis for economical impacts, base on direct and indirect effects to be expanded ( estimated,  $\sim > 2$  )
- **Scientific prospects and future plans**
  - for particle and nuclear physics, in Europe, north America, and in China
  - Observation and suggestions for ILC, obtained through worldwide visiting and Interviews



# MEXT

contracted with Nomura Research Institute (**NRI**)

- Subjects for survey and analysis:
  - **Technical feasibility** to realize the ILC
    - Regarding components, system design, management, and infrastructure
  - **Technical issues** to prepare for the ILC construction
    - Regarding industrial technology, and necessary time-scale, and prototype works.
    - Cost increase risk
  - **Cost reduction** possibility
    - with technical approaches not described in TDR





# LCC-ILC Progress Report in preparation

*to be useful for further surveys and studies*

- It contains the LCC-ILC technical **progress after TDR**, respecting:
  - *Civil engineering studies*
  - *Accelerator hardware design/development updates*
  - *Accelerator system layout updates for preferred site*
  - *Integration/test facilities to be prepared for “hub-laboratory functioning*
  - *Project Implementation Plan*
  - *Further preparatory work*
- It may be **useful as a reference** document for any survey and/or evaluation on the ILC activities, **updated**.