



INTERNATIONAL LINEAR COLLIDER
SLAC

ILC High Availability Electronics & Controls

DOE Program Review

SLAC June 5-6, 2006

Ray Larsen /for HA R&D Team

Outline

- I. Why High Availability & Why Now?
- II. HA ILC Power Systems Architectures
 - Modulators, Power Supplies, Kickers
- III. Diagnostics Processor
 - Intelligent platform management for Hardware, Software
- IV. HA ILC Controls, Instrumentation Standards
- V. Summary & Conclusion


I. Why HA and Why Now?

Why HA?

- Computer Modeling¹ demonstrates that ILC can achieve only ~20% uptime (Availability) with current subsystem architectures, component reliabilities, c.f. 85% or higher goal.
- Reliability = MTBF; Mean time to repair = MTTR
- Availability one component or subsystem, $A_1 = \text{MTBF}/(\text{MTBF} + \text{MTTR})$
 $\rightarrow 1$ as $\text{MTBF} \rightarrow \infty$ or $\text{MTTR} \rightarrow 0$.
- Availability of system of N components or subsystems $A_N = (A_1)^N$
- For 85% Total Machine Availability N major subsystems, $A_T = 0.85$, all subsystems must have average A_N of $(0.85)^{1/N}$
- For 20 major subsystems, required average $[A_N] = 0.992$
- Strive for $[A_N] > 0.99$ by HA design:
 - Increase MTBF: Use n/N modular failure-tolerant architectures
 - Reduce MTTR: Hot swap failed n/N modules without interrupting operations
 - Accomplish at minimal incremental capital and operating costs

¹*Availism*, T. Himel

I. Why Now?




- Limited Window of Opportunity to advance critical HA designs
- Strong investment in hardware and software R&D over 2-3 years needed to learn how to design, implement effective HA at modest cost.
- Program
 - Apply HA principles to Power, Controls and Instrument Systems
 - Investigate multi-level 1/n redundancy, modular design and hot-swap strategies.
 - Down-select architectures by end FY2009.

II. Power Systems - Marx Modulator

- ❑ 670 10MW RF Stations ~ 12% TPC
- ❑ Modulator Goals: Raise Availability, reduce modulator cost by >50%
- ❑ Demonstrate first prototype in lab at full power in FY06



2m x 2m x 2m Enclosure Air Cooled



- ❑ >MTBF: 3-Level n/N Redundancy
 - +2% RF Stations in overall system
 - 2/14 Mother-boards
 - 1/5 IGBT switch subassemblies
- ❑ <MTTR: Quickly replaceable “Cells”
- ❑ Intelligent Diagnostics
 - Fault management at Main Control
 - Imbedded diagnostics & control in every MBrd
 - Networked by redundant fiber to Main Control


II. Power Systems: DC Magnets

- ❑ Approx. 18,000 magnets & supplies in all systems
- ❑ For $A \sim 0.99$ require modular n/N, Dual Bulk, Dual Controller
- ❑ Improved MTBF magnets, water systems, cable connections etc.
- ❑ FY06-08 Goals: Demonstrate all HA features on multi-unit test system.



Prototype Test n/N Auto-Failover

II. HA Kicker System Goals




- Critical System to support 6 km rings
- 10-20 Modular Units in HA topology
- n/N redundant at Unit, Board levels
- Intelligent Diagnostics
- Auto-failover for boards
- Access for unit hot-swap (while machine running if possible)

- Prototype tested at KEK
- New MOSFET switch designs in process for shorter pulse
- Goal: Full 3 MHz unit in FY07

III. Intelligent Diagnostics Fault Management




- ❑ Apply to all power modular systems
- ❑ Board-level controls & monitoring from MCC
- ❑ Predict, evade faults to improve Availability
- ❑ Report faults to Main Control, Maintenance
- ❑ Goal: Test on Marx in FY06, DCPS in FY07-8



Marx Cell Rear View
DP Mounting

Control Computer

Ground Control Station (16 Ch)




IV. HA Controls & Instrumentation

- Three main goals:
 - High Availability Electronics Systems
 - Modernized platform to support highly integrated instrumentation, processing & communications
 - Standardized approach
- Main Approach: Evaluate Industry Standards
 - Newest HA packaging designs driven by Telecom industry standards consortium
 - Advanced Telecom Computing Architecture (ATCA) designed for crate (“shelf”) level availability of “five nines” (0.99999)
 - These are levels needed to achieve ILC Subsystem goals of 0.99 or better
 - Architecture includes intelligent diagnostics for shelf & system management
 - Marketplace very large, multiple vendors, pricing & support favorable
 - Flexible hardware board, daughtercard (mezzanine) options
- Plans: Evaluate industry standards for controls, instrumentation applications
 - Select most optimum approaches for various applications (in crate, standalone etc.)
 - Down-select major approaches for hardware, software by FY09
 - Needs significant investment of resources to succeed
 - Actively supported by ANL (lead), FNAL, SLAC, DESY, KEK, IUIC, others.

IV. C&I – ATCA Evaluation Kits

**5-Slot Crate w/ Shelf Manager
Fabric Switch
Dual IOC Processors**




4 Hot-Swappable Fans



16 Slot Dual Star Backplane

Shelf Manager




Dual IOC's Fabric Switch

Dual 48VDC Power Interface




Rear View


IV. ATCA Card Options





IV.HA Controls & Instrumentation



- FEATURES**
- ◇ Dual Star 1/N Redundant Backplanes
 - ◇ Redundant Fabric Switches
 - ◇ Dual Star/ Loop/ Mesh Serial Links
 - ◇ Dual Star Serial Links To/From **Level 2** Sector Nodes



- ◆ Dual Network Switch Module Locations
- ◆ Dual Star Fabric Connectors
- ◆ 48V DC Power Plugs
- ◆ Redundant Shelf Manager Cards
- ◆ Fan area



V. Summary

- HA Electronics projects vital to success of ILC.
 - Relatively low capital cost, high impact.
- Goal: Select HA architectural features for all critical systems by FY09.
 - Promising progress on HA design of Marx, DC power supplies (base modules available from several vendors), Kickers, Diagnostics controllers.
- Strong interlab collaboration formed for controls and instrument standards. Results also applicable to detectors.
 - More lab effort needed esp. from SLAC in FY07-09
- Strong industry support developing for ATCA, hardware and software. SLAC is associate member of Industry Consortium
- LCFOA vendors expressing interest in providing developmental modular power systems, ATCA controls systems hardware and software.

V. Conclusions

- HA design efforts are well underway in the ILC
 - Cannot meet up-time goals without it.
 - Full machine goal of $A > 0.85$ requires all subsystems to strive for overall average of > 0.99
 - *Note: Opportunity Cost of idle ILC ~ 135K\$US/hour.*
- New instrument standards based on modern chip technologies needed for next-generation ILC
 - ATCA platform offers ready solution to many controls, instrument applications.
 - Includes intelligent platform management, hot swap that can be leveraged into many other applications for ILC including power systems, utilities etc.
- Increasing levels of C&I support vital to success.