

VFCAL Report

W. Lohmann, DESY

Laser alignment system




Infrastructure for sensor diagnostics

Sensor test facilities

FE design

Labs involved: Cracow UST, Cracow INP,
Prague (AS), Tel Aviv Univ.
DESY (Z.)

Current design (Example LDC, 14 mrad):



Challenges


LumiCal: -control of position on $\sim 10 \mu\text{m}$ level
-control of the inner acceptance radius on $\sim \mu\text{m}$ level

BeamCal: -radiation hard sensors ($\sim 10 \text{ MGy/year}$)


Both: -compact (smallest possible Moliere radius)
-readout after each BX

Laser alignment system

Wojciech Wierba et al., INP Cracow





Two laser beams (one perpendicular, second with 45° angle to the sensor plane) allows to measure XYZ translation in one sensor



Octobre 20 2006

MPI Munich

Results and Status




- New lasers with aspherical lenses - better spot.
- Setup with two lasers - avoid beam splitting
- Compact prototype - in progress (new person involved)
- Reference measurement of XYZ translations - Renishaw industrial system (0.1 μm resolution)
- Stability tests

Infrastructure for Sensor Tests


How can we characterize a sensor?

- I/V measurement with both polarities
- C/V measurement (semiconductor (V_{dep} ?) or insulator?)
- spectrum for MIPs (charge collection efficiency)
- charge collection, leakage current etc. vs. irradiation dose
- ...
- Always check calibration, data integrity, repeatability
- Bookkeeping of data: from files to a data base

Measurement of mip spectra



Octobre 20 2006



MPI Munich

Infrastructure for Sensor Tests

Rooms (Cracow, DESY):

two rooms with filtered air (10k), stabilized temperature

- room 1: bonding and assembly
- room 2: all measurements without radioactive source



Instruments:

- manual prober in a shielded box (light, electrical screening)
- manual prober for probe cards (chip testing)
- microscopes with a large object distance
- manual bonding machine with x-y computer control
- glueing tools, oven etc.
- computer controlled instruments (I, C, V, V and I

Prob Station in TA



Test Beam Equipment



exit window
of beam line

collimator (I_{Coll})

sensor box (I_{Dia} , T_{Dia} , HV)


Faraday cup (I_{FC} , T_{FC})

FE design and studies

H. Henschel, M. Idzik et al.,
Cracow Univ., DESY

Readout board for PHY3 chip with


- control input/output
- level shifters
- biasing switches & networks
- power connector
- 18 FE inputs
- Amplifier



Testmeasurements with Phy3

Sequential Readout



- definite charge of 0.33pC injected into one channel after the other
- readout with (slow) clock, hence considerable decay of captured charge is observed



Future Design



- signal from 4 fC (mip) to 6 pC
- high occupancy - no multiplexing
- DC coupled sensors, C_{det} 20 -120 pf + fanout ($\sim 1\text{pF}/\text{cm}$)
- 300 (150) ns between bunches
- limited power dissipation ($\sim 10\text{ mW}/\text{ch}$)



- Charge sensitive
- test and physics mode variable gain
- test mode: $S/N \sim 10$
- physics mode: > 11 bit
- T_{peak} : 50-70 ns

Plans and Summary

- First prototype submission in 2-3 months
- Testbeam application planned
- More studies on general readout architecture necessary
- Compatibility with mechanics/cooling

First steps are done:

- Test beam equipment partially available and running, completion is ongoing
- Laser alignment 'proof of principle experiment' under construction
- Test facilities for sensors in Zeuthen and Tel Aviv; Zeuthen will be upgraded, Tel Aviv started to collect equipment
- FE electronics development started

Octobre 20 2006

MPI Munich