Transport and Assembly Procedures

Karsten Buesser

ILD Task Force Meetings

LAL 87.11.2016 E-JADE is a Marie Sklodowska-Curie Research and Innovation Staff Exchange (RISE) action, funded by the EU under Horizon2020



1



KITAKAMI Site: Transportation



Slide from Tokiko Onuki

General rule

total weight	trailer/ track	our package	daytime	night	Xpwy	paper work
25 ton	~10 ton	~15 ton	YES	YES	YES	0
44 ton	~20 ton	~24 ton	YES†/ NO	YES	NO	
80 ton	~30 ton	~50 ton	NO	YES	NO	10

[†] Probably "YES", if our package fits into a standard container (W=2,438mm).

Slide from Tomo Sanuki

TESLA Structure

AHCAL Assembly

Kitakami Side





Slide from Karsten Gadow



or anywhere in any detector



AHCAL Assembly

solution: all needed AHCAL parts fit into here



the container fits to standard transport as ships, railways, trucks and through

Slide from Karsten Gadow

t systems
tunnels

AUSSENMASSE			
Längo	mm	6058	
Länge	ft	19' 10 ½"	
Breite	mm	2438	
Dieite	ft	8'	
Höhe		2591	
попе	ft	8' 6"	

GEWICHT		
Tara	kg	2700
Tara	pd	5950
Max. Zuladung	kg	27780
	pd	61250
May Druttagewicht	kg	30480
Max. Bruttogewicht	pd	67200




AHCAL barrel in ILD

it does not matter for the AHCAL barrel where the central yoke and the coil stays, but it must be there, before the AHCAL barrel installation starts

barrel installation starts


Karsten Gadow | ILD Topical Integration Meeting | LAL-Orsay 08.010.2015 | Page 5

Slide from Karsten Gadow





AHCAL barrel integration tools



lifting and turning tool for AHCAL barrel absorber submodules available


- 2 x 18 t capacity
- operation with 2 hooks (z angle adjustment)
- precise motor controlled turning
- design for adaptation for sub-modules with and without sensitive layers started
- mounting, support and insertion frame
 - insertion frame design ready
 - insertion frame support design depends on final yoke size and useable space
- push and pull tool available
 - must be modified to the rail distance and rail shape/size

Karsten Gadow | ILD Topical Integration Meeting | LAL-Orsay 08.010.2015 | Page 8



Slides from Karsten Gadow


AHCAL half barrel absorber installation step 1







AHCAL barrel integration step 2




Karsten Gadow | ILD Topical Integration Meeting | LAL-Orsay 08.010.2015 | Page 9

DÈ

Slide from Karsten Gadow

AHCAL barrel integration step 4








AHCAL tower
book shelf fixation
no frame work needed
requires suitable scaffolding

Karsten Gadow | ILD Topical Integration Meeting | LAL-Orsay 08.010.2015 | Page 11



Slide from Karsten Gadow

AHCAL end cap installation step 15-28





AHCAL assembly in ILD installation scenario

- AHCAL submodules and towers should be already equipped with sensitive layers and pretested anywhere in the world to reduce installation, transportation and storing charges at the installation area
- all AHCAL parts and tools can be transported in standard containers
- the AHCAL assembly can be done at the surface or in the experimental hall
- after transportation to the experimental site, the AHCAL submodules and towers must be tested before the AHCAL barrel and endcap installation, to reduce possible delays due to failures by transportation
- the testing of the sensitive layers and frontend electronics for the AHCAL submodules and AHCAL towers needs a testing and storing place
- laboratory space and infrastructure should be available close to the experimental hall


Slide from Karsten Gadow



Videau Structure




Barrel integration : « Videau's Design » remind








Building in Industry: 40 parts



- Tight continuous weld
- Accuracy and repeatability
- Low distortion
- Filler metal is not required

Technology adapted to larged skin & repeatable structure


Tested with success at CIEMAT (Madrid)



Slide from J.C. lanigro

IPN Lyon





- Module done one by one
- 47 absorbers plates (thickness 15 mm) welded on 2 flanges
 - Weight = 11 t






Wheel Building in **Assembly Hall** : 8 modules x 5


Transport to Assembly Hall with normal truck - ILD area

- Step 1 : Wheel structure transport (8 travels) & assembly
- Step 2 : Modules transport 40 travels with 11 t
- •Step 3 : Modules assembly on the wheel structure with 100 t crane
 - 8 modules in position on specific tool & screwing/welding



Slide from J.C. lanigro

IPN Lyon




ILD Integration



Building Method

•Step 1 : Modules assembly to wheel

- 8 modules in position on specific tool
- welding / screwing and rotation
- Step 2 : Wheel on specific tool
- Step 3 : Special convoy to Assembly Hall



ILD Building

IPN Lyon

Slide from J.C. lanigro

ILD Integration


Page 7






Building Method

- •Step 1 : Modules assembly to wheel
 - 8 modules in position on specific tool
 - welding / screwing and rotation
- Step 2 : Wheel on specific tool
- Step 3 : GRPC insertion and connected
- Step 4 : Special convoy to Assembly Hall with GRPC inside wheels – ready to be connected



ILD Integration

End caps integration : 2 endcaps



IPN Lyon

ILD Integration

Page 12

Slide from J.C. lanigro



Barrel integration : scenarii


Endcap Building : 4 modules x 2

Building Method similar to Barrel, done after the barrel

• Scenario A : Modules transport by normal truck to Assembly Hall, all operations made in the Assembly Hall

• Scenario B : Modules transport by normal truck to Auxiliary Hall, endcap built in the Auxiliary Hall and GRPC insertion in Assembly Hall

• Scenario C : Modules transport by normal truck to Auxiliary Hall, endcap built & GRPC insertion in the Auxiliary, damper convoy to Assembly Hall















Scenarii with idea that Barrel & Endcaps made separatly, one after the other one

- Modules of Barrel & Endcaps made in industry
- Transport of modules to Assembly Hall or Auxiliary building
- 5 Barrels wheels & 2 Endcap-Ring building
- GRPC detectors insertion 1840 for barrel, 1872 for endcaps
- Barrel & Endcaps-Ring insertion with specific tools
- Services connections & efficiency test

Surface needed for operations

- (3712 GRPC have to be brought)
- Zone for barrel on structure storage before linked : 200 m²

Optimistic Time schedule

- Wheel transport & assembly : 1 week by wheel -> 5 weeks for barrel
- GRPC insertion & test : 6 weeks by wheel -> 30 weeks for barrel
- Connecting wheels, test & insertion in Yoke -> 5 weeks for barrel
- Total time for Barrel = 40 weeks
- Approximately same time for both Endcaps-Ring
- That means a SdHCAL integration time of :
 - Scenario A : 80 weeks in assembly Hall

Slide from J.C. lanigro

IPN Lyon

1200 m² for assembly of modules, specific structures, Services & GRPC detectors storage

Scenario B : 10 weeks in Auxiliary building & 70 weeks in Assembly Hall Scenario C : 70 weeks in Auxiliary building & 10 weeks in Assembly Hall

Assembly Study

- Try to optimise the ILD assembly in a possible Kitakami scenario
- Biggest uncertainty:
 - where and how to build the coil
- A combined effort between subdetectors, CFS group, ILD integration team is required to come up with a realistic assembly scenario for ILD
- Where can we do what?
 - at vendours/home institutes
 - at central lab campus
 - at IP campus
- This is cost relevant!

Integration Proposal > YB-: production + assembly

> HCAL production for endcaps




One production lane for about 6 months (12 modules)

In parallel: solenoid assembly

In parallel: finalisation of muon installation in YE+ and begin muon installation in YB0 (120 days)

Mounting YE- HCAL

Start YB- yoke assembly once YE-HCAL is ready or assemble YB- wheel in garage



Slide from Thomas Schörner-Sadenius



Conclusion

- We have detailed assembly plans for both structure versions
- Steel modules in both options can be transported to Kitakami on existing roads
- Rings for both options need to be assembled in or close by the IP region
 - T-rings need to be assembled in front of the central barrel yoke ring.
 - V-rings can be assembled close by, but require dedicated O(100t) transport possibility to the detector
- Details depend on the exact location and layout of the IP campus
- At this time it is probably safe to assume that either option could be made to work w.r.t. assembly and transportation boundary conditions in Kitakami (or elsewhere)





