


TESLA-Structure: Signal Paths and Electronics Accessibility/Reliability





Katja Krüger (DESY)
ILD Technical Task Forces Meeting
Orsay
8. November 2016

- > reliability of components studied in testbeams
 - principle of scintillator read out by SiPM demonstrated with physics prototype
 - operated successfully 2006-2011, several transports to testbeams at CERN, FNAL
- > high-granularity HCAL is not sensitive to a few dead channels
 - resolution observed in beam tests (~5 % dead channels in physics prototype) compatible with ILD simulation (no dead channels)
- > all components that could affect a large fraction of the detector are easily reachable and replaceable


Signal Paths in TESLA geometry

- signals are aggregated in stages
- central electronics components at the end face of the barrel, easily reachable



Components & Effects


- > LDA
 - two barrel sectors (~250000 channels) missing
- > interface boards (DIF, POWER, CALIB)
 - all channels in the layer (~2500 channels) missing
- > flexlead connector HBU ↔ HBU
 - all further HBUs in the slab missing
- > SPIROC ASIC
 - 36 channels missing
- > SiPM
 - single channel missing



Components & Effects & Repairs

> LDA


- two barrel sectors (~250000 channels) missing
- repair very urgent
- procedure to repair:
 - open detector ~1m
 - un-cable sector
 - replace LDA
 - re-cable & close
 - takes probably ~1-2 days



Components & Effects & Repairs

> interface board


- all channels in the layer (~2500 channels) missing
- **repair urgent**
- boards connected to layer purely passive, so failure improbable
- active boards easily replaceable:
 - open detector ~1m
 - replace board
 - close
 - takes probably ~1 day (opening of the detector)



Components & Effects & Repairs


> interface board

- all channels in the layer (~2500 channels) missing
- **repair urgent**
- boards connected to layer purely passive, so failure improbable
- active boards easily replaceable:
 - open detector ~1m
 - replace board
 - close
 - takes probably ~1 day (opening of the detector)



Components & Effects & Repairs


- flexlead connector HBU ↔ HBU
 - all further HBUs in the slab missing
 - experience from testbeam: flexleads sometimes difficult to connect, but once connected connection stays fixed
 - in final detector: add glue or similar
 - procedure to repair:
 - open detector wide
 - un-cable sector
 - pull out layer
 - replace connector
 - re-cable & close
 - takes probably a few days



Components & Effects & Repairs

> SPIROC ASIC


- 36 channels missing
- **not urgent to repair**
- **procedure to repair:**
 - open detector wide
 - un-cable sector
 - pull out layer
 - replace HBU
 - re-cable & close
 - takes probably a few days



Components & Effects & Repairs

> SiPM

- single channel missing
- **not necessary to repair**



- > no reliability problems observed in testbeams
- > TESLA structure allows easy access to all components that might affect a significant fraction of the detector
 - affecting a full layer or more: LDA and interface boards replaceable within 1-2 days
 - affecting a fraction of a layer: replacement possible during a (few days long) shutdown