Safety at the European XFEL

Selected items from a non-expert

Thomas Schörner-Sadenius KEK, 16 May 2017



European





Outline

Deutsches Elektronen-Synchrotron DESY

Germany Electron Synchrotron

The European XFEL – Introduction

Legal Basis for XFEL Safety

Main Safety Issues

- Access control and tracking
- Fire protection
- Communication
- •

nations per year

Mission:

- Development, construction, operation and scientific exploitation of accelerators
- Provide access and services for national and international users
- Exploration of Matter 16 May 2017

Deutsches Elektronen-Synchrotron DESY

Founded 1959

In a nutshell:

- Research centre of the Helmholtz Association, Germany's largest science organisation with ~30000 staff and ~3 billion EUR budget
- Two DESY sites (Hamburg, Zeuthen)
- 220 MEUR budget, 2300 staff
- > 3000 visiting scientists from 45







Deutsches Elektronen-Synchrotron DESY















Some facts:

- Overall length 3.4 km; superconducting linac (ILC technology) for 2.1 km
- Tunnel between 6 and 38 m underground
- Energy 17.5 GeV
- Cooled with helium to -271°C.
- Commissioning about to end (first light on 3 May).
 16 May 2017
 TSS: European XFEL Safety







A prime light source

A 10% prototype of the ILC

- Industrial production of 800 SCRF cavities
- Accelerating gradients close to ILC specs









European





XFEL Safety – Legal Basis



Procedures: plan approval process ("Planfeststellungsverfahren") Advantages:

- key planning tool including most legal requirements
- One authority to deal with only.

Disadvantage:

- Restricted flexibility in later project phases ("Planänderungen")
- XFEL: Plan fixed 2005, construction begin 2009, infrastructure after 2012

Planfeststellungsbeschluss

374 pages for procedures ... and tons of paper to detail all steps.



Landesamt für Bergbau, Energie und Geologie

in Clausthal-Zellerfeld

als Planfeststellungsbehörde

Planfeststellungsbeschluss

vom 20. Juli 2006

W 9108 PVF - IV - 2006/199

für den Bau und Betrieb des Röntgenlasers XFEL

einschließlich der für seinen Betrieb notwendigen

Anlagen und Gebäude

des Deutschen Elektronen-Synchrotron DESY Hamburg

Complications for Safety and Coordination

Two entities involved:

- DESY and XFEL company
- Required very clear management of responsibilities in all periods of construction, installation, commissioning



Two states and even more communities involved:

- States of Hamburg and Schleswig-Holstein
- Significant differences in technical equipment / standards, in command lines and in strategies, e.g. in fire brigging conventions, radio frequencies etc.

At least three stages of XFE construction in time, overlapping in space, with different safety requirements

- XFEL CFS pure construction
- Installation of components
- Commissioning (and later operation)

→ one person per time per construction unit in charge of safety, bundling all responsibility and knowledge / intermation; frequent changes.

→ Safety as a moving target with enormous coordination needs.

Basis for Safety and Coordination

Stand: 08.04.2005

Planfeststellungsbeschluss points (in one sentence) to external document (55 pages) provided by company ("STUVA"):

- Details all issues to be dealt with (except for mining law – done in Beschluss)
- If requirements of this document fulfilled, then safety assumed.
- Advantage: Changes to safety simpler than changes to plan!

Sicherheits- und Arbeitsschutzkonzept für die Errichtung, die Installation und den Betrieb der Forschungsanlage XFEL (Stand: 08.04.2005) Aufgestellt durch: STUMA STUVA e.V. Mathias-Brüggen-Str. 41 50827 Köln Tel.: +49-221-59795-0 Fax: +49-221-59795-50

Seite 1 von 55

Basis for Safety and Coordination

- Bauwerk mit Feuerwiderstandsklasse mindestens F 90 (entspricht der Forderung der IndBauRL f
 ür Untergeschosse)
- Feste Brandabschnittstrennung zu den Schächten bzw. zur Experimentierhalle
- Brand- und Rauchabschnittsbildung durch querschnittsübergreifende feste Abschottung bzw. eine feste Abschottung in Kombination mit einem dreifachen Wasservorhang im Durchgangsbereich alle 600 m (oder im Abstand eines Vielfachen von 150 m, d. h. eines Kryo-Abschnittes im XTL, in Sonderfällen bei geringer Brandlast in den XTDs max. 700m)
- Wassernebellöschanlage für Öltrafos
- Inertgaslöschanlage in allen Mess- und Steuerschränken
- Brandfrühsterkennung, Brandortung
- Entrauchung in allen Tunneln
- Auslegung der Entrauchungsanlagen in den Tunneln auf die Rauchentwicklung in der Selbstrettungsphase. Dieser Ansatz bietet bezogen auf die längste Fluchtzeit von 7 min (vergl. Kap. 4.4.2.1) eine ausreichende Sicherheitsreserve.
- Generelles Mitführen von Selbstrettern (mindestens 30 Minuten Haltezeit) f
 ür alle Mitarbeiter in allen Tunneln
- Fluchtwegkennzeichnung / Notfall-Informationssystem (akustisch / optisch) eignisabhängig
- Ersatzstromversorgung f
 ür Sicherheits- und Brandmeldetechnik (L
 üftungs gen, Notbeleuchtung, Fluchtwegkennzeichnung), Funktionserhalt E90
- lang nachleuchtende Fluchtwegmarkierung
- Sicherheits- bzw. Notbeleuchtung
- Flucht- und Rettungswege
- Abschluss zu den Schachtbauwerken bzw. der Experimentierhalle mit T30-Tü
- Zugangskontrollsystem / Vereinzelung
- Kommunikationsstellen / Nottelefon mindestens alle 50 m
- Installation von Antennen und Antennenanlagen für Kommunikationszwecke (Funk, Mobiltelefon, Feuerwehrfunk)
- Handlauf in ca. 1,10 m Höhe über dem Fluchtweg
- Feuerlöschleitung nass (Brauchwasserleitung) mit Abgängen mindestens alle 50m

- Auslegung der Beschleunigeraufhängung unter Beachtung einer eventuellen Brandbeanspruchung
- Mobile Krankentrage mit Fahrgestell, die an Hindernissen vorbei getragen werden kann, für die Rettung von Verletzten
- Absolutes Rauchverbot während Bau, Inbetriebnahme, Wartung und im Betrieb

- Für alle Heißarbeiten ist ein Schweißerlaubnisschein mit zugehörigen Sicherheitsregeln zwingend erforderlich. Ein Schweißverfahren mit größtmöglicher Sicherheit gegen Brandentstehung (z.B. Orbital- oder Schutzgasschweißen) ist zu wählen.
- Brennbare Materialien wie z.B. Verpackungsmaterial d
 ürfen zu keinem Zeitpunkt im Tunnel gelagert werden. Dies gilt insbesondere auch f
 ür die Ausr
 üstungsphase.
- Die Transporteinheit ist zusätzlich an beiden Enden der Transportfahrzeuge mit Scheinwerfern auszustatten, die Fluchtwegeinengungen ausleuchten.
- Die Transporteinheit wird zusätzlich mit einem nach unten verschwenkter Handlauf als Leiteinrichtungen versehen, um Personen auch bei erschwerten Sichtbedingungen (Rauch) auf die geringere Höhe des Fluchtwegs im Bereich der Transporteinheit aufmerksam zu machen.

Main Safety Issues at XFEL

Access control and person tracking system

Communication systems

- Permanently installed tunnel telephone
- Mobile phones
- Radio communication

Fire protection / extinguishing systems

- T,p sensors and smoke detectors in all elements of the tunnel
- Also in all switch cabinets (also have own extinguishing means)
- Separation of different tunnel sections with walls with doors or with high-pressure water curtains.

Helium detection and protection

Gas analysers, smoke detectors, ISOVAC ...

All done with very much redundancy.

Access Control and Tracking

Elements

- Singling units
- Authentication
- Authorisation
- Tracking (far-field transponders)
- Different systems thinkable.

Position and direction of all fleeing persons must be known at all times – legal requirement!

akti∨er Transponder

Visualisation of people underground







TSS: European XFEL Safety

Communication in the Tunnel





0

Fire Protection - Examples

Emergency vehicles to reduce intervention time



concept drawing for procurement



vehicle on duty

Fire Protection - Examples

High-pressure water curtains as separation of fire compartments

Installation phase

operating phase



Fire Protection - Examples

Extinguishing water pipes during in different phases





test setup in mockup-tunnel

16 May 2017

"Hen-Egg" Problem

Example: Water has to be provided without interruption – even in case of re-furbishments and major construction steps in the tunnel etc.

- Same applies for communication, power, sensors, tracking, etc. all need to be maintained and adapted to changing conditions.
- Requires a lot of improvisation and communication
- Rule of thumb: Alterations lead to cost increase by 100 %!
- Required: very detailed cable and piping management

Proven very useful at DESY

- Mock-up tunnel
- Also useful to test tunnel transportation system and other elements

