

Requirements from ILD

Karsten Buesser

Mini-Workshop on ILC Infrastructure and CFS for Physics and Detectors
16.05.2017


E-JADE is a Marie Skłodowska-Curie Research
and Innovation Staff Exchange (RISE) action,
funded by the EU under Horizon2020



IP Campus Planning

Surface ground Buildings and facilities

- Need to know more about the new proposed IP site
- NDA between KEK and DESY is being negotiated right now
- Hope to have it soon





KITAKAMI Site: Transportation

Slide from Tokiko Onuki



Manpower at IP Campus

- ILD and SiD have estimated number of FTEs working at the IP Campus (under and above ground)
- In peak detector installation times, we expect ~150 FTE at the IP campus
- During operation years, we still expect 50-60 FTE
- ~300 FTE at Central Lab Campus in peak times
- How reliable are these numbers?
- They clearly depend on the assumptions for the detector assembly models



ILD Assembly (selected examples)

AHCAL Assembly

Kitakami Side



or anywhere in any detector

AHCAL Assembly

solution: all needed AHCAL parts fit into here




**the container fits to standard transport systems
as ships, railways, trucks and through tunnels.....**

AUSSENMASSE		
Länge	mm	6058
	ft	19' 10 ½"
Breite	mm	2438
	ft	8'
Höhe	mm	2591
	ft	8' 6"

GEWICHT		
Tara	kg	2700
	pd	5950
Max. Zuladung	kg	27780
	pd	61250
Max. Bruttogewicht	kg	30480
	pd	67200



AHCAL barrel integration tools




- lifting and turning tool for AHCAL barrel absorber submodules available
 - 2 x 18 t capacity
 - operation with 2 hooks (z angle adjustment)
 - precise motor controlled turning
 - design for adaptation for sub-modules with and without sensitive layers started
- mounting, support and insertion frame
 - insertion frame design ready
 - insertion frame support design depends on final yoke size and useable space
- push and pull tool available
 - must be modified to the rail distance and rail shape/size

Karsten Gadow | ILD Topical Integration Meeting | LAL-Orsay 08.010.2015 | Page 8



AHCAL half barrel absorber installation step 1



Karsten Gadow | ILD Topical Integration Meeting | LAL-Orsay 08.010.2015 | Page 7








Wheel Building in **Assembly Hall** : 8 modules x 5

Transport to Assembly Hall with normal truck - ILD area

- **Step 1** : Wheel structure transport (8 travels) & assembly
- **Step 2** : Modules transport 40 travels with 11 t
- **Step 3** : Modules assembly on the wheel structure with **100 t crane**
 - **8 modules in position on specific tool & screwing/welding**






Wheel assembly in Auxiliary building :

Building Method

- **Step 1 : Modules assembly to wheel**
 - 8 modules in position on specific tool
 - welding / screwing and rotation
- **Step 2 : Wheel on specific tool**
- **Step 3 : Special convoy to Assembly Hall**






Wheel assembly in Auxiliary building : 8 modules => 5 wheels


Building Method

- **Step 1 : Modules assembly to wheel**
 - 8 modules in position on specific tool
 - welding / screwing and rotation
- **Step 2 : Wheel on specific tool**
- **Step 3 : GRPC insertion and connected**
- **Step 4 : Special convoy to Assembly Hall with GRPC inside wheels – ready to be connected**



Slide from J.C. Ianigro


Present Design



- Overall yoke dimensions
- > Radius 15.5m
 - > Length 13.2m
 - > Barrel weight 6900t
 - > End-cap weight 6500t
- total 13400t


Assembly scenario

- There are three options




ILD Subdetector Requirements

- Requirements from ILD sub-detectors have been assembled some time ago (02/2016):
 - need to be re-visited
 - in a more formal process



ILD Subdetector Requirements



T. Sanuki, T. Onuki

ILD Interface Documents

Proposal of an Interface Control Document (ICD):

Purpose of this document is:

- To know and record technical details of each subdetector
- To understand the consequences at the interfaces (gap, fixations, weight,)
- Follow up of different progress
-

One document by sub detector

Enter all technical details you know today (dimensions, weight, attachment points, center of gravity, positioning constraints, services, power consumption, thermal dissipation, integration specifications,)

Items may be missing (Please help actively to improve the document)

Each ICD will evolve during the phase of study.

They are not casted in stone yet

- ICD will become backbone of ILD Engineering Design study!!!
- Status will be monitored at ILD (Integration) meetings



R. Poeschl
H. Videau

Document on ILD Conventions and rules

international linear collider	ILD conventions and rules Template	Ref.: 77777 Ed.: 0 Rev.: 3 Date: 21/10/16	Page : 1/8
-------------------------------	---------------------------------------	--	------------

ILD conventions and rules

ILD

Prepared by	Signature	Accepted by	Signature
Roman Pöschl			

Approved by	Function	Date	Signature

Summary	
Annexes	

Document Change Record				
Edition	Revision	Date	Modified pages	Observations
0	1	21/10/16	all	Creation

Distribution See Distribution list at the end of this document

Template V1.0

Actual ICD

international linear collider	Interface Control Document Template	Ref.: Ed.: 1 Rev.: 0 Date:	Page : 1/9
-------------------------------	--	-------------------------------------	------------

Interface Control Document Template

XXXXXXXX (Sub detector name)

Prepared by	Signature	Accepted by	Signature

Approved by	Function	Date	Signature

Summary	
Annexes	

Document Change Record				
Edition	Revision	Date	Modified pages	Observations
1	0			

Distribution See Distribution list at the end of this document

Template V1.0

Technical Design Document of subdetector

international linear collider	Interface Control Document Template	Ref.: 77777 Ed.: 0 Rev.: 3 Date: 22/8/16	Page : 1/34
-------------------------------	--	---	-------------

Technical Design Document

SiEcal

Prepared by	Signature	Accepted by	Signature
Marc Anduze Henri Videau			

Approved by	Function	Date	Signature

Summary	
Annexes	

Document Change Record				
Edition	Revision	Date	Modified pages	Observations
0	1	7/10/16	all	Creation

Distribution See Distribution list at the end of this document

Template V1.0

Obligatory document:
Author: Central Integration Group

Obligatory document
Author: Subdetector group

Optional document
(Highly recommended)
Author: Subdetector group
-> See talks by Henri and Marc

R. Poeschl

Convention and Rules Document

Conventions and Rules

- Central Design and Integration group: KB, R. Poeschl, T. Tauchi
- V0.1 on EDMS:

	ILD conventions and rules Template	Ref. : ?????	Page : 1/8
		Ed. : 0 Rev. : 3 Date: 21/10/16	

	ILD conventions and rules Template	Ref. : ?????	Page : 2/8
		Ed. : 0 Rev. : 3 Date: 21/10/16	

- Table of Contents -

ILD conventions and rules

ILD

Prepared by	Signature	Accepted by	Signature
Roman Pöschl			

Approved by	Function	Date	Signature

Summary	
Annexes	

Document Change Record				
Edition	Revision	Date	Modified pages	Observations
0	1	21/10/16	all	Creation

Distribution	See Distribution list at the end of this document
--------------	---

1. LIST OF ACTIONS	2
2. INTRODUCTION	3
2.1. SCOPE OF THE DOCUMENT	3
2.2. APPLICABLE DOCUMENTS (AD)	3
2.3. REFERENCE DOCUMENTS (RD)	3
2.4. LIST OF ABBREVIATIONS	3
2.5. NOMENCLATURE	4
3. GLOBAL CONVENTIONS OF ILD.....	5
3.1. UNIT CONVENTIONS.....	5
3.2. DEFINITION OF THE ILD REFERENCE FRAME.....	5
3.3. NAMING AND NUMBERING CONVENTIONS.....	5
3.4. CABLE AND SERVICES PATH	6
3.5. DETECTOR CABLING SCHEME	6
Principles	6

1. LIST OF ACTIONS

- Unit conventions
- Coordinate system
- Naming and numbering conventions
- Services
- Local regulations (T. Tauchi):
 - Electrical Appliance and Material Safety Law
 - Fire Service Act
 - High pressure gas safety law
 - Act on Prevention of Radiation Damage by Radioisotope
 - Building Standards Law
 - Corresponding rules at KEK...

3. GLOBAL CONVENTIONS OF ILD

This document constitutes a reference for every document concerning design, construction, assembly of any part of ILD.

3.1. Unit conventions

All the dimensions are given in mm.

3.2. Definition of the ILD reference frame

The origin of the frame is the centre of the interaction region.

We consider that at the interaction point the plane containing both beams is the horizontal plane. This is not trivial considering that the beams are at angle with the magnetic field and have traversed, before the detector, a compensation solenoid. This definition should be inherited from the accelerator. TO BE handled by MDI group

The normal to this plane (vertical) is O_y . Calling P_{e^-} the mean momentum of the electrons and P_{e^+} the mean momentum of the positrons, O_z is proportional to $P_{e^-} - P_{e^+}$. It is close to P_{e^-} with an angle of 7mrad, the two momenta being equal in modulus and their angle being 14 mrad. O_x is deduced to make a right-handed frame.

The centre of the detector is the frame origin, its axis is O_z .

The global shape of ILD is cylindrical. The central part is called "barrel", the barrel is closed on each side by an end cap presenting disk shapes. The two end caps are called "end cap $z>0$ " and "end cap $z<0$ " with obvious definitions. This distinction is not valid for the inner detector part of the detector inside the TPC radius.




Figure 1. Schematic drawing of the detector barrel.




Figure 2. Schematic drawing exhibiting the two end caps of the detector

3.3. Naming and numbering conventions

Numbering definitions and scheme for ILD. The numbering of pieces goes with z for longitudinal structures, it goes with the azimuthal angle in the transverse dimensions. It starts at zero in such a way that multiplied by the angular span of the pieces one gets the angle of the pieces.

3.4. Cable and services path

from the Note on the integration of the ILD detector by C. Clerc and M. Joré

3.5. Detector cabling scheme

Principles

Two main constraints have driven our study:

- Allow maintenance with the minimum of cable disconnections.
- Minimise the number of cables and services in the way of particles

Thus, we propose the following cabling scheme (see figure 3.1.1.1):

- Inner and forward detectors cables/services along the beam
- Barrel detectors cables/services along the coil cryostat and between central and outer rings of barrel yoke. The cable might be distributed in chimneys. This is to be studied completely.
- Endcap detectors cables/services between barrel yoke and Endcap.




FIGURE 3.1.1.1 Cabling scheme

The inner and forward cables, in green in the figure above, will be routed along the pillar and after to the cable chains. The others cables will be routed to a patch panel connected to the cables chains.

The most delicate issue of this solution lies in the Lumical region. The cables coming from the inner part must find their way out along the Ecal ring, Lumical and support tube, but should not prevent the opening of the endcap. That last point implies a possibility of disconnection. Thus, a quick disconnection device, like a patch panel, is mandatory in this region. NOT TRIVIAL.

Interface Control Documents

	Interface Control Document Template	Ref. : Ed. : 1 Rev. : 0 Date:	Page : 2/9
--	--	--	------------

	Interface Control Document Template	Ref. : Ed. : 1 Rev. : 0 Date:	Page : 1/9
--	--	--	------------

- Table of Contents -

1. INTRODUCTION	3
1.1. SCOPE OF THE DOCUMENT	3
1.2. APPLICABLE DOCUMENTS (AD)	3
1.3. REFERENCE DOCUMENTS (RD)	3
1.4. DETAILS OF CHANGE TO THE PREVIOUS DESIGN	3
1.5. LIST OF ABBREVIATIONS	3
1.6. LIST AND NOMENCLATURE OF MAJOR PARTS	4
2. GENERAL INTERFACE DESCRIPTION	5
3. MECHANICAL INTERFACE	5
3.1. COORDINATE SYSTEM	5
3.2. MECHANICAL CONCEPT	5
3.3. CRITICAL DIMENSIONS	5
3.4. WEIGHTS	5
3.5. POSITIONING AND ALIGNMENT CONSTRAINS	5
4. ELECTRICAL INTERFACE	5
4.1. BLOCK DIAGRAM	5
4.2. CONNECTION DIAGRAM	5
4.3. LIST OF CONNECTORS	6
4.4. CABLING AND CONNECTING SHEETS	6
4.5. ELECTRICAL CIRCUIT OF THE GROUNDING	6
4.6. POWER CONSUMPTION	6
4.7. OTHER ELECTRICAL INTERFACES	6
5. FLUID INTERFACE (IF NEEDED)	6
5.1. GAS SYSTEM INTERFACE	7
5.2. LIQUID SYSTEM INTERFACE	7
6. THERMAL INTERFACE (IF NEEDED)	7
7. TEST INTERFACES	7

Interface Control Document Template

XXXXXXXX (Sub detector name)

Prepared by	Signature	Accepted by	Signature

Approved by	Function	Date	Signature

Summary	
Annexes	

Document Change Record				
Edition	Revision	Date	Modified pages	Observations
1	0			

Distribution	See Distribution list at the end of this document
--------------	---

Template V1.0

R. Poeschl
H. Videau

Template sent to ILD Subdetector groups before Xmass 2016

- Plan to distribute ICD to ILD by end of July 2016 , i.e. Before the summer break
- R.P. Preferred to went through the excercise for Si Ecal
Effort was joined and then lead by Henri Videau
- Regular Meetings and discussions since
- It turned out that a lot of conventions have to be reviewed (or being reminded)
=> e.g. creation of a table on nomenclatures

R. Poeschl
H. Videau

1.5. Nomenclature


Nomenclature			
Module	Module	Overlap	Distance in z between barrel and end cap
Stave	Set of 5 modules covering an octant of the barrel	Overshoot	Amount by which the end cap outer radius exceeds the barrel outer radius.
Slab	Tungsten slab sandwiched between two detecting structures, to be slit in the stave.	Alveoli layers	
Alveolus	Hole in the module structure to contain a slab	Alveoli columns	

Looks trivial but is very useful

Example: SiECAL

- **Until further notice reference for ICD is DBD**
- However, unavoidable changes can be taken into account
e.g. SiECal Barrel Module


R. Poeschl
H. Videau




- Keep changes w.r.t. DBD ALARA (As Low As Reasonable Achievable)
 - Document them clearly
- **How to deal with modified L***

Drawings by
M. Anduze

SiEcal Barrel Module with rails



Fastening of SiEcal Module to Hcal




R. Poeschl
H. Videau

(Here) ICD should give information about

- distance between rails
=> Constraints on positions of female rails -> see talk by Marc
- Should not give information on e.g. the design of the alveolar layers

Example: SiECAL



SiECal external components i.e. Relevant for ICD

- SiECal Hub 1
(hub to external supplies and DAQ)
- Rails (connection to Hcal)

SiECal internal components i.e. Relevant for TDD


- Cooling pipes,
- SiECal Hub2 (internal hub)
- Slab columns

... as long as they don't exceed the space between ECal and HCal or influence detectors in another way (heat, interspersed noise, etc.)

R. Poeschl
H. Videau

Disclaimer: Design subject to change

Example: SiECAL



Example: SiECAL

R. Poeschl
H. Videau

In electronic trailer:

- LV: One power supply type stave/quadrant
- HV: One power supply type stave/quadrant
- DAQ farm: 1 computer stave/quadrant for acquisition
- Slow control: One slow control computer
- One clock source


All mistakes are mine !!!

- We hope to get a more reliable picture about the requirements and interfaces for the ILD sub-detectors via a formal process using Interface Control Documents
- This process will converge only slowly, as a lot of the information is not available at this stage:
 - R&D for detectors and electronics proceeds
 - Understanding the dependencies between the sub-detectors and the outer world is difficult and depends on many details
- Nevertheless, we hope to have a first - incomplete and maybe inconsistent - picture before the end of this year
- The output of this process should also be a better picture of all interfaces that ILD has with the outer world:
 - Experimental areas - surface and underground
 - IP campus
 - Main campus

Interface to the Environment



SiEcal Cooling System – Very schematic view



R. Poeschl
H. Videau

Concept by
D. Grondin

Where to locate such a cooling plant?


Other examples:

- Gas supply systems
- Electronic trailer


Example: SiECAL

Push-pull System


- ILD lives on a moving platform
 - In symbiosis with SiD and the machine...
- Where to put the external services?
- First, we need the sub-detector requirements!



Detector Hall and two Vertical Shafts




Overall Facilities of the DH Region



Access Shafts

- 18 m main shaft for detector installation
 - plus some services
- 10 m shaft for
 - elevators
 - stairs
 - power, cooling, air conditioning, gas supplies, (...)
- We need to know how much of this is required by ILD!

Two Vertical Shafts



Main shaft D=18m

- Center of DH
- Detectors Installation by Gantry Crane

Utility shaft D=10m

- Utility lines: Pipes, ducts, cables
- Personnel access to Detector Hall by Elevator and Stairs

Masanobu Miyahara

ILD Requirements for Experimental Hall




B. List,
T. Tauchi,
KB

1	Requirements for the ILC Detector Hall							
2	Title	Description	Rationale	Numerical Value	Justification	Building	Area	Tr
3								
4	Magnetic Stray Field	The magnetic stray field at the IP caused by a detector in parking position must be less than	use of iron-based tools	50G	CMS experience, measurements at DESY	DH	Operation	De
5	Magnetic Stray Field	The magnetic stray field around the detector must be less than	functioning of detector near electronics and equipment	2000G	unclear	DH	Safety	De
6	Beam Height	The beam height above the IR floor must be	detector diameter	9m	ILD and SiD design in DBD	DH	Operation	Ci
7	DH crane operation	It must be possible to operate a crane in the DH for ILD and SiD independently	decouple installation schedule			DH	Operation	
8	DH crane combination	For heavy loads, it should be possible to couple both DH cranes	assuming individual crane capacity is less than maximum required load			DH	Operation	
9	DH crane coverage	The DH crane must cover a region of size ... In the DH in single / coupled operation	Underground installation work	S25m xH35m	footprint of detector, platforms and pacman assembly space	DH	Operation	
10	DH Crane hook height	The main hall crane must have a hook height of at least	Underground installation work	20.5m	needs to be checked	DH	Operation	
11	DH Crane hook height	The main hall crane must have a hook height of at least	Underground installation work	20.5m	needs to be checked	DH	Operation	
12	DH Crane hook height	The main hall crane must have a hook height of at least	Underground installation work	5m above detector	needs to be checked	DH	Operation	
13	DH Crane hook height	The main hall crane must have a hook height of at least	Underground installation work	5m above detector	needs to be checked	DH	Operation	
14	DH Crane capacity	The DH crane must be able to move a mass of (single / coupled operation)	Underground installation work	(250t + 80t)x2		DH	Operation	
15	DH Crane capacity	The DH crane must be able to move a mass of	Underground installation work	40t x 2	does this cover the pacman load?	DH	Operation	
16	AH Crane capacity	The Assembly hall crane must be able to move a mass of	Surface assembly work	250t	Yoke iron segments	AH	Operation	
17	AH Crane capacity	The Assembly hall crane must be able to move a mass of	Surface assembly work	(250t + 80t)x2	coil modules	AH		
18								
19	ILD platform width	The movable platform for ILD must have width	Push-pull operations	20m	detector and ancillaries sizes	DH	Operation	
20	ILD platform length	The movable platform for ILD must have length	Push-pull operations	20m	detector and ancillaries sizes	DH	Operation	
21	ILD platform thickness	The movable platform for ILD must have thickness	Push-pull operations	2.2m	ARUP studies	DH	Operation	
22	SiD platform width	The movable platform for SiD must have width	Push-pull operations	20m	detector and ancillaries sizes	DH	Operation	
23	SiD platform length	The movable platform for SiD must have length	Push-pull operations	20m	detector and ancillaries sizes	DH	Operation	
24	SiD platform thickness	The movable platform for SiD must have thickness	Push-pull operations	> 2.2m	ARUP studies plus difference in detector height	DH	Operation	
25	Radiation level	The radiation level during accelerator operation at the detector outside must be at most	DH access while beam is on	0.2 (0.5) uSv/h	KEK(SLAC-GERT) requirement	DH	Safety, Legal	
26	Radiation dose for beam loss incident	The radiation dose for the maximum credible beam loss incident at any position outside the shielding wall must be at most	DH access while beam is on	250 mSv/h, 30mSv integrated per incident	SLAC requirement	DH	Safety, Legal	

It's on EDMS/Confluence!

- ILD Interface Documents and list with requirements for experimental hall are on EDMS and ILD Confluence
- Links from ILD Confluence to newest releases:
- <https://confluence.desy.de/pages/viewpage.action?pageId=45738956>
- On: <https://confluence.desy.de/display/ILD/ILD>



Confluence interface showing the page structure and content:

- SEITENHIERARCHIE
 - > The ILD Organisation
 - > ILD Working Groups
 - > ILD Physics Working group
 - > ILD Software Working Group
 - > ILD Technical Working Group
 - Technical Task Forces
 - **Minutes / Reports / Technical Documents**
 - Central Design & Integration
 - Vertex
 - Tracker
 - Calorimeter
 - Very Forward System
 - Iron Instrumentation
 - Trigger & Data Acquisition
 - ILD Meetings
 - > ILD Management space
 - > Tools
 - > ILD notes and publications
 - > Information

Minutes / Reports / Technical Documents

Karsten Buesser posted on 26. Jan. 2017 14:35h - last edited by Karsten Buesser on 13. Apr. 2017 13:09h

Minutes

- Technical Converner Meeting Minutes
 - 17. March 2017
 - 15. February 2017
 - 12. January 2017
 - 28. November 2016
 - 26. October 2016
 - 20. September 2016
 - 11. July 2016
 - 04. June 2016
 - 13. May 2016
- Task Force Meeting Summaries
 - TF Meeting, 07.-08. November 2016, LAL, Orsay

Reports

- Technical Coordinator Reports
 - ILD Phone Meeting, 04. April 2017
 - ILD Phone Meeting, 07. February 2017
 - ILD Collaboration Meeting, 07. December 2016, Morioka
 - ILD Phone Meeting, 21. September 2016
 - ILD Phone Meeting, 20. July 2016
 - ILD Collaboration Meeting, 3.-5. June 2016, Santander

Technical Documents

- General
 - ILD Interface Control Document Template V1.0
 - ILD Coordinate System Definition (adapted from LDC)
 - ILD Conventions and Rules V0.0 (PDF) (WORD)
 - Requirements for Experimental Hall V2.0 (PDF) (XLS)

Links to EDMS

Conclusions

- We have first estimates of the requirements for the environments (surface and underground) of ILD:
 - space for assembly, maintenance and operations
 - services and supplies
- We try to get more reliable number by introducing a more formal process on the integration of ILD
 - Interface Control Documents
 - Convention and Rules
- We expect to have a first - probably still incomplete - picture before the end of the year
- Started also with a list of requirements for the experimental hall
- ILD is still evolving, sub-detector technologies not everywhere decided, R&D on-going
 - a somewhat moving target
- Still try to get the best picture that we can have at this time