

Status of R&D at

Frédéric Magniette
On behalf of the SiW-Ecal Team at LLR














Short slab prototype

- 7 layers with ILD level of integration (1024 channels per ASU)
- Single ASU slabs




DAQ improvements

- Online data treatment system (Presented at CHEF'17)
- New monitoring system
- New script system integrating movement table (no more night shift)
- Linear tracks reconstruction (online)




Beam-test 2017 @DESY

- Good results (All details in A. Irles talk)
- Full validation of the technical concept
- Some minor drawbacks
- Time to grow
 - Development of a new SMB/FEV adapted to long slab
 - Development of an electrical long slab prototype




Short slab prototype limitations

- Masked channels
- HV noise sensitivity
- Long slab chaining problem
- Fast clock limitations (frequency and cut)
- No hardware identification
- No way to input an outside spill number
- Using Skiroc2 instead of Skiroc2a




New SMB

- Developed with Kyushu University
- Cope with ILD geometry
- All necessary components on the 70x40 zone
- Only debugging feature are out of bounds
- New connector imprint compatible with connectors and kapton
- High level of integration



New FEV

- Very low noise design
- Reducing masked channels
- Adapted to Skiroc2a
- ILD compliant connection (70mm)
- Data rerouting to avoid long path from end of slab to SMB (U path)
- Includes capacitance for power pulsing
- New power supply decoupling
- Cope with ILD width
- Status : first batch delivery mid-march




DAQ improvements

- Fast Clock
 - adjustable at 40 or 50MHz
 - off during acquisition
- Hardware identification (See Yu Miura Talk)
- Spill number injection from outside
- Eudaq module (in collaboration with Adrian)

New slabs



- Planned production of 5 new short slabs
 - Kyushu & LLR
 - Wafer 650 μm & 525 μm
 - New SMB/FEV
 - Skiroc2a



- Expect better behavior (masked channel...) with same performance (S/N)
- Planned production of long slab in future


Long slab electrical prototype

- To test electric signal propagation and clock properties
- To debug read-out system on long path
- To evaluate electrical consumption




Long Slab Status


- 2 ASUs mounted – up to 12 expected
- One by one mounting strategy
- Equiped with baby-wafer (4x4)
- Hood for light protection
- Handling structure for beam-tests
- Satisfying level of noise




Cosmic Runs



Cosmic Runs (2)



Cosmic Runs (3)




Mechanical structure

- Adapted for
 - Beam-tests
 - cosmic-tests
 - radioactive source tests
- 360° rotation
- Adjustable height
- Wheels for long move
- Fine adjustment in both directions



Compact DAQ study for ILD

- Adaptation of the prototype DAQ to ILD constraint
- DIF suppression
- Redesign of the GDCC
- Reducing wires by buses or combined protocols
- HV generation inside GDCC



Scheduling

- Waiting for a good news in August
- In the meantime
 - Finishing the electrical long slab prototype
 - Finishing a new SMB/FEV short slab prototype
 - Finishing the options study for the compact DAQ
 - Beam-test @DESY in July 2018