# **ILD Integration Meeting**

## **TPC Mechanics**

11. February 2019, DESY

Volker Prahl on behalf of the TPC Collaboration

Most of the slides presented at:

## Mini-Workshop on ILC Infrastructure and CFS for Physics and Detectors

Friday 23 Feb 2018, KEK Tsukuba Campus

https://agenda.linearcollider.org/event/7804/ overview

Indebted to many authors from whom I have reused their material





#### **Over view**

- TPC support structure (AHCAL)
  - Requirements of the TPC support structure
  - Pros and cons of various fixing point
  - Various designs of the support structure
  - Design of the support structure
- HV-Cable and routing
- Cathode design
- TPC installation
  - TPC assembly
  - TPC insertion
- Conclusion and outlook



## **TPC** support structure

#### Requirements of the TPC support structure

- > Non-magnetic material
- Low thermal expansion coefficient
- > Robust system in x,y,z,


- Carbon fiber structure preferred

- > Accuracy and stability has to be constant over the lifetime
- Earthquake-safe system
- Short support structure (more a wish than a realistic option)
- Vibration absorption in Z direction
- Required accuracy 100 µm or better for Vertex, SIT, FTD !, realistic?
- Min free space of 10 mm in all directions ! Gaps ! I guess it is too small



## **TPC Support Structure**

#### Requirements of the TPC support structure, AHCAL around !



3 Point 3x120°, preferred gaps: 1,12, 6

4 Point 4x90°, preferred gaps: 3, 15, 11, 7 but this gaps filled 100%


Only the cryostat is foreseen to support the TPC

Volker Prahl , ILD Integration Meeting, TPC Mechanics I




| 11.02.2019 | Page 4

Main dimensions of the TPC (outside)  $\emptyset$  Od = 3616, r=1808  $\emptyset$  Id = 658, r=329 Length = 4700 incl. endplate and cabling



#### Flat ribbon support



Adjustable in x,y,z



## **TPC Support Structure**


#### Pros and cons of various fixing points


	AHCAL	Cryostat
3x120°	<ul> <li>Accuracy</li> <li>Shorter support structure</li> <li>HCAL deformation</li> <li>Stability under seismic conditions of the AHCAL</li> </ul>	<ul> <li>+ Accuracy</li> <li>- Longer support structure</li> <li>+ Cryostat deformation</li> <li>+/- Seismic stability</li> </ul>
4x90°	See above - More space required	See above - More space required



#### **HV-Cable and routing**

- Gap for the HV-Cable (two, incl. one spare?)
- TPC services
- TPC cooling lines
- TPC Support
- Cooling systems of







## **Cathode design**

Typical cathode design:

Tensioned foil (mylar, CFC, ...) supported by inner and outer ring



Design goals and problems:

- Light weight, thin
- Mechanically stable and robust (inaccessible)
- Supply of HV non trivial


 Studies in laboratory support this design: load is about 2kg/10cm outer radius

HV supply through special
 HV cable, OD about 14mm for
 100 kV

#### STAR-TPC



## **Cathode design**



Wetting tool and mold for an T-Shape cross section rim from NIKHEF, designed for the Atlas Endcap 2m outer dia

Instance of the outer / inner wheel of the Cathode




Volker Prahl , ILD Integration Meeting, TPC Mechanics I



| 11.02.2019 | Page 9

#### **HV Cable and routing**

#### Overview of an first idea of the HV-cable routing



voiker רומוי , וותegration Meeting, TPC Mechanics I



| 11.02.2019 | Page 10

#### **TPC** installation

Thomas Schörner-Sadenius Volker Prahl Paris, 8/9 October 2015

#### Some basic assumptions – all to be argued

#### No (long) transport of full TPC, field cage or fully equipped endplates $\rightarrow$ need to assemble TPC at IP campus

- Our assumption here: TPC assembly in the AH. Compatible with Yasuhiro's overall plan assuming realistic TPC time scales?
- Then space in AH necessary
- Do it in research office building? But then where full TPC system test (gas!)?
- No TPC assembly in DH.


# No TPC assembly in DH – sufficient space and possibility to work in parallel with yoke construction, but probably bad timeslot?

#### Current scenario therefore:

- Horizontal or vertical assembly in AH hall (exact position tbd)
- Space requirement: 100 m<sup>2</sup> (probably 60 m<sup>2</sup> enough, but some contingency), plus storage space (for modules) and test area for modules
- Field cage delivered in one or two big pieces and assembled in AH
- Necessity to create grey-room / ISO7 characteristics around TPC assembly place




#### **TPC installation**





#### **TPC** assembly



#### Then


- Cleaning of field cage
- Construction of grey/clean room around TPC field cage (ISO 7)
- Equipping of end-plates with tested modules using robot (petal-like structures in EP quadrant holes).
- System test (in AH)



#### **TPC** assembly


#### Horizontal procedure in a few steps

- Note: Grey room / ISO7 with stable T and FFUs needed from start. – Access to grey room through sliding gate with air lock
  - Assumption that field cage self-supporting and first EP\_equipment



#### **TPC** assembly


#### Horizontal procedure in a few steps



Alternative: First fixing of inner vessel in field cage, then installation / spanning of cathode. Top view of TPC assembly




#### **TPC inserting**



8/9 October 2015 TSS: TPC Assembly



#### **TPC inserting**



Section A-A

8/9 October 2015 TSS: TPC Assembly



#### **Conclusion and outlook**

#### Conclusion

- More studies of the support system required
  - Required space is an issue with the infrastructure and gaps between and in the middle of the AHCAL / ECAL octagons
  - Alternative approaches have to be considered
  - Various cross sections and materials of the support bars will be calculated
  - Alternative system design maybe required


#### Outlook

- Build the second field cage
- Availability of space in the gaps has to be evaluated
- More FEA studies
- Minimize the cross section of the support bars
- HV-Cable routing
- Field cage electrical insulation
- Cathode, design and inserting
- TPC Assembling and mounting, services
- TPC insertion
- Local regulations (Gas, HV, ...)
- And many more...




#### TPC assembly and inserting steps some ideas from Thomas Schörner-Sadenius, Volker Prahl
















































#### Then


- Cleaning of field cage
- Construction of grey/clean room around TPC field cage (ISO 7)
- Equipping of end-plates with tested modules using robot (petal-like structures in EP quadrant holes).
- System test (in AH)




| GEMEINSCHAFT 8/9 October 2015



- Note: Greyroom / ISO7 with stable T and FFUs needed from start.
  - Access to greyroom through sliding gate with air lock
  - -- Assumption that field cage self-supporting and first EP equipment




End-plate structures on trolleys and beginning of end-plate equipping (R); supporting star on inner-vessel platform








Field-cage assembly








## Horizontal procedure in a few steps Marriage of field-cage and end-plate R








Horizontal procedure in a few steps Set-up of inner vessel with cathode ("sail")








Marriage of inner vessel with cathode and field cage








Marriage of inner vessel with cathode and field cage



Alternative: First fixing of inner vessel in field cage, then installation / spanning of cathode.




Marriage of inner vessel with cathode and field cage. Fixing the supporting "star" supporting the inner vessel and the sail







Removing inner-vessel platform and finalisation of end-plate L










Inserting end-plate L: approaching the field cage ...








Horizontal procedure in a few steps

Inserting end-plate L: approaching the field cage, supporting the inner vessel and removing the supporting star, ...








### Horizontal procedure in a few steps

Inserting end-plate L: approaching the field cage, supporting the inner vessel + removing the supporting star, pushing in end-plate L










# Horizontal procedure in a few steps

Ready






DESY

# Alternative horizontal procedure

### Assumptions: Similar as before, but ...

- EP equipment at the end with robo
- Question of overall time planning (end-plate equipment the most time-consuming item







### Vertical procedure – time estimate

ID	Task Name	Duration	Start	Finish	Predecesso	Resource Names	F	January B		NA	April	В	July		E		Oct	tober M	-
0	TPC Assembly	254 day	Sun 01.01.17	Thu 21.12.17				В		M	E		M	1	C	i t	>	IVí	
1	Platform setup	0 days	Sun 01.01.17	Sun 01.01.17			· ·	01.01											
2	End-plate delivery	0 days	Sun 01.01.17	Sun 01.01.17			· ·	01.01											
3	Inner vessel delivery	0 days	Sun 01.01.17	Sun 01.01.17			· ·	01.01											
4	Field cage delivery to hall	0 days	Sun 01.01.17	Sun 01.01.17			·	01.01											
5	Module testing	70 days	Mon 02.01.17	Fri 07.04.17				-											
8	Placing field cage on end-plate	5 days?	Mon 02.01.17	Fri 06.01.17	1;2;4			1											
14	Installation of inner vessel	1 day?	Mon 09.01.17	Mon 09.01.17	8														
16	Installation of cathode	1 day?	Tue 10.01.17	Tue 10.01.17	14														
18	Installation of top end-plate	3 days?	Wed 11.01.17	Fri 13.01.17	16														
22	Cleaning and greyroom installation	21 days	Mon 16.01.17	Mon 13.02.17	18			<b>•</b>	-	_									
25	Cabling of field cage, inner vessel and cathode	12 days	Tue 14.02.17	Wed 01.03.17	22				Ψ2										
28	Installation of Modules	160 days	Thu 02.03.17	Wed 11.10.17	25;6					<b>_</b>						_	-		
31	Final test of TPC	51 days	Thu 12.10.17	Thu 21.12.17	28												-		<b>-</b>
34	TPC ready	0 days	Thu 21.12.17	Thu 21.12.17	31														






# Horizontal procedure – time estimate


ID	Task Name	Duration	Start	Finish	Predecesso	E	January B	М	April		В		July M	F		В	October	1	E	January B
0	TPC Assembly	292 day	Sun 01.01.17	Tue 13.02.18		_			_			-		_					_	
1	Start of Assembly	0 days	Sun 01.01.17	Sun 01.01.17			• 01.01													
2	Greyroom setup	45 days	Mon 02.01.17	Fri 03.03.17			÷													
6	Trolley installation and test	11 days?	Mon 06.03.17	Mon 20.03.17	2			<b>—</b>	•											
13	End-plates on trolleys	2 days?	Tue 21.03.17	Wed 22.03.17	12			l.												
16	End-plate mounting R	87 days	Thu 23.03.17	Fri 21.07.17	13				-					1						
20	End-plate mounting L	87 days	Mon 24.07.17	Tue 21.11.17	13;16															
24	Field cage assembly	25 days	Wed 22.03.17	Wed 26.04.17	13				<b>_</b>	•										
31	Marriage field cage + end-plate R	5 days?	Mon 24.07.17	Fri 28.07.17	19;30															
35	Inner vessel setup on platform	3 days?	Mon 31.07.17	Wed 02.08.17	31									<b>س</b>						
39	Marriage of inner vessel + sail	10 days?	Thu 03.08.17	Wed 16.08.17	35										]					
44	Marriage of inner vessel / sail + field cage	10 days?	Thu 17.08.17	Wed 30.08.17	31;39									Ţ	<b>-</b>					
50	Marriage of end-plate L + field cage	6 days?	Wed 22.11.17	Wed 29.11.17	44;23													Ţ	•	
55	Removal of trolleys	3 days	Thu 30.11.17	Mon 04.12.17	50														<b>W</b>	
60	TPC tests	51 days	Tue 05.12.17	Tue 13.02.18	55														<b>_</b>	
63	TPC ready	0 days	Tue 13.02.18	Tue 13.02.18	62															



DESY


# TPC insertion – mechanism?






















































Section A-A











# Veeeery preliminary conclusions

### Currently, more in favour of vertical assembly:

- Space requirements
- Time requirements
- Ease of access / logistics
- ....

# But many steps need thorough planning, and many engineering solutions are still missing.

Also for insertion of TPC into ILD, and for mounting and suspension

### Nevertheless – best current guess:

- Assembly requires one year after delivery of field cage
- Space requirements: 100 m<sup>2</sup> (ISO 7 / grey room quality)
- Plus space for module storage and testing, plus services





# Some near-future steps

### Continue to work on the models, assumptions and their

#### consequences

- Principal procedures, needs and requirements
- Some important topics:
  - Support of TPC in ILC?
  - Prevention of longitudinal movement?
  - Cathode design?
  - End-plate design?
  - Space and infrastructure in DH (gas, power, electronic hut etc.)

### To be decided soon: Where to assemble TPC?

- AH or research office building?
- If research office building, then still full TPC system test before lowering in AH?

### Draw on previous experience

■ Specifically ALICE → meeting in November at CERN

### Get in touch with global integration efforts

Hope to intensify contact to Yasuhiro HELMHOLTZ | GEMEINSCHAFT 8/9 October 2015 TSS: TPC Assembly

