


# How to build the ILD TPC?

INTEGRATION  
MEETING  
DESY,  
Feb.11,2019



From design to reality



P. COLAS, A. SUGIYAMA

# OVERVIEW

## Gravitational loads

- Self-weight of structure : 895 kg
- Weight of the modules : 1176 kg (84 modules / endplate and 7 kg / modules)

→ Total weight of 2 000 kg

## Overpressure of 3 mbar

- Pressure applied on the cages
- Forces applied on each endplate by taking into account the pressure on modules






N.B.: what is called modules here (400x400 mm<sup>2</sup>) can be seen as supermodules consisting of 4 smaller modules

# FIELD CAGE

Requires a mandrel to shape the composite material  
Kapton with copper strips  
Installation of flanges



A construction on site looks preferable to a remote construction followed by a travel. Requires space in the surface.





# ENDPLATES

One piece, mold? Space frame?  
Which material? Stainless steel?  
Aluminum+carbon fibre? ( $O(50 \mu)$  accuracy) of the  
module positioning  
Need to fill windows by dummy modules to keep  
the stiffness and exchange them one by one in the  
grey room after assembly.



# MODULES

Modules include frame, PCB, amplification system, Front-end electronics (FECs and concentrator), cooling.

3 cables (HV, LV, Signal) and one pipe per module.


They must be shipped after full testing and re-tested after reception at Kitakami.

A special tool is necessary to mount them

*Example of a price estimate for a T2K upgrade module (Rui de Oliveira)*

File preparation cost :	800 CHF
Tooling:	1800 CHF
Protection box:	500 CHF/box (to be returned after each delivery)
Price for 1 detector:	4970 CHF with +/- 10% accuracy 5370 CHF with +/- 3% accuracy
Price for 32 detectors:	3976 CHF/detector with +/- 10% accuracy 4296 CHF/detector with +/- 3% accuracy
Connector assembly:	to be defined

Delivery: approximately 4 to 5 detectors every 6 weeks after order reception  
CERN is the producer of these parts.  
Price don't include VAT.




ALICE GEM modules being assembled at CERN




# SUPPORT

To the cryostat or to the HCAL?  
 Best for deformations: isostatic median support to the HCAL (shorter 'ribbons')  
 Damping to be studied.


V.Prahl



Isostatic median support





Julie Elman, Zhihong Sun



Shape factor x3000

● ● Various possible fixing points

# INTERFACES



Very High Voltage for the central cathode : Very big cable (insulation), curvature radii 70mm to 280mm. Or make it onsite (needs space also)

Low-voltage power: bundles of 10 copper cables  
6 mm<sup>2</sup> section (32 A).  
6 sectors per end-plate : 120 cables, 12kW(100 W per cable).  
With 20 m cables (R=0.06 Ω) 60 W loss.  
Can we accept this such a loss (60% of the useful power?)  
Need cable cooling? DC-DC converters?



Detector HV and fibres for readout less demanding

Patch panels on each sector to allow disconnecting the TPC

Do we need a jacket against heat from the ECAL?


# CONVENTIONAL FACILITY REQUIREMENTS

Utility Space	
Platform	~20-30 m
Service Gallery	+ 50 m
U/S Cavern	+ 30 m
Surface	+100 m





# CONVENTIONAL FACILITY REQUIREMENTS

Sub-detector name				TPC	
Number of 19-inch electronics racks	Platform				for LV supply for HV(+VHV) supply
	Service gallery				
	Utility/Service Cavern (USC)				
Sub-detector cooling system	Floor in USC			Don't mind	
	WxDxH		12x(0.8x0.7x1.5)	m <sup>3</sup>	
Gas system	Space on surface (WxD)		8x4	m <sup>2</sup>	Big tank  gas circulation purification/removal O <sub>2</sub> ,H <sub>2</sub> O gain monitor
	Space in USC (WxD)			m <sup>2</sup>	
	Space on service gallery (WxD)			m <sup>2</sup>	
	Space on platform (WxD)		2x2	m <sup>2</sup>	
Laser system	Space in USC (WxD)		1x0.6	m <sup>2</sup>	
Other requirements					
Comment by Y.Sugimoto	Laser system has to be placed in an isolated room in USC for safety reason.				

Do we need any other space?

monitor(temperature, , )


controll, interlock,, somewhere near detector

# CONVENTIONAL FACILITY REQUIREMENTS

Sub-detector name	TPC
P_FE	12 kW
Q_PC	kW
e	80%
P_BE	kW
P_CS	1.2 kW
Type of cooling water for cooling system	Normal temperature
P_LV	15 kW
Q_LV	3 kW
Q_BE	0 kW
Q_CS	13.2 kW

Assumption  
 1.5M channel/EP  
 PConsumption 4mW/ch  
 => 12 kW

HV Power consumption  
 ~5W from LP1 extrapolat




- $P_{FE}$  : Power consumption of sub-detector Front-end Electronics
- $Q_D$  : Heat loss in sub-det. (=  $P_{FE}$ )
- $Q_{PC}$  : Heat loss in power cables
- $P_{LV}$  : AC power input to LV PS
- $\epsilon$  : Efficiency of LV PS ( $P_{LV} \cdot \epsilon = P_{FE} + Q_{PC}$ )
- $Q_{LV}$  : Heat loss in the LV PS ( $= (1-\epsilon) \cdot P_{LV}$ )
- $P_{BE}$  : AC power input to back-end elec./HV power supply
- $Q_{BE}$  : Heat loss in the BE/HV PS ( $= P_{BE}$ )
- $P_{CS}$  : Electric power to drive the cooling system
- $Q_{CS}$  : Heat to be extracted from cooling system ( $= Q_D + P_{CS}$ )

How to build the TPC?

# ASSEMBLY

V. Prah, Th. Schörner-Sadenius



Is one year enough? How much manpower needed?