


ILC Project Update

Shin MICHIZONO

KEK/Linear Collider Collaboration (LCC)

- *ILC area systems*
 - *Electron source*
 - *Positron source*
 - *Damping ring*
 - *RTML (bunch compressor)*
 - *Superconducting RF*
 - *Final focus*
 - *Beam dump*
 - *CFS*
- *ILC preparation (US, Japan, Europe)*
- *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
- *Summary*

Technology of the ILC




- Creating particles **Sources**
 - polarized electrons/positrons
- High quality beams **Damping ring**
 - Low emittance beams
 - Small beam size (small beam spread)
 - Parallel beam (small momentum spread)
- Beam transport **RTML (bunch compressor)**
- Acceleration **Main linac**
 - superconducting radio frequency (SRF)
- Getting them collided **Final focus**
 - nano-meter beams
- Go to **Beam dump**



ILC beam structure

The ILC is operated at a repetition rate of 5 Hz.
A beam pulse comes every 200 milliseconds.



ILC Project Update

Shin MICHIZONO


KEK/Linear Collider Collaboration (LCC)

- *ILC area systems*
 - ➡ • *Electron source*
 - *Positron source*
 - *Damping ring*
 - *RTML (bunch compressor)*
 - *Superconducting RF*
 - *Final focus*
 - *Beam dump*
 - *CFS*
- *ILC preparation (US, Japan, Europe)*
- *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
- *Summary*

Generation of polarized electron

3 step model for electron emission

N.Yamamoto, LCWS2014



1. At the Super-lattice (SL) layers, electrons are pumped by ***Circularly polarized laser*** from the highest valence band to conduction band.
2. Excited electrons are diffused to surface.
3. Electrons are emitted through the ***NEA (Negative Electron Affinity) surface***.

These processes contribute parameters such as ***Polarization, Quantum Efficiency (QE)***. ***Energy Gap*** (structure design) corresponds to λ .

Electrons excited from the heavy hole and from the light hole have different spins. When the degeneracy of these two levels is solved and electrons are excited from one level, max. 100% spin polarization can be obtained.

Results at Nagoya Univ.

N.Yamamoto, LCWS2014


- Strain-Compensated Superlattice
 - Higher crystal quality
 - Thicker superlattice

Max. Pol. (~ 92%)
QE(~ 2.2 %) were achieved

GaAs-GaAsP Strain-Compensated.

- Obtained
 - Pol. ~92%
 - With QE 2.2%
- ~90% looks realistic

$$P \equiv \frac{N_L - N_R}{N_L + N_R}$$



Demonstrated ILC parameters (e- source)

Parameter	Requirement	Design	Achieved	Unit	Facility
Bunch Charge	3.2	4.8	8.0	nC	SLAC -SLC
Average Beam current	21	42	1000	μ A	JLAB
Beam current in pulse	5.8	11.6	60	mA	Cornell U.
Polarization	80	80	90	%	Nagoya, SLAC, KEK
Quantum Efficiency	0.5	0.5	2.2	%	Nagoya
Drive Laser (in pulse)	1.8	10	>10	W	Commercially available

ILC Project Update


Shin MICHIZONO

KEK/Linear Collider Collaboration (LCC)


- *ILC area systems*
 - *Electron source*
 -  • *Positron source*
 - *Damping ring*
 - *RTML (bunch compressor)*
 - *Superconducting RF*
 - *Final focus*
 - *Beam dump*
 - *CFS*
- *ILC preparation (US, Japan, Europe)*
- *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
- *Summary*

Positron Source (Undulator)

125 GeV electrons are injected to the helical undulator. The photons produced at the undulator is used for the electron/positron pair creation at the rotating target. Polarized positrons can be generated.



*Positron source will be reported at Tuesday Accelerator Plenary
K.Yokoya "Progress of the Accelerator Design"*



test at Daresbury






PHYSICAL REVIEW LETTERS **107** (2011) 174803



Two undulators in one cryomodule were tested. Both achieved nominal magnetic fields.

Positron Source (e-Driven)

Extra 3GeV linac is used for the positron generation. High energy electrons are not necessary. (Electron independent commissioning is possible. However, polarization is not available.)



Positron rotating target



	E-Driven	undulator	Existing X-ray generator
Cooling/Seal	water/magnetic fluid	Radiation/ magnetic levitation	water/magnetic fluid
radius (mm)	250	500	160
weight (kg)	65*	50*	17
Tangential velocity (m/s)	5	100	160
rotation (rpm)	200	2,000	10,000
Beam heat load(kW)	20	2	90
Vacuum pressure (Pa)	10^{-6}	10^{-6}	10^{-4}

*The weight depends on the design of the disk part and the material

- Reliable rotating target
- Replacement of rotating target

Demonstrated ILC parameters (e+ source)


Parameter	Requirement	Design	Achieved	Unit	Facility
Bunch Charge	3.2	4.8	8.0	nC	SLAC SLC (E-Driven)
Undulator pitch	11.5	11.5	2.5	mm	SLAC E166
Positron Polarization (optional)	30	30	80	%	SLAC E166
W-Re Target Heat Load (PEDD* for E-Driven)		34	70	J/g	SLAC SLC (E-Driven)
Ti alloy Target Heat Load (PEDD for Undulator)		61	160	J/g	Estimated from physics constant table
Flux Concentrator Peak field (E-Driven)	5.0	5.0	10	T	BINP
QWT peak field (Undulator)	1.0	1.0	2.3	T	KEK

PEDD: peak energy deposition density

ILC Project Update


Shin MICHIZONO

KEK/Linear Collider Collaboration (LCC)

- *ILC area systems*
 - *Electron source*
 - *Positron source*
 -  • *Damping ring*
 - *RTML (bunch compressor)*
 - *Superconducting RF*
 - *Final focus*
 - *Beam dump*
 - *CFS*
- *ILC preparation (US, Japan, Europe)*
- *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
- *Summary*

Damping ring

Worldwide light sources' emittance




Horizontal emittance is smaller at MAX IV.

Vertical emittance is smaller at Australian LS, SLS, DIAMOND.

Beam extraction by fast kicker


Bunch extraction test at ATF




Bunch-space at ATF exp. and ILC

	ATF exp.	ILC
DR	5.60 ns	6.15 ns
extraction	302-308ns	554 ns

Fast Kicker waveform



T.Naito *et al.*, NIM A **571** (2007) 599.



T.Naito *et al.*, PR ST-AB **14** (2011) 051002


Demonstrated ILC parameters (Damping Ring)

Parameter	Requirement	Design	Achieved	Facility	Comment
Horizontal Emittance(ε_x)	0.4nm	0.4nm	0.34nm	MAX-IV	Pedro F. Tavares, 2017 Phangs Workshop
Vertical Emittance (ε_y)	2pm	2pm	< 2pm	SLS, Australian LS, Diamond LS	TDR
Normalized Emittance ($\gamma\varepsilon_x/\gamma\varepsilon_y$)	4.0 μ m/20nm	4.0 μ m/20nm	4.0 μ m/15nm	ATF	Y. Honda <i>et al.</i> , PRL 92 (2004) 054802.
Fast Ion instability				SuperKEKB	On going
Electron Cloud Instability				SuperKEKB/CesrTA	On going
Kicker Rise Time	< 6.15ns	< 3.07ns	2.2ns	ATF	T. Naito <i>et al.</i> , NIM A 571 (2007) 599.
Kicker Voltage	± 10 kV	± 10 kV	± 10 kV	ATF	T. Naito <i>et al.</i> , PR ST-AB 14 (2011) 051002.
Kicker Voltage stability	0.07%	0.07%	0.035%	ATF	
Kicker Frequency	1.8MHz	2.7MHz	3.25MHz	ATF	
Fast Kicker extraction test				ATF	


ILC Project Update

Shin MICHIZONO

KEK/Linear Collider Collaboration (LCC)

- *ILC area systems*
 - *Electron source*
 - *Positron source*
 - *Damping ring*
 -  *RTML (bunch compressor)*
 - *Superconducting RF*
 - *Final focus*
 - *Beam dump*
 - *CFS*
- *ILC preparation (US, Japan, Europe)*
- *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
- *Summary*

RTML (Bunch compressor)



“Bunch compressor” compresses the bunch **from 6 mm to 0.3 mm** before entering the main linac (15GeV).

This final bunch length is one or more orders of magnitude longer than FEL etc., so it is not difficult (eg SACLA; FWHM 3 "μm").

If the phase of the RF cavity is jittered, jitter occurs in the arrival time of the beam at the collision point. Therefore, the phase jitter of the RF cavity of the ILC bunch compressor must be kept within **0.24°** (0.15 mm). (but not difficult compared with the XFEL requirements of $\sim 0.01^\circ$)


Demonstrated ILC parameters (RTML)

Parameter	Requirement	Design	Achieved	Facility	Comment
BC phase error	0.24°		0.042°	KEK-STF	M.Omet, Ph.D thesis (2014)
BC amplitude error	0.5%		0.041%	KEK-STF	
Horizontal emittance increase ($\gamma\epsilon_x$)	1 μ m	RTML (0.47 μ m) , BC (0.43 μ m), ML (0.00 μ m), total (0.90 μ m)		In simulation	TDR
Vertical emittance increase ($\gamma\epsilon_y$)	15 nm	RTML (6.4nm) , ML (4.5nm), total (10.9nm)		In simulation	TDR


ILC Project Update

Shin MICHIZONO

KEK/Linear Collider Collaboration (LCC)

- *ILC area systems*
 - *Electron source*
 - *Positron source*
 - *Damping ring*
 - *RTML (bunch compressor)*
 -  *Superconducting RF*
 - *Final focus*
 - *Beam dump*
 - *CFS*
- *ILC preparation (US, Japan, Europe)*
- *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
- *Summary*

Beam Acceleration in Main Linac



Superconducting Accelerator

RF unit (below) is placed repeatedly in a line

Cryomodule

KLY



Klystron: RF power is generated

Waveguide : RF power is distributed

Beam pulse length (1ms, 5Hz)

1312 Beam bunches

Acceleration gradient

RF pulse length

Interval of beam bunch



Accelerating field in cavity
It is repeated in 5Hz

Cryomodule: 8 cavities are included.


Beam bunch:



Main Linac at the ILC



R. Geng (JLAB)




ILC SRF Global Integration Model


~8,000 x 1.1 (Yield = 90%)
~ 9,000 cavities of mass-production



Industry:
manufacturing
components



Hub-lab:
regionally
hosting
integration
& Test




Demonstrated ILC parameters (SRF)

Parameter	Requirement	Achieved	Comment
Acc. Gradient in the cryomodule	31.5 MV/m	32.5MV/m (PXFEL-1, DESY) 31.5MV/m(CM-2, ASTA) 32 MV/m(CM-1&2a,STF)	DESY-Proto-XFEL (ILC-TDR V3, Part-1, p43) FNAL-ASTA (E. Harms, AWLC14 May 2014) STF(KEK news May 22,2019)
Average Q0 in cryomodule	10^{10}	-- (PXFEL-1, DESY) 0.9×10^{10} (CM-2, ASTA) 0.7×10^{10} (CM-1&2a,STF)	FNAL-ASTA (E. Harms, AWLC14 May 2014) KEK-STF report (Y. Yamamoto, STF,2016)
Acc. Gradient at vertical test	$\geq 35(\pm 20\%)$ MV/m $\geq 90\%$ yield	<37 MV/m> ~94%	TDR vol-3 part I, Chapter 2.3
Beam current	5.78mA	6mA (800 μ s beam pulse length)	DESY-FLASH 9mA-study, TDR vol-3 part I, p.80
Number of bunches	1312	2400 (800 μ s beam pulse length)	
Bunch charge	3.2nC	3nC (600 μ s beam pulse length) 2nC (800 μ s beam pulse length)	
Bunch space	554ns	333ns	
Bunch length	727 μ s	800 μ s	
Rf pulse width	1.65ms	>1.65ms	
RF pulse repetition	5Hz	10Hz	DESY XFEL

ILC Project Update

Shin MICHIZONO

KEK/Linear Collider Collaboration (LCC)

- *ILC area systems*
 - *Electron source*
 - *Positron source*
 - *Damping ring*
 - *RTML (bunch compressor)*
 - *Superconducting RF*
 -  • *Final focus*
 - *Beam dump*
 - *CFS*
- *ILC preparation (US, Japan, Europe)*
- *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
- *Summary*


ATF International Collaboration



Institute of High Energy Physics
Chinese Academy of Sciences




Laboratoire d'Annecy-le-Vieux
de Physique des Particules



- ATF international collaboration established in 2005.
- During the construction phase (~2010), many researchers joined for the installation of the components of in-kind contribution.
- Since 2011, the researchers visit for mainly the beam study.
- Many researchers are working for this collaboration.

ATF/ATF2: Accelerator Test Facility



Develop the nanometer beam technologies for ILC


■ Key of the luminosity maintenance

■ 7.7 nm beam at IP (ILC250)

ATF2: Final Focus Test Beamline

Goal 1: Establish the technique for small beam

Goal 2: Stabilize beam position




FONT* Bunch train feedback at final focus

*Feedback On Nanosecond Timescales


<https://journals.aps.org/prab/abstract/10.1103/PhysRevAccelBeams.21.122802>

CAIN simulation




Depending on the relative position of the beam, **beams** are greatly scattered by the beam-beam effect.

ILC bunch structure




The position of the beam between pulse trains shifts due to ground vibrations and equipment noise.

On the other hand, the position of the beam does not change significantly in the pulse train.



Efficient beam collision can be achieved **with high-speed feedback** that measures the initial beam position of the pulse train and corrects the position of subsequent bunches in the train.

Feedback latency should be less than bunch space.



The first bunch does not collide, but the second and subsequent bunches will collide.

Beam Size and Stability at ATF2 for final focus at ILC

Goal 1: Establish the ILC final focus method with same optics and comparable beamline tolerances

- ATF2 Goal : **37 nm** → ILC **7.7 nm** (ILC250)


- Achieved **41 nm** (2016)

Goal 2: Develop a few nm position stabilization for the ILC collision


- **FB latency 133 nsec achieved**

(target: < 366 nsec)


- **positron jitter at IP: 106 → 41 nm (2018)** (limited by the BPM resolution)



History of ATF2 small beam



Nano-meter stabilization at IP (2018)



Demonstrated ILC parameters (Final focus)

Parameter	Requirement	Design	Achieved	Facility	Comment
ATF2 beam size (σ_y^*)	37 nm (ATF2 design)		41 nm	ATF2	T.Okugi, LINAC2016
ILC beam size	7.7 nm (ILC design)			ATF2	
Feedback position stability	12% of beam size (1nm)	10% of beam size	10% (FB OFF) ⇒ 4% (FB ON)	ATF2	P. Burrows, AWLC2018
Feedback latency	< 554 ns	< 366 ns	133 ns	ATF2	Physics Procedia 37 (2012) 2063. Phys.Rev.Accel.Beams .21.122802

ILC Project Update

Shin MICHIZONO

KEK/Linear Collider Collaboration (LCC)

- *ILC area systems*
 - *Electron source*
 - *Positron source*
 - *Damping ring*
 - *RTML (bunch compressor)*
 - *Superconducting RF*
 - *Final focus*
 - *Beam dump*
 - *CFS*
- *ILC preparation (US, Japan, Europe)*
- *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
- *Summary*



Beam dump


- ILC beam dump is designed for 1TeV collision energy, and ILC250 has enough margin.

P. Satyamurthy, et.al., NIM A 679 (2012) p67-81.

Water dump (10 atm; boiling temp. 180°C)

Peak temp. by beam: 155°C

- Water flow: 2.17m/s
- Inlet temp.: 50°C
- Diam. 1.8m, length 11m (30X₀)
- SUS 316LN, thickness 2 inch
- End plate: SUS t7.5cm




Water beam dump	Req.	Des.	Achieved	unit	Comment
ILC 250GeV	2.6	17	–	MW	Designed for 500GeV beam
SLAC 2mile LINAC	–	2.2	0.75	MW	ILC beam dump prototype
CEBAF	0.9	1.0	0.73	MW	In operation at Jefferson Lab from the 90s to the present. 2 units (2 beam lines). Composite type with aluminum plates arranged in water.

Beam dump system

Tritium is generated in the water beam dump. Saturated value is expected ~ 100 TBq (~ 0.3 g tritium) in the two beam dumps (100 t water).

- Detailed design of the cooling system
- Remote handling of beam dump window



ILC Project Update

Shin MICHIZONO

KEK/Linear Collider Collaboration (LCC)

- *ILC area systems*
 - *Electron source*
 - *Positron source*
 - *Damping ring*
 - *RTML (bunch compressor)*
 - *Superconducting RF*
 - *Final focus*
 - *Beam dump*
 - *CFS*
- *ILC preparation (US, Japan, Europe)*
- *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
- *Summary*





ILC Accelerator: Lattice design and tunnel design

ILC250 Lattice design was fixed, Accelerator tunnel design is on-going


**Total Accelerator tunnel length
= 20,549.5m (20.5km)**

Civil engineering will be reported at Tuesday Accelerator Plenary
N.Terunuma "Progress of Civil Engineering Design"






Bird's eye view of ILC in Kitakami candidate site




Tunnel design for Kitakami Candidate Site (ILC250GeV 20.5km)

Plan of Interaction point



Surface-to-Underground access-tunnel



Surface Access Station

Access Tunnel (10% down-slope tunnel, about 1km length)

Underground Access Hall

Accelerator Tunnel

ILC Project Update

Shin MICHIZONO


KEK/Linear Collider Collaboration (LCC)

- *ILC area systems*
 - *Electron source*
 - *Positron source*
 - *Damping ring*
 - *RTML (bunch compressor)*
 - *Superconducting RF*
 - *Final focus*
 - *Beam dump*
 - *CFS*
- ➡ • *ILC preparation (US, Japan, Europe)*
- *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
- *Summary*

ILC preparation plan/activity

European ILC preparation plan as “E-JADE” report

https://www.e-jade.eu/sites/sites_custom/site_e-jade/content/e49893/e65922/e73204/ILC-EIPP.E-JADE.v2.12.20180703.pdf



USA

US-Japan Joint Research on ILC Cost Reduction
High Luminosity ILC Workshop (May 2019) @FNAL
<https://indico.fnal.gov/event/20759/>
<https://arxiv.org/abs/1910.01276>

KEK ILC action plan

https://www.kek.jp/en/newsroom/KEK-ILC_ActionPlan_Addendum-EN%20%281%29.pdf

The International Linear Collider A European Perspective

Prepared by: Philip Bambade¹, Ties Behnke², Mikael Berggren², Ivanka Bozovic-Jelisavcic³, Philip Burrows⁴, Massimo Caccia⁵, Paul Colas⁶, Gerald Eigen⁷, Lyn Evans⁸, Angeles Faus-Golfe¹, Brian Foster^{2,4}, Juan Fuster⁹, Frank Gaede², Christophe Grojean², Marek Idzik¹⁰, Andrea Jeremie¹¹, Tadeusz Lesiak¹², Aharon Levy¹³, Benno List², Jenny List², Joachim Mnich², Olivier Napoléon⁶, Carlo Pagani¹⁴, Roman Poeschl¹, François Richard¹, Aidan Robson¹⁵, Thomas Schoerner-Sadenius², Marcel Stanitzki², Steinar Stapnes⁸, Maksym Titov⁶, Marcel Vos⁶, Nicholas Walker², Hans Weise², Marc Winter¹⁶.

¹LAL-Orsay/CNRS, ²DESY, ³INN VINCIA, Belgrade, ⁴Oxford U.,
⁵U. Insubria, ⁶CEA/Irfu, U. Paris-Saclay, ⁷U. Bergen, ⁸CERN, ⁹IFIC,
U. Valencia-CSIC, ¹⁰AGH, Kraków, ¹¹LAPP/CNRS, ¹²IFJ-PAN,
Kraków, ¹³Tel Aviv U., ¹⁴INFN, ¹⁵U. Glasgow, ¹⁶IPHC/CNRS.

KEK-ILC Action Plan

KEK-ILC Action Plan Working Group

1. Introduction

The International Linear Collider (ILC) is a next-generation energy frontier electron-positron collider. It will reach a center-of-mass energy of 500 GeV in the first stage, and can be upgraded to an energy to 1 TeV in the future. It aims to precisely measure the properties of the Higgs particle and Top quark, discover new particles and phenomena, and search for new physics beyond the Standard Model of elementary particle physics.

The worldwide high-energy physics community has recognized importance of the ILC, and established the Global Design Effort (GDE) in 2005 under the supervision of the International Committee for Future Accelerators (ICFA). The GDE has advanced the design and technical development of the ILC within the international framework. In June 2013, GDE published its progress in the ILC Technical Design Report (ILC-TDR); this report included accelerator design, technology, construction costs, and the human-resource requirements necessary to realize the ILC. The ICFA established the Linear Collider Collaboration (LCC) under the supervision of the Linear Collider Board in February 2013 to oversee the detailed ILC accelerator design and engineering.



Based on discussions for its future plan, the Japan Association of High Energy Physicists proposed to host and to realize the ILC as a global project in October 2012. In May 2013, the Ministry of Education, Culture, Sports, Science and Technology of Japan (MEXT) asked the Science Council of Japan (SCJ) to study the ILC project from a scientific viewpoint. In September 2013, the SCJ produced a “Report on the International Linear Collider Project”. In May 2014, MEXT established the ILC Advisory Panel (ILC-AP), and has been studying issues pointed out by the SCJ. In June 2015, MEXT ILC-AP produced a report, “Summary of the International Linear Collider (ILC) Advisory Panel’s Discussions to Date”. Based on this report, further action has been taken to establish a new working group to verify the human resource and training plan necessary to realize the ILC.

European Strategy input
The International Linear Collider
A European Prospective

ILC Cost-Reduction R&D in US-Japan Cooperation on SRF Technology



Based on recent advances in technologies;

- Nb material/sheet preparation
 - w/ optimum Nb purity and clean surface



- SRF cavity fabrication for high-Q and high-G

-w/ a new “N Infusion” recipe demonstrated by Fermilab



Fermilab High Luminosity ILC Workshop (May 2019)

<https://indico.fnal.gov/event/20759/>

Fermilab Workshop on ILC HL-HG

Wednesday, May 8, 2019 from 08:00 to 18:00 (US/Central)
at Fermilab (Hermitage Conference Room)

Description Now that the Japanese decision on ILC has been delayed, the fate of ILC within the European community is likely to suffer. In particular since European enthusiasm for FCC-ee has been rising as the next Higgs Factory. Another competitor is CEPC. One of strong arguments that FCC proponents offer is the very high luminosity (6 times ILC) at 250 GeV. But the downside of FCC is of course the cost, which starts at 10B\$ (from CDR) not including the tunnel (+3 B\$) and detector (+2 B\$). Over a longer timescale, US will hold Snowmass to discuss future options for US HEP thrusts. There will probably be many proposals, such as Muon-collider-based Higgs Factory, Neutrino Factory, PIP-III, Gamma-Gamma Higgs Factory.

The goal of this one-day workshop is to discuss the possibility for a competitive ILC Higgs Factory with high luminosity upgrade option and the 350 GeV upgrade option. Can the High Lumi ILC offer the same luminosity as FCC-ee but be significantly less expensive than FCC-ee?

We will explore paths to competitive high luminosity upgrade options for ILC, estimate the cost for the upgrade, and discuss strategies on how to increase support for ILC within the European community and later at Snowmass. We will also discuss paths to a higher energy 350 GeV top factory upgrade to correspond to the higher energy option in the FCC plans.

Material: [Agenda](#) [Beamstrahlung Photon Load on the TESLA Extraction Septum Blade](#) [CERN-ACC-2019-0003 \(FCC-ee\)](#) [CLIC 2018 Summary Report](#) [Chapter 7 ILC Beam Delivery System](#) [Future prospects of accelerator science for particle physics](#) [ILC_European_Perspective_Final](#) [ILC_Global_Project_Final long](#) [ILC_Global_Project_Final short](#) [The International Linear Collider Machine Staging Report 2017](#)

Wednesday, May 8, 2019

08:30 - 08:45 Introduction to the Workshop 15'
Speakers: Dr. Sergey Belomestnykh (Fermilab), Dr. Anna Grassellino (Fermilab)

08:45 - 09:30 High Lumi Upgrade and 350 GeV parameter options and cost impacts 45'
Speaker: Prof. Hasan Padamsee (Cornell University)
Material: [Slides](#)

09:30 - 09:45 Discussion 15'

09:45 - 10:15 High Q/High Gradient paths 30'
Speaker: Dr. Anna Grassellino (Fermilab)
Material: [Slides](#)

10:15 - 10:30 Discussion 15'

10:30 - 10:45 Coffee break

10:45 - 11:15 Detector Constraints and ILC Luminosity 30'
Speaker: Prof. Hitoshi Yamamoto (Tohoku University)
Material: [ILC table](#) [Lum-energy-doc preliminary](#) [Luminosity vs Log E plot](#) [Power vs Log E plot](#) [Slides](#)

11:15 - 11:30 Discussion 15'

11:30 - 13:00 Lunch

13:00 - 13:30 Impact on Positron Source 30'
Speaker: Dr. Nikolay Solyak (FNAL)
Material: [Slides](#)

13:30 - 13:45 Discussion 15'

13:45 - 14:15 Impact on Damping Rings and Ring-to-Main-Linac 30'
Speaker: Prof. David Rubin (Cornell University)
Material: [Slides](#)

14:15 - 14:30 Discussion 15'

14:30 - 14:45 Coffee break

14:45 - 15:15 Open discussion on presented options, challenges and other topics 30'

15:15 - 15:45 Interaction Region and IP parameters 30'
Speaker: Dr. Andrei Seryi (Jefferson Lab)
Material: [Slides](#)

15:45 - 16:15 Discussion 30'
Material: [Slides](#)

16:15 - 16:30 Closing remarks 15'
Speakers: Dr. Sergey Belomestnykh (Fermilab), Dr. Anna Grassellino (Fermilab), Prof. Hasan Padamsee (Cornell University)

Fermilab High Luminosity ILC Workshop (May 2019)

- Significant luminosity improvements are made possible by SRF R&D advances since TDR
- Main result is given below – by implementing technically feasible changes, ILC baseline luminosity of 1.35×10^{34} can be increased
 - Increased number of bunches x2
 - Increased rep rate x3
 - Increased Q_0 x 2
 - Beam and IP parameters same as ILC baseline
- Effective luminosity with polarization advantage (x 2.5) is $20 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$ (ILC) vs. $17 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$ (FCC-ee, including multiplier of 2 for multiple interaction points)
- AC power ~270 MW (ILC) vs. 282 MW (FCC-ee)

Accelerator preparation phase R&Ds

	Pre-prep.	P1	P2	P3	P4	1	2	3	4	5	6	7	8	9	10	Phys. Exp.
<u>Preparation .</u>																
<u>Construction</u>																
<u>Commissioning</u>																
<u>Physics Exp.</u>																

Main tasks to be done during 4-year preparation phase

Area	Tasks	KEK ILC action plan
Accelerator Design	Design parameter optimization	
SCRF	Mass-production and quality control Superconducting material, cavity properties (electric field, resonance characteristics) Hub-lab functioning System performance stabilization (Stabilization of the performance and maintenance, including international transport of CM)	
Nanobeam	Minimizing the beam size and demonstrating stability Beam handling (DR, RTML, BDS, BD)*	
Accelerator elements - Positron source (e+) - Beam dump	e+ : Undulator-driven (polarization) or an electron-driven system (backup), heat balance of the dump , cooling, safety	
CFS	Basic Plan by assuming a model site, engineering design, drawings, survey, assessment	
common technical support	Safety (radiation, high-pressure gas, etc.) Communication and network	
Administration	General affairs, finance, int. relations, public relations Administrative support for ILC pre-lab	

European ILC preparation plan

Item/topic	Brief description	CERN	France CEA	Germany DESY	Time line
SCRF	Cavity fabrication including forming and EBW technology,	✓			2017-18
	Cavity surface process: High-Q & -G with N-infusion to be demonstrated with statics, using High-G cavities available (# > 10) and fundamental surface research		✓	✓	2017-18
	Power input-coupler: plug compatible coupler with new ceramic window requiring no-coating	✓			2017-19
	Tuner: Cost-effective tuner w/ lever-arm tuner design	✓	✓		2017-19
	Cavity-string assembly: clean robotic-work for QA/QC.		✓		2017-19
Cryogenics	Design study: optimum layout, emergency/failure mode analysis, He inventory, and cryogenics safety management.	✓			2017-18
HLRF	Klystron: high-efficiency in both RF power and solenoid using HTS	✓			2017- (longer)
CPS	Civil engineering and layout optimization, including Tunnel Optimization Tool (TOT) development, and general safety management.	✓			2017-18
Beam dump	18 MW main beam dump: design study and R&D to seek for an optimum and reliable system including robotic work	✓			2017- (longer)
Positron source	Targetry simulation through undulator driven approach			✓	2017-19
Rad. safety	Radiation safety and control reflected to the tunnel/wall design	✓			2017 – (longer)

European ILC preparation plan

European Strategy input document

The International Linear Collider A European Perspective

Prepared by: Philip Bambade¹, Ties Behnke², Mikael Berggren², Ivanka Bozovic-Jelisavcic³, Philip Burrows⁴, Massimo Caccia⁵, Paul Colas⁶, Gerald Eigen⁷, Lyn Evans⁸, Angeles Faus-Golfe¹, Brian Foster^{2,4}, Juan Fuster⁹, Frank Gaede², Christophe Grojean², Marek Idzik¹⁰, Andrea Jeremie¹¹, Tadeusz Lesiak¹², Aharon Levy¹³, Benno List², Jenny List², Joachim Mnich², Olivier Napoly⁶, Carlo Pagani¹⁴, Roman Poeschl¹, Francois Richard¹, Aidan Robson¹⁵, Thomas Schoerner-Sadenius², Marcel Stanitzki², Steinar Stapnes⁸, Maksym Titov⁶, Marcel Vos⁹, Nicholas Walker², Hans Weise², Marc Winter¹⁶.

¹LAL-Orsay/CNRS, ²DESY, ³INN VINCA, Belgrade, ⁴Oxford U.,
⁵U. Insubria, ⁶CEA/Ifu, U. Paris-Saclay, ⁷U. Bergen, ⁸CERN, ⁹IFIC,
U. Valencia-CSIC, ¹⁰AGH, Kraków, ¹¹LAPP/CNRS, ¹²IFJ PAN,
Kraków, ¹³Tel Aviv U., ¹⁴INFN, ¹⁵U. Glasgow, ¹⁶IPHC/CNRS.

	SCRF	HLRF	Sources	Damping Rings	Instru- mentation	Beam Dynamics	Beam Delivery System	Cryogenics
CERN		C,O	O	G,C,O	C,G	C,G	C,G	O
France	X,E,G		G		A,G	G	C,G	
Germany	X,G	X	G	G	X	G		X,O
Italy	X,E,G			G				
Poland	X,E		O		E,O			X,E,O
Russia	X		G					
Spain	X,E				A		C,G	
Sweden	E						G	
Switzerland					X,C			
UK	E		G	G	A,C,G	C,G,A	C,G,A	

TABLE III. European expertise relevant for ILC accelerator construction, based on experience in the recent past. This is based on two major construction projects, the E-XFEL (X) and the ESS (E), several more R&D oriented efforts namely the GDE/LCC (G), ATF-2 (A), CLIC (C) and experience in other accelerator projects (O)

ILC Project Update

Shin MICHIZONO

KEK/Linear Collider Collaboration (LCC)

- *ILC area systems*
 - *Electron source*
 - *Positron source*
 - *Damping ring*
 - *RTML (bunch compressor)*
 - *Superconducting RF*
 - *Final focus*
 - *Beam dump*
 - *CFS*
-
- *ILC preparation (US, Japan, Europe)*
- *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
- *Summary*

Recommendations on ILC Project

KEK published “Recommendations on ILC Project”
based on the discussion at the international WG.

Recommendations on ILC Project Implementation

High Energy Accelerator Research Organization (KEK)

October 1, 2019

<https://www.kek.jp/en/newsroom/2019/10/02/1000/>

https://www2.kek.jp/ilc/en/docs/Recommendations_on_ILC_Project_Implementation.pdf

TABLE OF CONTENTS

1. Introduction	1
2. International Cost Sharing for ILC Construction and Operation	3
2.1. General Principles	3
2.2. Sharing of ILC Construction Cost	4
2.2.1. Civil Engineering	4
2.2.2. Conventional Facilities	4
2.2.3. Superconducting RF and Accelerator Components	5
2.2.4. Sharing of Person-Power Contributions during Construction of the Accelerator	5
2.2.5. ILC Laboratory Central Budget During Accelerator Construction	6
2.3. Sharing of ILC Detector Construction and Operation	7
2.4. Function of the ILC International City	7
2.5. Sharing of Operational Cost	8
2.6. Sharing of the Decommissioning Cost	8
3. Organization and Governance	9
3.1. Introduction	9
3.2. ILC Pre-Lab	10
3.2.1. Host Laboratory and Member Laboratories	10
3.2.2. Mandate	10
3.2.3. Organization	11
3.2.4. Funding	11
3.2.5. Project Management	12
3.2.6. Preparation for Mass Production and Towards Hub Laboratories	12
3.2.7. Regional Design Offices	12
3.2.8. Interplay between the Pre-Lab and Inter-governmental Negotiations	13
3.3. ILC Laboratory	13
3.3.1. Legal Basis	13
3.3.2. Governance and Organizational Structure	14
3.3.3. Council Representation and Voting Structure	14
3.3.4. Laboratory and Project Management	15
3.3.5. Interface between ILC Laboratory and Experiments	16
4. Technical Preparation Plan in Response to MEXT's ILC Advisory Panel and the Science Council of Japan (SCJ)	17
4.1. Technical Preparation Plan of the Main Preparatory Phase	17
4.2. Specific Items Identified by MEXT's ILC Advisory Panel and the SCJ report	18
5. Summary	23
Appendices	24
A. Charge to KEK International Working Group on the ILC Project	24
B. Member List of KEK International Working Group on the ILC Project	25
C. Member List of the Preparatory Group	25
D. Meeting Records	25
E. Current Status of ILC Accelerator	26
E.1. ILC 250 Accelerator Overview	26
E.2. ILC Accelerator Preparation Status	26
E.2.1. Superconducting RF (SCRF) cavities	26
E.2.2. Positron Source	27
E.2.3. Damping Ring	29
E.2.4. Interaction Region	29
E.2.5. Beam Dump	30

Topics on ILC advisory panel's report

Table 4.1: Summary of the ILC Advisory Panel's Discussions to Date after Revision. The quoted page numbers refer to those of the ILC Advisory Panel's report.²¹

Page #	R&D Issues
5, 13, 32	[Damping Ring] There still remain issues on several subsystems, such as beam dump, positron source, electron source, <u>beam control</u> , and the <u>injection/extraction of the damping ring</u> .
32	[Beam Dump] The <u>whole beam dump system</u> should be developed in the main preparatory phase. The required technologies include durability of the window, where continuous high-power beam pass through, and its maintainability and resistance to earthquakes.
32,33	[Positron Source] The helical undulator scheme is adopted as the positron source. It contains some technologies under development such as the <u>cooling of the target</u> irradiated by the gamma rays from the undulator and the <u>replacement method of the activated target</u> .

Summary of the ILC Advisory Panel's Discussions to Date after Revision

http://www.mext.go.jp/component/b_menu/shingi/toushin/__icsFiles/afieldfile/2018/09/20/1409220_2_1.pdf

Topics on report of Science Council of Japan

Table 4.2: Technical issues pointed out in the report by the Science Council of Japan.²²

R&D Issues
[SCRF] The design reference value for the SCRF acceleration gradient of 35 MV/m is based on the technical level that is currently achievable. It will be necessary to achieve this reliably and with a <u>good yield including automation techniques</u> ; further performance improvement is also desired.
[SCRF] It is foreseen that the bulk of the SCRF cavities will be provided through in-kind contribution from the participating countries. An important issue will be the <u>quality assurance that maintains the compatibility</u> among them.
[Positron Source] In the main preparatory phase, it is planned that the prototype of the <u>rotating target</u> will be made and the <u>magnetic focusing system</u> immediately after the positron source will be developed. The technology selection is to be made by the second year of the main preparatory phase. The strategy should be clarified, taking into account the R&D cost.
[Interaction Region] The technology for the control and feedback system related to the <u>beam focusing and position control</u> needs be established. The acceptable level of microtremor in the interaction region needs to be quantified.
[Beam Dump] The soundness monitoring of the <u>window material</u> , the concrete design for a remote-controlled <u>replacement/exchange system</u> , and the detail of the reaction between a high energy beam and water need to be adequately studied during the main preparatory phase.

Technical preparation

4.1. Technical Preparation Plan of the Main Preparatory Phase

The technical preparation plan defines all activities necessary during the main preparatory phase to prepare for the construction phase of the ILC. It is part of the KEK-ILC Action plan, which describes the ILC project in three phases: (a) pre-preparatory phase, (b) main preparatory phase, and (c) construction phase (See Figure 3.1.). KEK released the KEK-ILC Action Plan in 2016. It was updated for ILC250¹⁶ in 2018.¹⁷ The KEK-ILC Action Plan includes the tasks necessary to address the specific technical issues pointed out by MEXT's ILC Advisory Panel (Table 4.1) and the SCJ report (Table 4.2). It also describes the human resources necessary in the main preparatory phase. The technical preparation plan will be conducted by the ILC Pre-Lab. The plan assumes that most of the preparatory tasks will be carried out through international collaboration.

The technical preparation plan described in the KEK-ILC Action Plan includes the following preparatory tasks and identifies the required budget:

- (a) development of accelerator systems and components that addresses MEXT's ILC Advisory Panel and SCJ technical concerns (approximately 20% of budget),
- (b) civil engineering (geological survey, engineering design, etc.) (approx. 30%),
- (c) Hub-Lab/pilot plant in Japan (approx. 20%),
- (d) detailed engineering design of accelerator components (approx. 10%),
- (e) labor cost in addition to existing human resources (approx. 20%).

SRF cavity and cryomodule production

SCRF cavity and cryomodule production: SCJ and MEXTs' ILC Advisory Panel had technical concerns about maintaining cavity quality during mass production and cryomodule assembly. The plan is to demonstrate prototype manufacturing using a new cost-effective production method on the scale of 1% of the full production, corresponding to about 100 cavities in the main preparatory phase. Half of the cavities will be produced in Japan and the other half in other regions/countries. The performance of the cavities will be evaluated to test their yields, and plug-compatibility will be checked. Other components, such as couplers and tuners, are also expected to improve in terms of performance; they will also be manufactured, and their yields will be evaluated. Overall testing after assembling these parts into a cryomodule will be the final step of evaluating the performance as an accelerator component. The US and Europe have significant experience in cavity production and in formulation of countermeasures against performance degradation after cryomodule assembly. It is anticipated that Germany and the US will work on cost reduction of the cavity fabrication process and on reproducibility and high yield of cavity performance at the design gradient, while France could play a leading role in automation of cryomodule assembly.

SRF cryomodule transport

SCRF cryomodule transport: SCJ and MEXTs' ILC Advisory Panel also had technical concerns about the effect of cryomodule transport on cavity performance. Europe and the US have significant experience with land transportation of cryomodules. This experience needs to be extended to marine transport, while assuring that performance is maintained. In order to demonstrate performance preservation after transport, multiple cryomodules meeting ILC specifications will be manufactured in the main preparatory phase, and after initial performance testing, they will be delivered to another region, where their performance will be tested again. This work will be performed by international cooperation among KEK and institutes in the US and Europe by transporting cryomodules between two or more regions. It will also provide an opportunity to establish an SCRF hub laboratory in Japan.

Positron source

Positron source: SCJ and MEXT's ILC Advisory Panel had technical concerns about the rotating target, particularly its system design and the need for a plan for replacing activated targets, and about the magnetic focusing system. System designs for monitoring the reliability of the equipment and for remote handling to replace the rotating target will be performed in the main preparatory phase. Germany and the US possess experience from having studied positron sources for the ILC during the GDE process. In addition, CERN, France, and Russia possess expertise in positron sources. They could all be important partners for system design of the rotating target and the magnetic focusing devices. KEK will lead an industry-academia joint effort to develop the system design of the remote handling system for replacing the rotating target while ensuring environmental and radiation safety. In addition to these tasks pointed out by MEXT and SCJ, the KEK-ILC Action Plan recognizes that a system design of the photon dump system of the positron source is needed. CERN, Germany, and the US could become important partners in carrying out this system design of the photon dump, building upon Germany's extensive experience in system design for the undulator positron source and upon experience of CERN and the US in operating high-power beam dumps. Design of an electron-driven positron source as a backup technology will also be continued.

Damping ring

Damping Ring: MEXT's ILC Advisory Panel had technical concerns, as described in the MEXT's commissioned research/survey report ²⁰ [NRI], about several damping ring subsystems, including stability and reliability of the injection and extraction kicker systems and necessity for a high-resolution fast feedback system. System design of the fast feedback system in the damping ring could be performed by a collaboration between Japan and Italy, and tests will be performed at SuperKEKB at KEK. SuperKEKB has a circumference close to that of the ILC damping ring and a feedback system similar to ILC250. System development of the high-resolution fast feedback system for the ILC will be performed based on experience of the system operation and upgrade development at SuperKEKB. For its injection and extraction system, fast kicker magnets and a fast-pulsed power source have been developed, and multiple kicker systems have already been operated under beam operation. The remaining task is to ensure the stability and reliability over long-term operation. A long-term stability test of the fast kicker system will be performed at the Accelerator Test Facility (ATF) at KEK. Furthermore, international collaboration is foreseen on upgrading and improving the reliability of the fast kicker system for the damping ring. CERN and Italy could be important partners for the system design of the injection and extraction system, as they have been studying fast kickers since the GDE process.

Final focus

Interaction Region: SCJ stated technical concerns about the technology of the control and feedback system and about long-term stability of beam focus and position. The beam size at the ATF2 focal point is designed to be 37 nm, which is technically equivalent to a beam size of 7 nm for ILC250. At ATF2, the achieved beam size is smaller than 41 nm, which is consistent with the design beam size. The ILC prototype feedback system has been verified to satisfy all ILC requirements. Beam focusing and position control for the ILC final focus system have been studied at ATF2 at KEK. Based on the final-focus R&D experience at ATF2 at KEK and for CLIC, a long-term stability study of beam focusing and position control for the ILC final focus system will continue through collaboration with CERN and the UK.

Beam dump

Beam Dump: SCJ and MEXT's ILC Advisory Panel stated technical concerns regarding: reliability, earthquake protection, and stability of the window of the main beam dump; reaction between the high energy beam and water; and containment of activated water. In the main preparatory phase, the scheme for monitoring the integrity of the beam dump window will be studied and the system design for items such as the containment of activated water will be performed. CERN operates beam dumps for large accelerators and high-power beam dumps, and the US operates water-circulated beam dumps. They could be important partners for the system design of the beam dump. KEK will lead the system design of the beam dump facilities, ensuring environmental and radiation safety with cooperation from the government, industry, and the scientific community.

Technical preparation with international collaboration


Table 4.3: Accelerator-related technical preparation tasks and possible partners for international collaboration as envisioned by KEK.

Component	Issue	Summary of tasks	Candidates for collaboration
SCRF Cavity	Mass production incl. automation	Performance statistics, mass production technology	France, Germany, US
	Cryomodule transport	Performance assurance after transport	France, Germany, US
Positron Source	Rotating target	Exchanging target, system design	CERN, France, Germany, US + industry-academia efforts
	Magnetic focusing system	System design	France, Germany, Russia, US
	Photon dump ²³	System design	CERN, Germany, US
Damping Ring	Fast kicker	Test of long-term stability, system design	CERN, Italy
	Feedback	Test at SuperKEKB	Italy
Interaction Region	Beam focus/position control	Test of long-term stability	CERN, UK
Beam Dump	Total system	System design	CERN, US
	Beam window, cooling water circulation	Durability, exchangeability, earthquake-resistance	CERN, US + industry-academia efforts

ILC Project Update

Shin MICHIZONO

KEK/Linear Collider Collaboration (LCC)

- *ILC area systems*
 - *Electron source*
 - *Positron source*
 - *Damping ring*
 - *RTML (bunch compressor)*
 - *Superconducting RF*
 - *Final focus*
 - *Beam dump*
 - *CFS*
 - *ILC preparation (US, Japan, Europe)*
 - *Technical preparation in “Recommendations on ILC Project”*
 - *MEXT and SCJ’s comments*
 - *Superconducting RF*
 - *Positron source*
 - *Damping ring*
 - *Final focus*
 - *Beam dump*
-  • *Summary*

Summary

- *Most of the ILC accelerator parameters **have been demonstrated at the various facilities.***
- *SRF **Technology matured** based on the success of **European XFEL** (10% scale of ILC Main linac).*
- *ILC preparation:*
 - *ILC **cost reduction R&Ds** are ongoing under US-Japan cooperation and ILC improvement adopting these results are considered at US.*
 - *KEK issued ILC action plan.*
 - *European ILC preparation plan as “E-JADE” report was summarized.*
- *KEK published **“Summary of Recommendations on ILC Project”** based on the discussion at the international WG.*
- *The technical preparation plan **in response to reports by ILC Advisory Panel** organized by MEXT and the Science Council of Japan is presented.*
- *The plan identifies **technical tasks to be carried out through international collaboration.***


Thank you for your attention

ILC beam parameters

	ILC		
	initial	L upgr.	500 GeV
c.m. energy [GeV]	250	250	500
rep. rate [Hz]	5	5/10	5
no. bunches / pulse	1312	2625	1312/ 2625
bunch population [10^9]	20	20	20
av. beam current I_b [μA]	21	21/42	21/42
IP beta function β_x^* [mm]	13	13	11
IP beta function β_y^* [mm]	0.41	0.41	0.48
IP geometric emittance ϵ_x [pm]	20	20	20
IP geometric emittance ϵ_y [fm]	140	140	70
rms IP beam size x [nm]	516	516	474
rms IP beam size y [nm]	7.7	7.7	5.9
luminosity enhancement H_D	2.55	2.55	2.26
total luminosity L [$10^{34}/\text{cm}^2\text{s}^1$]	1.35	2.7/5.4	1.8/3.6
luminosity in top 1% $L_{0.01}/L$	73%	73%	58.3%
electrical site power [MW]	115	135/185	163
helium inventory [t]	43	43/85	85
site length [km]	20.5	20.5/31	31
integrated luminosity [fb^{-1}/yr]	100	300	600

Tritium

- ILC250 typical operation generates Tritium of $\sim 3.6\text{TBq/year}$.
- There are about 223 TBq annually in the rain throughout Japan.



https://www.meti.go.jp/earthquake/nuclear/osensuitaisaku/committee/takakusyu/pdf/008_02_02.pdf (in Japanese)

ILC construction cost summary

Summary of the ILC Advisory Panel's Discussions to Date after Revision

http://www.mext.go.jp/component/b_menu/shingi/toushin/_icsFiles/afieldfile/2018/09/20/1409220_2_1.pdf

Item	500GeV ILC (original plan)	250GeV ILC (revised plan)			
		Cost estimation presented at the TDR WG	Option A (250GeV ILC as a Higgs factory)	Option A' (Incorporated results from cost reduction R&D)	
※The cost estimates listed below in (1) to (7) is a summary reported by the research community. It should be necessary to pay attention to additional cost risk possibly caused by the risk factors and technical issues described in the Section 3, in this TDR-WG report.					
Construction of the ILC accelerators and detectors	(1) Accelerator (2) Detectors	1,091.2 billion yen	735.5 ~ 803.3 billion yen	785.3 ~ <u>803.3</u> billion yen	<u>735.5</u> ~ 753.5 billion yen
(3) An additional cost arising from inaccuracy and items described in the Section 3 of the report may be added					
(1) Accelerator (ref. TDR) [revised]		990.7 billion yen	635.0 ~ 702.8 billion yen	684.8 ~ 702.8 billion yen	635.0 ~ 653.0 billion yen
Civil engineering and construction	830.9 billion yen	169.0 billion yen	515.2 ~	111.0 ~ 129.0 billion yen	111.0 ~ 129.0 billion yen
Accelerator construction		870.9 billion yen	583.0 ~	404.2 ~ 454.0 billion yen	454.0 billion yen
Labor		159.8 billion yen	583.0 billion yen	119.8 billion yen	119.8 billion yen
(2) Detectors and related expenditures (ref. TDR) [No change]		100.5 billion yen	100.5 billion yen	100.5 billion yen	100.5 billion yen
Detector construction		76.6 billion yen	76.6 billion yen	76.6 billion yen	76.6 billion yen
Labor		23.9 billion yen	23.9 billion yen	23.9 billion yen	23.9 billion yen
(3) Uncertainty (ref. TDR) [No change]		About 25% of (1)+(2)	About 25% of (1)+(2)	About 25% of (1)+(2)	About 25% of (1)+(2)
※Inaccuracy: Only the inaccuracy in the cost estimation is included. What is not included are technical risks, extension of construction period and change in market price.					
(4) Operation (ref. TDR) [revised]		49.1 billion yen	36.6 ~ 39.2 billion yen	39.2 billion yen	36.6 billion yen
Utilities and maintenance		39.0 billion yen	29.0 ~ 31.6 billion yen	31.6 billion yen	29.0 billion yen
Labor		10.1 billion yen	7.6 billion yen	7.6 billion yen	7.6 billion yen
(5) Other expenditures (not in TDR)					
Preparatory cost (Design, R&D, Environmental assessment, training, technology transfer, management and administration, including labor cost)		Not estimated	[New estimation] 23.3 billion yen	23.3 billion yen	23.3 billion yen
Not estimated in TDR		Not estimated	Not estimated	Not estimated	Not estimated
land acquisition, living environment for overseas researchers, access road, infrastructure such as lifeline, computing center			[New estimation] Waste and spring water disposal, power transmission and substations, low voltage supply		
		(6) Contingency	About 10% of project cost (accelerators+detectors+operation*) (ref. PIP)		
		[New estimation]	Reserve fund for unexpected expenditure.	*annual operation cost × operation years	
		(7) Decommissioning	Equivalent to 3 years of operation.		
		[New estimation]	Accelerator components will be re-used, for which storage facilities should be prepared.		