



International Workshop on Future Linear Colliders

**LCWS2019** Sendai  
October 28 – November 1

# Infrastructure News for CERN's FCC and CLIC studies

John Osborne CERN

31 October 2019 – Sendai, Japan



## Cost and schedule estimate

compatible with the CDR baseline for all 3 machines: FCC-hh, FCC-ee and FCC-eh

Refinement of results (fire compartments, caverns spacing)


**Additional ILF studies (cash flow, spoil volume per site, HL-LHC cost comparison)**



## HE-LHC

Requirements gathered from cryogenics, electrics and HVAC, which determined the modifications needed for HE-LHC for civil engineering

Cost estimate produced



## Spoil Management

Study of the molasses re-use (approx. 9 million cubic meters of spoil)

Samples tested from HL-LHC sites



## Optimisation of tunnel alignment

Tunnel layout optimisation based on geology, shafts depth, construction risks and surface sites

Potential surface areas identified following first review with host states



## Ongoing work:

- Surface site investigation
- Site investigation planning
- Spoil management study
- Transfer line design

May 2018

Aug. 2018

Sep. 2018


Dec. 2018

Jan.- June 2019

Ongoing

CDR volumes submitted to  
European Strategy for Particle  
Physics Update

Underground civil infrastructure for FCC - 3D schematic (not to scale)



## Shafts:


Experimental Shafts:

15 m dia. + 10 m dia.

Service shafts:


12 m dia.

Magnet delivery shaft: 18 m




## Alcoves

- 25 m x 6 m x 6 m
- Located at 1.5km spacing



## Service Caverns

- 25 m x 15 m x 100 m



c Small Experimental Caverns  
30 m x 35 m x 66m



Large Experimental Caverns  
35 m x 35 m x 66 m

Beam Dump Caverns  
• 10 m x 10 m x 50 m

## Tunnels:


- 97.75 km of 5.5 dia. machine tunnel
- Approx. 8 km 5.5 dia by-pass tunnels

- Would be constructed at the same time as FCC-hh
- Infrastructure must be able to accommodate both machines.
- Enlargements required at experiment points A and G.





Structure	Quantities	Description	Applicable Section from the Baseline Design
Machine Tunnels	9,091m	5.5mID tunnel	Machine Tunnels
Service Shafts	2No	9mID shaft	9m shaft with same support of the 10mD Experiment Shafts
Service Caverns	2No	25m span, 50m long cavern	Service Cavern
Injection Cavern	1No	25m span, 50m long cavern	Service Cavern
Dump Cavern	1No	16.8m span, 90m long cavern	Junction Cavern
Junction Cavern with the FCC before Point L	1No	25m span, 50m long cavern	Service Cavern
Junction Cavern with the FCC after Point L	1No	25m span, 50m long cavern	Service Cavern
Junction Caverns between Machine Tunnels and FR Galleries	3No	16.8m span, 20m long (x2), 100m long (x1) caverns	Junction Cavern
FR Galleries	2No	5.5m span, 1070m long tunnel	Bypass Tunnel
Waveguide Connections	50No	1mD, 10m long	Klystron Connections
Connection Tunnel	4No	3m span	Connection Tunnels



Alignment Shafts Query

Choose alignment option  
V4variation\_2017-5 ☐

Tunnel elevation at centre: 322mASL

Grad. Params

Azimuth (°): -75.5

Slope Angle x-x(%): 0.3


Slope Angle y-y(%): 0.08

**LOAD** **CREATE** **UPDATE** **CALCULATE**


Alignment centre

X: 2499941 Y: 1107760

	Angle	Depth	Angle	Depth
LHC	38°	48m	-41°	88m
SPS		121m		127m
T12		121m		127m
T18		51m		119m



Point	Actual	Shaft Depth (m)			Geology (m)		
		Molasse SA	Wildflysch	Quaternary	Molasse	Urgonian	Limestone
A	166	0	0	13	153	0	0
B	123	0	0	29	94	0	0
C	130	0	0	47	83	0	0
D	240	45	0	40	155	0	0
E	79	0	0	79	0	0	0
F	558	0	0	139	419	0	0
G	259	0	0	13	246	0	0
H	230	0	0	0	230	0	0
I	193	0	0	13	181	0	0
J	237	0	0	6	231	0	0
K	51	0	0	36	15	0	0
L	175	0	0	24	151	0	0
Total	2442	45	0	439	1958	0	0



97.75km tunnel circumference


~90 % molasse – suitable ground for tunneling. Only one sector in limestone.

3720 m sum of shaft depths


558 m deepest shaft (F): proposed to be replaced with an inclined tunnel

# Typical tunnel cross section

Steel structure with passive fire protection. Connection:



5.5m inner diameter



Pre-cast concrete segmental lining


Cast-in-situ concrete invert

Safety compartments




Pre-cast concrete element



FCC-ee





FCC-hh



# Experimental points cavern layouts



- With a 10 m spacing it is feasible but a high strength concrete pillar is required.



- With 45 m spacing in good molasse, the rock pillar alone is sufficient.
- Cheapest and lowest risk option for CE



# Inclined access tunnel at point F

Option	558 m Shaft	10% inclined access	15% inclined access
Excavation length	558 m (12 mID)	3820 m (9.0mID)	2750 m (9.0mID)
Total duration (months)	22.2	25.8	23.2
Relative CE Cost	1	1.08	0.78
Advantages	<ul style="list-style-type: none"> <li>Shorted length of services</li> </ul>	<ul style="list-style-type: none"> <li>Improved surface site location and access</li> <li>TBM ready in cavern for tunnel excavation</li> </ul>	<ul style="list-style-type: none"> <li>Improved surface site location and access</li> <li>TBM ready in cavern for tunnel excavation</li> </ul>
Disadvantages	<ul style="list-style-type: none"> <li>Baseline lift mechanism not feasible</li> <li>Surface site has difficult access</li> </ul>	<ul style="list-style-type: none"> <li>Increased length of services</li> </ul>	<ul style="list-style-type: none"> <li>Increased length of services</li> <li>Transport method at 15% to be confirmed</li> </ul>




Existing LEP transfer tunnel TI18 15% from SPS to LHC

Whole project cost and schedule implications, including transport and services, still to be evaluated.

## Additional construction lots

- 2 no. Shafts near the LHC for the connection tunnels LHC-FCC
- 2 Beam transfer tunnels

**Mixshield TBM used for tunneling under Lake Geneva**



## Intermediate Access Adits

- Necessary to cope with overall time schedule to meet deadlines for machine installation

**Project divided in 12 construction lots**

## Construction techniques:

- 1) TBM tunnels (red)
- 2) Mined tunnels (blue)

**Access to main tunnel works through:**

- Shafts at 11 points
- Sloped Access adit at 1 point (instead of 570 m shaft)

# Spoil Management

Extraction Site	Volume (m <sup>3</sup> )			
	Soft Ground	Limestone	Molasses	Total
Construction Shaft at LHC1	11,031	0	133,735	144,765
Construction Shaft at LHC2	0	0	202,589	202,589
Shafts at Point A	26,469	0	791,948	818,417
Shafts at Point B	35,161	0	326,482	361,643
Shaft at Point C	181,807	0	385,920	567,727
First Construction Tunnel at Point D	0	0	709,452	709,452
Shaft at Point D	15,992	8,806	668,961	693,760
Second Construction Tunnel at Point D	0	0	235,355	235,355
Shaft at Point E	6,528	0	174,792	181,320
Tunnel at Point F	0	1,206	375,414	376,621
Shaft at Point G	33,086		471,215	504,301
Construction Tunnel at Point H	0	244,081	750,620	994,701
Shaft at Point H	0	7,329	421,401	428,730
Shaft at Point I	6,528	0	796,634	803,161
Shaft at Point J	6,528	0	805,629	812,157
Shaft at Point K	13,381	0	610,972	624,353
Shafts at Point L	29,990	0	671,700	701,690
<b>Total Spoil Volume</b>	<b>366,500</b>	<b>261,422</b>	<b>8,532,821</b>	<b>9,160,743</b>

Assumed bulking factor of 1.3









FIGURE 14-1: SPOIL SCHEDULE FOR LHC, A, B AND LHC1



**Production of up to 42,000m<sup>3</sup> per month**  
**9million cubic meters to dispose**  
**Can the molasse be re-used?**





*FCC-eh underground: 430MCHF*

*Two additional experimental points and associated civil infrastructure*


*\*The expected accuracy range is between -30% and +50% for feasibility stage*



- Information near to CERN is strong due to previous experience on LEP/LHC.
- Multiple deep boreholes in the area.

- Alignment close to limestone rockhead.
- The exact location and angle of the limestone/molasse interface undefined.

- Limestone formation known, but characteristics and locations of karsts unknown.




- Location of the interface between molasse and molasse subalpine not certain, tunnel alignment in proximity.

- Seismic and borehole information for lake crossing from proposed road tunnel, but layered nature of lake bed leads to uncertainty.

- Moraine/molasse interface not certain, cavern close to interface.
- Lack of deep boreholes in area.

- No deep borehole information available in the area.
- Complex faulted region.
- Molasse/limestone interface uncertain.



# Schedule for preparatory phase

CDR



European Strategy Update 2020



	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028
LHC operation	LS2		LHC run3			LS3			LHC run4	
CERN feasibility	Alignment optimisation									
Site investigations		Feasibility SI	Phase 1	Phase 2	Phase 3					
Consultant Contracts		Contract and tender strategy		Market Survey	Tender and Award	Preliminary Design	Tender Design		Construction Design	
Construction								Market Survey	Tender and Award	
EIA and permitting documents	EI and permitting documentation									Start of construction



## **Feasibility SI** **(2020-2021)**

- Walkover survey
- Geophysical investigation of all the access points, Geneva Lake crossing, Rhone and Arve Valley



## **Principal SI (2022-2023)**

**Phase 1** – site investigations required for the development of preliminary design

**Phase 2** – confirmation of geological profiles and engineering design parameters

Types of site investigations:

- Boreholes
- Site testing (eg insitu stress test, point load testing, SPT, CPT, permeability tests)
- Rock laboratory testing (eg uniaxial compressive strength, petrographic studies)




## **Additional SI** **(2024-2025)**

**Phase 3** – additional explorations needed in order to obtain a reliable cost estimate




# Ongoing work and future steps

- A further round of alignment optimisation following input from surface site review



Geology and construction risks


## Machine shape



## Access (vertical shafts / inclined tunnels)

Existing infrastructure (eg road networks, buildings) and future developments

Environmental protected areas




- ❑ Continuous desktop study of geology (collaboration with geological survey public institution and engineering consultants)
- ❑ Exploring GIS tools and alignment optimisation software - Workshop with industries at CERN held in October 2019 on tunnel alignment tools and tunnel monitoring :

<https://indico.cern.ch/event/823271/>

Long term tunnel monitoring for maintenance should be built into designs for ILC at concept stage



- ❑ Site investigations planning
- ❑ Spoil management study
- ❑ Transfer line design





## Other Studies

HE-LHC 3D schematic  
(not to scale)




HE-LHC tunnel cross-section showing enlargement for fire door (548 m spacing)

- Existing LHC infrastructure
- HL-LHC infrastructure
- HE-LHC infrastructure

Angel Navascues – SMB-SE

HE-LHC: capital cost per domain



**Preliminary cost estimate produced for civil engineering: ~300 MCHF**


- Civil Engineering 300 MCHF, 4%
- Technical Infrastructure 800 MCHF, 11%
- Machine 5000 MCHF, 69%
- Injector & transfer lines 1100 MCHF, 15%

Michael Benedikt,  
Physics at FCC,  
4 March 2019


For HE-LHC modifications to existing LHC infrastructure are required to house a new accelerator:

- New cryogenic caverns and electrical alcoves
- New access shafts
- New buildings for cryogenics, electrical and ventilation equipment
- Installation of fire separation walls including extension of the tunnel envelope every 548 m
- Partial refurbishment of LHC Sector 3-4

## LHC tunnel profile (sector 3-4 in limestone)



**1999 'Submarine' proposal**  
 – heavy steel lining of  
**600m section** - Rejected  
 because of high costs and  
 reduction of tunnel  
 diameter




**Water inflows during LEP construction**

## Tunnel inspection 2019 (current condition of sector 3-4)




**Continuous monitoring, maintenance and refurbishment works are necessary to extend the lifetime of the LHC tunnel for the use of a future particle collider.**









Variable geology – mainly soft ground : Bresse marls and clay. Locally sandstone and limestone.  
Some borehole show presence of gypsum.








FCC tunnel profile




- An transfer line of 60km length connects LHC to FCC crossing through the Jura Mountains. This raises risks associated to tunnelling through limestone such as karstic features, water inflow and instability during excavation.
- High overburden (up to 1300m) and very deep shafts in the Jura.






FCC 90km racetrack with 11km straight sections & CLIC 380GeV 11km tunnel






## TOT output for FCC 90km racetrack + 11km CLIC



More layouts combining FCC and CLIC have been studied.

# What next for FCC (and/or CLIC ?!) : Long Term LHC Plan



# Site investigation planning and pre-construction planning (FCC or CLIC similar)


Conceptual  
Design Report



European Strategy  
Update 2020



FCC pre-construction schedule	2019				2020				2021				2022				2023				2024				2025				2026				2027				2028								
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4									
LHC Operation Period					LS2				LHC run 3												LS3				LHC run 4																				
CERN feasibility	Alignment optimisation																																												
Site Investigation					Feasibility SI (geophysics & walkover surveys)				Principal SI - Phase 1				Principal SI - Phase 2				Principal SI - Phase 3 Additional SI as necessary																												
Consultant Contracts					Contract and tender strategy				Market Survey				Tender and Award				Preliminary design				Tender design				Construction Design																				
Construction Contracts																													Market Survey				Tender and Award												
EIA and permitting documents	Environmental Impact Assessment and permitting documentation																																												

**Start of Construction**

★ Start of Construction

## Types of site investigation:

- Collection of existing information
- Walkover survey
- Geophysical investigations (to define interfaces)
- Boreholes
  - Site testing (eg Insitu stress test, point load testing, SPT)
  - Rock laboratory testing.


## Phases:

Feasibility: Non-intrusive investigations to allow consolidation of alignment. Focus on access points, Lake crossing and the Rhone and Arve crossings.

Principal: Substantial portion of the geotechnical investigations. As a result of this, the alignment might need to be changed.

Additional: Any investigations required for the final design, emphasis on obtaining date required for the contractors.

Administration



**Thank you and Questions !**

**John Osborne**