
Report from the Technical Board



Katja Krüger CALICE meeting Montreal 4 March 2020







Since CERN CALICE meeting

- 2 Technical Board meetings since TB report during CERN meeting
- two testbeams since then:
 - MAPS ECAL (ALICE FoCAL): 25. Nov. 2. Dec 2019 in TB24, 17.-13.
 February 2020 in TB22 and 6.-13. April 2020 in TB22 at DESY
- > further planned testbeams in 2020 at DESY
 - SiECAL:
 - 23.-29 March in TB24
 - 30. November 6. December in TB22
 - AHCAL:
 - 16.-22. March in TB24
 - 1.-7. June in TB24
 - 17.23. August in TB24
 - 19.25. October in TB22
 - (CEPC) SciECAL: 17.-30. August
- > software




MAPS ECAL

1 week 25. Nov. to 3. December 2019 in TB24

MAPS prototype

- mTower
- Small digital electromagnetic calorimeter 3x3 cm² with 24 layers of 2 ALPIDE sensors and 3 mm W absorbers
- Pixel size 29.24 μm x 26.88 μm
- Readout based on ALICE ITS upgrade, with some adjustments
- Trigger scintillators from MPI Munich





MAPS ECAL


1 week 25. Nov. to 3. December 2019 in TB24

MAPS prototype

mTower


12 sensor layers

- Small digital electromagnetic calorimeter 3x3 cm² with 24 layers of 2 ALPIDE sensors and 3 mm W absorbers
- Pixel size 29.24 μm x 26.88 μm
- Readout based on ALICE ITS upgrade, with some adjustments
- Trigger scintillators from MPI Munich



MAPS ECAL

- 1 week 25. Nov. to 3. December 2019 in TB24: concentrating on many "technical" aspects in analysis
 - pedestal
 - noise dependence on thresholds
 - alignment
 - readout rate
 - discovered a problem limiting the readout rate to ~100 Hz, while expected ~5kHz
- 1 week 17.-24. February 2020 in TB22
 - full 24 layer mTower (1 layer broken)
 - readout rate problem understood (data transfer to PC)
 - concentrating on physics measurements
- > will have 1 more week 6.-13. April 2020 in TB22





SIECAL


- > beamtime:
 - 1 week 23.-29 March in TB24
 - 1 week 30. November 6. December in TB22
- step-by-step development towards full SiECAL prototype with ~25 layers
- > goals for March:
 - test new compact DAQ system with more layers (up to 15)
 - test FEV-12 COB with full silicon wafer
 - MIP calibration, stability, ...
 - EM showers: effects in shower core? shower profiles, ...
- goals for November:
 - up to 25 active layers
 - compact stack for all layers
 - integration: EUDAQ, beam telescope, ...



AHCAL

- > beamtime:
 - 1 week 16.-22. March in TB24
 - 1 week 1.-7. June in TB24
 - 1 week 17.- 23. August in TB24
 - 1 week 19.- 25. October in TB22
- goal for all: smaller tests of new hardware
 - Megatile: tested a full-size version in 2019, working on reduced cross-talk
 - KLauS ASIC: first stand-alone test with beam in March, then integration into AHCAL DAQ
 - CMS HGCAL tileboard prototype: first test with particles








SIECAL + AHCAL

- the beam times of SiECAL and AHCAL in March are back-to-back:
 - 16.-22. March and 23.-29 March in TB24
- in the medium term, combined tests of technological prototypes are a must
- decided to use the opportunity for a first test of combined running with a few layers in March
 - common 40 MHz clock provided by AHCAL CCC
 - hardware synchronisation based on micro-spill and BUSY signals
 - software still under discussion
 - had a fruitful meeting with the experts on 27 February, hardware and firmware modifications look small and feasible
 - will dedicate part of the AHCAL beamtime to these tests



CEPC SciECAL

- beamtime: 2 weeks 17.-30. August
- plan: operate a full SciECAL prototype in beam in 2020
- > status
 - all EBUs produced and tested electrically
 - all scintillator strips wrapped in ESR foil
 - finish assembly, commission and test with cosmics before shipping to DESY
- had asked for 2 weeks in October, August is probably too tight in time
 - some discussions with testbeam coordinators, hope for cancellations







Software

- central space for CALICE software is in svn
 - has serious short-comings
 - unclear long-term support
 - many people nowadays are used to git(hub)
- investigated several (git-based) options, all have their advantages and dis-advantages
- decided to go for gitlab (CERN-based)
- set up by Daniel, now need to fill it with life!
- CALICE software is based on ilcsoft; for the moment, DESY continues ilcsoft support



Conclusions

- 2018 saw completion of several important testbeam campaigns at CERN SPS
 - should not forget to acknowledge AIDA-2020 support in papers, proceedings, talks, posters, ... where appropriate
- 2019 more quiet (as expected), mostly smaller prototypes
 - important for first tests of new developments
- > 2020 will probably similar
- increased demand at DESY in 2019 and 2020, but we mostly got what we asked for

if we want to have successful tests of combined prototypes in 2021, we need to prepare them well, and 2020 is the time to do that!

