International Development Team

Technical Design Documentation and WBS for EDR
Benno List, DESY
IDT WG2 Meeting
5.1.2021

Accelerator activities at ILC Pre-lab phase



Technical preparations /performance & cost R&D [shared across regions]

- SRF performance R&D
- Positron source final design and verification

- Technical preparation
- · Nanobeams (ATF3 and related): Interaction region: beam focus, control and Damping ring: fast kicker, feedback
- Beam dump: system design, beam window, cooling water circulation
- Other technical developments considered performance critical

Final technical design and documentation [central project office in Japan with the help of regional project offices (satellites)]

- Engineering design and documentation, WBS
- Cost confirmation/estimates, tender and purchase preparation, transport planning, mass-production planning and QA plans, schedule follow up and construction schedule preparation

 Engineering Design Report (EDR)
- Site planning including environmental studies, CE, safety and infrastructure (see below for details)
- Review office
- Resource follow up and planning (including human resources)

Preparation and planning of deliverables [distributed across regions, liaising with the central project office and/or its satellites] Mass-production

- · Prototyping and qualification in local industries and laboratories, from SRF production lines to individual WBS items
- · Local infrastructure development including preparation for the construction phase (including Hub.Lab)
- Financial follow up, planning and strategies for these activities

CE, local infrastructure and site [host country assisted by selected partners]

- · Engineering design including cost confirmation/estimate
- Environmental impact assessment and land access
- Specification update of the underground areas including the experimental hall
- Specification update for the surface building for technical scientific and administrative needs

Civil engineering



TDR and Technical Design Documentation






Technical Design Report (TDR) <u>summarizes</u> TDD for publication

Technical Design Documentation (TDD) captures entire design efforts, results & rationale






ILC-EDMS <u>organizes</u> the Technical Design Documentation, providing **structure**, **traceability**, **version & configuration mgt.**, and **change control**



DT WBS and Documentation



- Technical Design Documentation is organized along WBS
- WBS: "A deliverable-oriented hierarchical decomposition of the work to be executed by the project team" [PMBOK]
- Different project phases are projects of their own, with their own WBS:
 - WBS for Technical Design Phase TDP
 - WBS for Prelab phase
 - WBS for constructionm phase
- In each phase, prepare WBS for next phase
 - Define WBS for prelab phase now
 - Define construction project WBS in prelab phase



http://www-fusion-magnetique.cea.fr/etn-qpn/ws-scheduling/EFDA%20Conference%20-%20Scheduling.pdf


Example: ITER WBS.

Top Level ist programme phase

Structure of TDD from TDR (TDP-II) phase




- WBS for Technical Design Phase II (TDP-II) was never fully formulated
- Provisional WBS used to structure Design Documentation
- Main Structure:
 - Accelerator systems
 - SCRF technology
 - CFS
 - Some cross cutting activities:
 AD&I, Costing, Project management, Documentation
 - Other Technical Areas (magnets, vacuum, ...) from RDR only present as parts of accelerator systems
- After Black December (12/2008), value engineering reduced to bare minimum, technical area groups outside SCRF non-existing -> No top-level element for Technical areas other than SCRF



DT Access to TDD



- New Web interface: https://edmsdirect.desy.de/treebrowser/ilc/
- Provides easy navigation through the TDR WBS and the associated documentation
- No log-in required
- Integrated preview of document PDF
- Documents are interrelated through links
- Link to EDMS interface also provided
- Some elements (costs!) are only available after log in with EDMS account, documents are visible only in full EDMS client



DT Design Register



- Design Register gives overview over design status of accelerator systems and their documentation
- Has a list of "mandatory documents" whose status is tracked
- Includes cross references
- Good practice: Prepare a list of artefacts / mandatory documents to be provided by the work packages
 - Drawings / CAD models
 - Schematics
 - Data sheets / specifications
 - Requirements
 - Calculations: Power, heat, costs, availability...
 - Procedure descriptions (installation, alignment, diagnostics, maintenance,...)





IDT WBS Structure for Prelab-Phase



- Guiding principles of a WBS:
 - Deliverable-oriented
 - Compatible with work organisation
- Example:
 - One group designing magnets solely for Damping Rings, as part of a separate DR design effort: "DR magnets" under "Damping Rings"
 - One group designing magnets for several (or all) accelerator systems as a separate effort:
 "Magnets" as separate Work Package
 - Decision on structure depends on how work is organized
 - Can change between project phases
 Can have a "Magnets " work package in prelab phase, and a "Damping Rings" work package including magnets in construction phase

- What are the deliverables in the Prelab phase?
 - Final deliverables: construction-ready design, project plan, cost book
 - Intermediate deliverables: Component counts, power estimates, requirements, design criteria...
 - EDR is ("only") a human-readable summary of these design deliverables

Deliverables

Accelerator activities at ILC Pre-lab phase



Technical preparations /performance & cost R&D [shared across regions]

- SRF performance R&D
- Positron source final design and verification

- Technical preparation
- Nanobeams (ATF3 and related) Interaction region: beam focus, control and Damping ring: fast kicker, feedback
- Beam dump: system design, beam window, cooling water circulation
- Other technical developments considered performance critical

Final technical design and documentation [central project office in Japan with the help of regional project offices (satellites)]

- Engineering design and documentation, WBS
- Cost confirmation/estimates tender and purchase preparation transport planning, mass-production planning and QA plans, schedule follow up and construction schedule preparation
- Site planning including environmental studies, CE, safety and infrastructure (see below for details)

 Engineering Design Report (EDR)
- Review office
- Resource follow up and planning (including human resources)

Preparation and planning of deliverables [distributed across regions, liaising with the central project office and/or its satellites] Mass-production

- Prototyping and qualification in local industries and laboratories, from SRF production lines to individual WBS items
- Local infrastructure development including preparation for the construction phase (including Hub.Lab)
- Financial follow up, planning and strategies for these activities

CE, <u>local infrastructure</u> and site [host country assisted by selected partners]

- Engineering design including cost confirmation/estimate
- Environmental impact assess ment and land access
- pecification update of the underground areas including the experimental hall
- Specification update for the surface building for technical scientific and administrative needs

Civil engineering

IDT Deliverables of the Prelab-Phase -> And who does it



- Accelerator design*
 - Overall integrated design -> AD&I
 - Sources, DR, RTML, ML, BDS -> Acc. Systems
 - Artefacts: Lattice, beam parameters, system description, imput for CFS design criteria (requirements), component counts, design for specific components, availability data,
- SCRF design and prototypes*
 - Cryomodules, cavities, couplers, tuners, SC quad, BPM, HLRF (klystrons, modulators, PDS), cryogenics -> SCRF groups
 - Artefacts: Component designs, technical data, prototypes, subsystem design, component unit costs, subsystem costs, production plans, requirements
- Technical components design*
 - Magnets, vacuum, diagnostics, LLRF, controls, dumps, collimators, survey and alignment, installation... -> Technical area groups
 - Artefacts: Component designs, technical data, prototypes, subsystem design, component unit costs, production plans, requirements

- Conventional facilities and site design*
 - Civil engineering (caverns, tunnels, surface buildings) design
 - Technical infrastructure (el. Power, water, HVAC, network, transport, safety, ...) designs
 - Site design (Campus, transport, water, power lines, housing...)
 - Artefacts: Requirements / design criteria, construction plans, costs, schedule, schematics, env. impact assessment,
- Project plan*
 - Cost estimate, cost book, project implementation plan, project schedule, construction project WBS and organisation, logistics plan, legal framework... -> project office
- Engineering plan
 - System architecture, Requirements, Risks, CAD model, Technical Documentation, QA plan...
- Outreach & PR material
 - Web site, videos, lectures, exhibitions... -> Outreach team

Possible 1st level elements of a Prelab WBS



THE ACCELERATOR (PRODUCT)

- Accelerator Design and Integration
 - Design the accelerator, its accelerator subsystems and their subsystem specific components
- SCRF and HLRF Technology
 - Design all SCRF and HLRF components and the cryogenic system, for the ML and other accelerator subsystems, produce prototypes, qualify vendors and hub labs, establish/qualify production sites and companies
- Accelerator Components
 - Design accelerator components (except SCRF/HLRF), including instrumentation and controls
- Conventional Facilities and Siting
 - Design all conventional facilities and the site

CROSS-SECTIONAL ACTIVITIES

- Project Management and Legal Affairs
 - Perform project management of the prelab phase (cost, schedule, ...)
 - Prepare Project Management of the Construction phase
- Systems Engineering and Quality Management
 - Support systems engineering processes of prelab phase (documentation, CAD, requirements, ...)
 - Prepare Systems Engineering processes for construction phase (all of the above, risk management, quality management, ...)
- Outreach and Public Relations
- Safety and Environment
 - Manage all safety, health, radiation and environmental protection issues

Possible 2nd Levels



Accelerator Design and Integration

- Accelerator System Integration
 - Integrate accelerator subsystems, provide overall design and performance
- Sources
 - Design electron and positron sources and specific components (undulator, target regions, gun and laser system)
- Damping Rings
- RTML
- Main Linac and Bunch Compressors
 - Design Main Linacs and Bunch Compressors, based on SCRF design
- BDS

SCRF and HLRF Technology

- Cryomodules
 - Design all L-Band cryomodules for Main Linac, sources
 - Produce, transport to and test prototypes in Japan
- Cavities
- Cavity Material
- Tuners
- Couplers
- Quad / BPM package
- Klystrons
- Modulators
- Waveguide distribution
- Cryogenics

Possible 2nd Levels, cont'd



Accelerator Components

- Magnets, Kickers and Power Supplies
- Vacuum
- Dumps and Collimators
- Instrumentation
- Controls and LLRF
- Installation, Supports and Girders
- Survey and Alignment

Conventional Facilities and Siting

- Civil Engineering
- Electrical Power
- Water Cooling
- Heating, Ventilation, Air Conditioning
- Site Activation

IDT Possible 2nd Levels, cont'd



Project Management and Legal Affairs

- Project Management and WBS
- Costs
- Schedule
- Project Risks
- Procurement
- Logistics
- Human Ressources
- Legal Affairs

Systems Engineering and Quality Management

- Technical Documentation
- Requirements Management
- Technical Risks
- Quality management
- Configuration Management
- Standards and Conformance
- Change Management

Outreach and Public Relations

Safety and Environment

- Safety and Health Protection
- Environmental Protection
- Radiation Protection

IDT WBS Structure and Costing



- Cost estimate from TDR phase
 - WBS based organized according to a WBS
 - Bottom-up add number * unit costs of all components
- Final result was reported in a matrix form: (accelerator systems) X (technical areas)
- Cost estimate is based on WBS of construction project – need not be identical with WBS of prelab phase!
- In strictly WBS based costing, a "Magnets" work package would contain all costs for fabrication of magnets, "installation" would contain costs of installation
 a parallel "Damping Rings" work package would not include these costs!
- Does not answer "How much do the Damping Rings cost?" or "Which components drive DR costs?"

- TDR WBS tried to answer these questions by a convention for levels 1/2 of WBS
 - 1: Accelerator systems
 - 2: technical areas
- Runs into many problems:
 - · CFS: two systems in one tunnel
 - Same components in different systems: How to handle one-off costs, quantity rebates, spares
- Strength of a WBS based costing is 100%rule: Every level is exactly the sum of its parts
- Reports on cost distribution are based on attributes, not on structure!
 - Distinguish atomic items from items that are summed up
 - Atomic items get attributes to allow all kinds of reports
 - Cost sharing over attributes must be possible (e.g. 75% BDS, 25% Sources)

DT Summary, Conclusions



- Define the deliverables of the Prelab phase
 - What designs have to be provided
 - Designs: How mature / detailed?
 - Ready for detailed design
 - Ready for call for tender
 - Ready for fabrication
 - Other documents: Cost book, schedule, legal documents, ...
 - EDR only summarizes these efforts
 -> EDR contents and structure to follow project organisation and results
- Reinstate accelerator system groups to design the accelerator
- Reinstate technical areas to design components -> input to accelerator design, CFS, project management

- Define artefacts that need to be provided by the work packages, with target dates:
 - Component specifications and data sheets, system overview, component counts, unit costs, heat loads, ...
 - Make sure necessary inputs are requested and provided in time (CFS heat loads require component counts and component data sheets, which require component specs from lattice design...)
- Cross-Sectional activities (project management, systems engineering)
 - Support Prelab phase
 - Prepare Construction phase



Reserve

IDT CFS documentation – Americas and Japan



CFS Design Criteria for all subsystems



Task Force to Study Issues to Construct ILC in Japan