

Data quality and Beam Test Performance SiW-ECAL TB@DESY 2021

Adrián Irlles (*AITANA group at IFIC – CSIC/UV*)
on behalf the SiW-ECAL team

IFIC
INSTITUT DE FÍSICA
CORPUSCULAR

AITANA
MATTER AND TECHNOLOGY

 UNIVERSITAT
DE VALÈNCIA
CSIC
CONSEJO SUPERIOR DE INVESTIGACIONES CIENTÍFICAS

CALICE

Ciemat
Centro de Investigaciones
Energéticas, Medioambientales
y Tecnológicas

IJCLab
Irène Joliot-Curie
Laboratoire de Physique
des 2 Infinis

LMR

LPSC
Grenoble

LPNHE
PARIS



OMEGA
Microelectronics

cnrs
IN2P3
Les deux infinis


 九州大学
KYUSHU UNIVERSITY

 東京大学
THE UNIVERSITY OF TOKYO





- ▶ **DESY offers non-spilled beams of 1-6GeV (e-, e+)**
- ▶ **15 layers with 1024 readout cells each**
 - More than any LHC calorimeter
 - But it fits in a suitcase
- ▶ **First week dedicated for commissioning**
 - Threshold optimization, single cell calibration, etc
- ▶ **Second week dedicated to electromagnetic showers**
- ▶ Mounting started monday afternoon
- ▶ Ready for data taking since wednesday morning
 - But it took us a bit more for problems with the movable stahe
 - **Since then: the smoother data taking :D**






► **First 4 layers have been “ressurrected”**

- Not operative before for different reasons


► **7 more layers have been “rebuild” → to adapt them to the new ultracompact DAQ (**heavy manipulation**)**

► **4 Layers new**

- 2 of them with sensors glued in two separated batches (one sensor for test, the other 3 one year later)



- ▶ **DESY offers non-spilled beams of 1-6GeV (e-, e+)**
- ▶ **15 layers with 1024 readout cells each**
 - More than any LHC calorimeter
 - But it fits in a suitcase
- ▶ **First week dedicated for commissioning**
 - Threshold optimization, single cell calibration, etc
- ▶ **Second week dedicated to electromagnetic showers**
- ▶ Mounting started monday afternoon
- ▶ Ready for data taking since wednesday morning
 - But it took us a bit more for problems with the movable stave
 - **Since then: the smoother data taking :D**




**Technical TestBeam
with new DAQ,
larger concentration (xyz) than ever**

<https://github.com/SiWECAL-TestBeam>

- ▶ **SiWECAL-TB-analysis** → code for commissioning, detector operation and technical analysis
 - Branch during the beam test: slboard_TB2020
 - New branch tfor analysis TB2021-Analysis (as master)
- ▶ SiWECAL-TB-Sim
 - Tools for simulation (DD4HEP based) and for digitization
- ▶ SiWECAL-TB-LCIO Analysis
 - For LCIO based analysis
 - Starting from event building (see H. Garcia's talk)
- ▶ Users/developpers: Y. Okugawa, J. Kunath, H. Cabrera, F. Jimenez, S. Tsumura

**SiWECAL-TB-Analysis is the
master code for “technical” studies.**



Simulation

- ▶ Define xml file with geometry
- ▶ Create data files (SimHits) + digitise them (CalorimeterHits) + get MIP calibration constants
 - Requires the knowledge of the thresholds per chip
 - + noise studies

ASCII
files

Build events

Physics w/ showers


Physics w/ MIPs
Validation of the simulationn. Fabricio

- ▶ Linearity (vs beam energy) –
- ▶ Shower profiles
- ▶ Shower studies with different angle incidences
- ▶ **More ?**
- ▶ **Requires the MIP/Pedestal calibration**


Basic performance: pedestals

- ▶ 15slabs x 16 ASIC x 64 chns x 15 sca =
- 230400 pedestal calibration constants


pedestal pos.



width of pedestal






ped_high_chip0_chn12_sca0




Basic performance: pedestals


- ▶ 15slabs x 16 ASIC x 64 chns x 15 sca =
- 230400 pedestal calibration constants



average of MPVs




- ▶ 15slabs x 16 ASIC x 64 chns =
 - 15360 single cell calibration constants
 - (shown here averages for each ASIC)



► We observe few unhomogeneities:

- Layers 7-10 have thicker sensors (larger signal)
- Issues during the gluing of the sensors of Layers 9-10 were reported (training of the gluing robot, different mix of glue used, manual interventions during the process)
- Layer 12 had one wafer replaced

average of MPVs





First quick mip calibration run

Holdscan MIPs vs Position scan MIPs

average of MPVs

average of MPVs



First quick mip calibration run

Long calibration run (position scan)
Were we observed problems with HV system

▶ **Beam tests are crucial to understand the hardware !!**

- New DAQ system and a mix of new and old layers
- Higher density and number of channels than ever in the project
- Unexpected situations that challenge the hardware only appear during testbeam (HV issue)

▶ Work is being done in several fronts

- Technical studies (pedestal calibration, noise, mip calibration, ...)
- Data analysis
- Simulation