# Technical Board report

Lucia Masetti JGU Mainz

**CALICE Collaboration Meeting** April 20th, 2021









# News since September

- 3 Technical Board meetings, last one just before the beginning of this session
- Testbeam readiness review of SiW-ECAL in October at IJCLab
- Testbeams:
  - At DESY: end of 2021 and beginning of 2022 SiW-ECAL and AHCAL standalone and combined
  - Dual readout: testbeams at FNAL in December and February
  - At CERN: still preliminary plan for 3x2 weeks for SiW-ECAL + AHCAL; SDHCAL; (CEPC) SciECAL + AHCAL
    - Waiting for official approval by SPSC for the last two slots
- Daniel Jeans informed me about his intention to step down as software coordinator
  - Thanks Daniel for 8 years of very active commitment to CALICE!





# SiW-ECAL readiness review

- Full day meeting at IJCLab
- Many thanks to Jiri Kvasnicka, MaryCruz Fouz and Wei Shen for their precious help as members of the panel!
- Report by the panel:
  - The panel finds the project in general in a very good state with the prototype running stably for weeks taking cosmics data proving the reliability of the system. Most of the concerns that were brought up during the review had already been considered by the team. They are aware of possible shortcomings and have clear plans for mitigation.
  - Recommendations for preparation, running, analysis of the data and further steps were given





### SPSC review


- Our 3 requests for 2 weeks beam time each at the SPS this year were seen as "6 weeks for CALICE" and we were required to go through a review by the SPSC
  - First 2 weeks for SiW-ECAL and AHCAL already planned for, approval by SPSC needed for the remaining slots
- Document submitted on March 23rd
- Meeting with reviewers on April 7<sup>th</sup> and presentation by Roman at the SPSC meeting April 12<sup>th</sup>
- Preliminary positive feedback for all slots this year
  - Logistics of CEPC-AHCAL still to be clarified
  - For the next years, requests might be made together with a long-term plan to be presented to the SPSC





### SPS schedule

### SPS user schedule for 2022









### SiW-ECAL in beam test @ DESY




### **Detector Setup**



Detector in beam position



### Hit maps of all 15 layers



- Stack operational
- Analysis ongoing
- Gearing up for upcoming beam test at CERN










### **CALICE Sc-ECAL – Readiness status**



- Successful beam test at BEPC-II Testbeam Facility at IHEP campus (2020)
  - E3 beam line: mixed particles with protons and pions (momentum: 300MeV-1.2GeV)
  - Mostly with low-energy hadrons; a very small fraction of electrons
  - Limited statistics due to the low beam rate (~1Hz)
- Conclusion: Sc-ECAL prototype demonstrated to be ready for beam tests
  - Tests with high energetic electrons and hadrons are mandatory for prototype validation














### **AHCAL Technological Testbeam Prototype**



- Large enough to contain hadron showers
  - 38 active layers of 72\*72 cm²
  - 4 HBUs per module
  - in total: 608 SPIROC2E ASICs, ~22000 channels
  - SiPMs: Hamamatsu S13360-1325PE
  - Overall weight 6t
- All modules interchangeable
- Built with scalable production techniques in ~2 years
- Operated in beam tests with muons, electrons and pions at CERN SPS in 2018
  - 3 weeks of beam time
  - Collected O(100) mio events
  - Very stable running
  - Nearly noise free
  - < 1 per mille dead channels</li>
- Main goal for upcoming beam test campaign is common running with electromagnetic calorimeters and testing of new technological developments 145<sup>th</sup> SPS-C Meeting – April 2022








13




### **AHCAL Prototype – New sensitive layers**



- Optimised for operation at circular colliders
- Each sensitive layer with 3 HBUs: each (24×72 cm<sup>2</sup>) hosts 108 tiles (40×40×3 mm<sup>3</sup>)
- DAQ optimised to achieve a much higher event rate
- New SiPM option: NDL-SiPM with high PDE, high pixel density and large sensitive area





- New AHCAL sensitive layers: status and plans
  - Successful tests with cosmic muons with two layers
  - 4 full layers assembled recently, soon followed by 20 more layers (mid-April)
  - All new layers planned to be ready before June







### **SDHCAL** – Beam test goals



#### Main goals:


- Apply a new calibration scheme (based on equalizing the response by applying different threshold value/ASIC) in order to improve on the SDHCAL response homogeneity.
- Study the difference of hadronic showers produced by protons, pions and kaons in order to exploit their differences in developing new PID techniques.


#### Other goals:

- Test SDHCAL with SiW ECAL
- Test the woven strips scheme
- Test first timing-SDHCAL layers (AiDAInnova)
- $\bullet\,$  Test  $\mu Well$  chambers as active layers by replacing a few GRPC

#### **Beam requirements:**

- Muons
- Pions, kaons, protons, from 10 to 90 GeV (pure hadrons)
- Low intensity beam ( < 1000 particle/cm2/spill)</li>











UNIVERSITĂT MAINZ

JOHANNES GUTENBERG






### Common beam tests



### Preparation on common SiW-ECAL AHCAL beam test



SiW-ECAL + AHCAL DAQ test @ DESY in March 2022



- Common beam tests are a particular strength of CALICE
  - Particle reconstruction with realistic setup
  - Early integration of full calorimetric systems
- Successful synchronisation of data recorded with SIW-ECAL and AHCAL
- Common running makes full use of EUDAQ tools (developed within European projects)





# Summary

- Looking for a new software coordinator
  - Suggestions for good candidates are welcome
- Many new testbeam data being collected and analysed
  - More upcoming testbeams, including at the CERN SPS
  - Our prototypes are mostly ready, logistics being clarified
- SPSC review in April
  - Preliminary feedback very positive, waiting for official confirmation



