




Sc-ECAL Status and Outlook

W. Ootani ICEPP, Univ. of Tokyo
on behalf of Sc-ECAL group

ILC Strategy Meeting, May. 3rd, 2022




Sc-ECAL Group

ILD R&D group



University of Tsukuba

CEPC R&D group



Institute of High Energy Physics
Chinese Academy of Sciences

Sc-ECAL Group

ILD R&D group



University of Tsukuba

CEPC R&D group









Institute of High Energy Physics
Chinese Academy of Sciences

→ Already with a scope beyond ILD

Sc-ECAL in a Nutshell

•Scintillator-Tungsten ECAL

- Scintillator strip (45mm×5mm×t2mm) read out by SiPM
- Virtual segmentation of 5×5mm² by strips aligned alternately in horizontal and vertical orientations
- Significant reduction of readout channels(10⁸→10⁷) retaining performance
 - Cost reduction
 - Power consumption reduction→ advantageous especially for CEPC





Brief History

We are here


• Physics prototype

- Scintillator ($45 \times 10 \times 3 \text{ mm}^3$) readout by WLS fibre+SiPM
- Demonstrated good performance (energy resolution and linearity) using 2-32GeV electron at Fermilab




• Technological prototype: single layer

- Scintillator strip ($45 \times 5 \times 2 \text{ mm}^3$) directly coupled to SiPM
- Strips are assembled on PCB with integrated readout electronics (“EBU”)
- 144 strips/EBU readout by 4 ASICs (SPIROC2b)



• Technological prototype: full layer

- Joint R&D with CEPC-ECAL group
- Scintillator strip ($45 \times 5 \times 2 \text{ mm}^3$) with SiPM
- 32 layers, $\sim 23.4 X_0$
- 210ch /EBU




Large Prototype


• Large technological prototype of Sc-ECAL

- Jointly developed by R&D groups for CEPC and ILD
- Full layers (32 layers)
 - Detection layer of 210×225mm² with 210 scintillator-strips
 - 30 layers with single SiPM readout
 - 2 layers with double SiPM readout
 - Absorber plate (3.2mm-thick 15%-85% Cu-W alloy)
 - Total material thickness $23.4 X_0$


Detection layer on EBU




Large prototype



Strip-SiPM coupling





Layout of detection layers




Large Prototype

•Super-layer

- Composed of two sets of EBU and absorber plate
- Strips are aligned alternately in horizontal and vertical orientations
- 16 super-layers in total




Top view




Bottom view

•Mechanical structure


- Mechanical structure with $17 \times$ slots for super-layer modules
- Whole setup can be rotated by 90° for cosmic ray test
- Air-cooling fans at both sides



Large Prototype DAQ



Data Collection of Sc-ECAL



Large Prototype Commissioning

- **No beam test performed yet due to pandemic**

- Sc-ECAL/CEPC-AHCAL combined test beam at CERN SPS in October 2022


- **Long LED run (~1 month)**

- SiPM calibration (gain, cross-talk, after-pulsing)
- Electronics calibration
- Stability test

- **Long cosmic ray run (~3 month)**

- MIP calibration
- Stability test
- Performance study
 - Detection efficiency, position resolution
 - Study with cosmic-ray induced shower

Prototype rotated by 90° for cosmic-ray test



Large Prototype

Performance



● Performance measurement with cosmic ray track

● Detection efficiency


- ~85%
- Inefficiency due to threshold and gap between strips

● Position resolution


- 1.5-2.3mm




CR event display with hit reconstruction



Detection efficiency



Position resolution





Large Prototype Performance


• Long-term stability

- SiPM gain
 - Very stable over one month
- MIP gain
 - Constant decrease of 5-10%/3months
 \leftrightarrow 1-2%/year @T2K ND280/INGRID
 - Under investigation. Electronics or scintillator?


SiPM gain without temp. correction



MIP stability with temperature correction




with temp. correction




Large Prototype Performance

• Study with cosmic-ray induced shower


- Good agreement between data and MC
- Small deviation for higher energy event
 - Likely due to problem of CR energy distribution in MC




Longitudinal profile



Transverse profile



Energy sum




Timing

Effect of TOF (res. 50ps) on particle ID performance


• Timing capability recognised as additional value by Sc-ECAL group

- Particle ID for charged hadron to cover inaccessible momentum region by dE/dx
- Rejection of pileup/off-timing BG
- Rejection of slow neutron events
- Improve PFA performance
- Hit position reconstruction in double SiPM readout
- ...





U. Einhaus, arXiv:2110.15115

Hit position resolution with double SiPM readout (Measured)



Truth cluster TOF distribution of real photon and fake photon clusters (CEPC)




Timing


- What we could do with scintillator+SiPM system?

- Our experience on similar detector in MEG II experiment

- Scintillator plate read out by multiple SiPMs connected in series
- Time pickup by waveform analysis (constant fraction)
- Excellent timing resolution down to **40 ps** with the best configuration
 - Fast scintillator (BC-422): $60 \times 30 \times 5 \text{ mm}^3$
 - 6x SiPM ($3 \times 3 \text{ mm}^2$, pixel pitch: $50 \mu\text{m}$)
- Expected **70 – 80 ps** with ~100 photoelectrons





Properties	BC-418	BC-420	BC-422	BC-422Q	BC-404
Light Output ^{a)} (% Anthracene)	67	64	55	19	68
Rise Time ^{a) b)} (ns)	0.5	0.5	0.35	0.11	0.7
Decay Time ^{a)} (ns)	1.4	1.5	1.6	0.7	1.8
Peak Wavelength ^{a)} (nm)	391	391	370	370	408
Attenuation Length ^{a)} (cm)	100	110	8	8	140
Time Resolution ^{c)} (ps)	48 ± 2	51 ± 2	43 ± 2	66 ± 3	–



Timing


• Study on dedicated timing layer

- Time resolution with standard strip-SiPM configuration: 300 – 400 ps
- Dedicated timing layer with scintillator tile + larger SiPM under consideration
 - **Target resolution ~ 50 ps** (from MEG II experience)
 - Tile layer would also help mitigating ghost hit in strip layers






• Test bench measurements

- Scintillator tile
 - $15 \times 15 \times 3 \text{ mm}^3$
 - standard (EJ200 (=BC408)), fast (EJ232 (=BC422))
- SiPM: MPPC S14160-3050HS ($3 \times 3 \text{ mm}^2$, pixel pitch: $50 \mu\text{m}$)...
- Resolution down to ~ 87 ps
 - Still a bit worse than that for MEG II detector even with larger N_{pe}
 - Optimisation in progress (scintillator quality, multiple SiPM connected in series, SiPM coupling, ...)



	Dimple readout	Double-side readout	MEG II
rise time	1.7ns	1.7ns	1.2ns
S/N	89	82	103
Light yield	200 p. e.	211 p. e.	~100 p. e.
time resolution	112 ps	87 ps	~80 ps
time res * \sqrt{LY} [ns · $\sqrt{\text{p. e.}}$]	1.6	1.3	~0.8





More Realism in Simulation


• Realistic conditions to implement in simulation

- ✓ • SiPM saturation
- ✓ • Hit position dependence of light yield
- ✓ • Misalignment between strip and SiPM
- Gap between strips (dead area)
- ...



SiPM saturation
(measured with UV laser)





Jet energy resolution



Position dependence of light yield



Jet energy resolution



Remaining Challenges

• Performance evaluation in beam test

- Standalone beam test at IHEP BSRF (leakage electron from synchrotron radiation beam line)
- Combined beam test at CERN with Sc-ECAL and CEPC-AHCAL in Oct 2022

• Engineering work for large scale production

- Scintillator production (injection moulding)
- Automated assembly system
- System for QC/QA
→More reliable cost estimate

• Readout electronics

- Power pulsing operation
- Long slab
- Electronics dedicated for timing



• Infrastructure design for ILD

• Most urgent R&D items from CEPC viewpoint

- Low-power and high-performance SiPM readout ASIC
- Active cooling

• No significant progress to address the issues

- No sufficient manpower and funding for both Chinese and Japanese sides
- Newcomers would be welcome in these area



Strip wrapping and assembly on EBU was done by hand (Shanghai Institute of Ceramic)