


# WG2 SRF: WP3 Crab Cavities Design Review Workshop #2

Peter McIntosh
UKRI-STFC Daresbury Laboratory

22<sup>nd</sup> June 2022





## Agenda for Today (GMT)



13:30	Introduction and Remit for the Workshop	Peter McIntosh (STFC)	5 min		
13:35	Specification Review	Peter McIntosh (STFC)	5 min		
Cavity Design Updates					
13:40	Elliptical/Racetrack	Graeme Burt (Lancaster University)	15 + 5 min		
14:00	RF Dipole (RFD)	Suba De Silva/Jean Delayen (ODU/JLab)	15 + 5 min		
14:20	Double Quarter Wave (DQW)	Silvia Verdu Andres (CERN)	15 + 5 min		
14:40	Wide Open Waveguide (WOW)	Binping Xiao (BNL)	15 + 5 min		
15:00	Quasi-waveguide Multicell Resonator (QMiR)	Andrei Lunin (FNAL)	15 + 5 min		
15:20	Preparations for Down-selection review (Sept 27 <sup>th</sup> 2022)	Peter McIntosh (STFC)	10 min		
15:30	Meeting close				

#### Preparations for 2<sup>nd</sup> Design Workshop (22<sup>nd</sup> June 2022)



- Assess and compare CC EM designs, not likely finally optimised:
  - Cavity,
  - HOMs,
  - Couplers,
  - Multipacting,
  - Tuning.
- Clarifying then next steps to perform first CC down-selection on 27<sup>th</sup> Sept 2022:
  - All EM design aspects complete, including pressure stability and fabrication assessment.
  - Down-select 2 optimum CC designs for future prototype development (external review).
- Final CC down-selection, post-prototype validation at ~18-months later (Mar 2024).

#### **Workshop Remit**



- For WP3 teams to identify progress made with CC designs.
- Identify outstanding issues which may exist regarding specifications as defined (v13).
- Agree the cavity parameters to define for down-selection review finalise process today.

#### **CC Design Updates**



Elliptical/Racetrack

• RF Dipole (RFD)

Double Quarter Wave (DQW)

Wide Open Waveguide (WOW)

Quasi-waveguide Multicell Resonator (QMiR)

G Burt (Lancaster U)

S De Silva/J Delayen (ODU/Jlab)

S Verdu Andres (CERN)

B Xiao (BNL)

A Lunin (FNAL)

### **Specifications Update (v13)**



Parameter		Recent Spec (After TDR)		1 TeV CoM Spec <sup>2</sup>			
Beam Energy (GeV) e-		TDR) Upgrade <sup>1,2</sup>			500		
Crossing Angle (mrad)		14					
Installation site (m from IP)		14					
RF Repetition Rate (Hz)		5	10	4			
number of bunches	ber of bunches 1312		2625	2450			
Bunch Train Length (ms)	Train Length (ms) 727		961	897			
Bunch Spacing (ns)	554			366			
Beam current (mA)	5.8		8.75	7.6			
Operating Temp (K)	2						
Cryomodule installation length (m)	3.25						
Horizontal beam-pipe separation (m)	0.1967	(centre) ±0	).0266 (each e	nd of ins	tallation	length)	
			-				
Cavity Frequency (GHz)	3.9	2.6	1.3	3.9	2.6	1.3	
Total Kick Voltage (MV)	0.615	0.923	1.845	2.5	3.7	7.4	
Max Ep (MV/m)	45			45			
Max Bp (mT)		80 80					
Amplitude regulation/cavity (% rms)	3.5 (for 2% luminosity drop)						
Relative RF Phase Jitter (deg rms)	0.069						
Timing Jitter (fs rms)	49 (for 2% luminosity drop)						
Max Detuning (Hz)		200 TBC					
Longitudinal impedance threshold (Ohm)							
Trasverse impedance threshold (MOhm/m) (X,Y)	48.8, 61.7						
Cavity field rotation tolerance/cavity (mrad rms)	5.2 (for 2% luminosity drop)						
Beam tilt tolerance (H and V) (mrad rms and urad rms)	0.35, 7.4 (for 2% luminosity drop)						
Minimum CC beam-pipe aperture size (mm)		>25 (same as FD magnets)					
Minimum Exraction beam-pipe aperture size (mm)		20					
Beam size at CC location (X, Y,Z) (mm,um,um)		0.97, 66, 300					
Beta function at CC location (X, Y) (m,m)		23200, 15400					
CC System operation		assume CW-mode operation					

#### **Break Here**



# Preparations for Down-Selection Review Sept 27<sup>th</sup> 2022



- Terms of Reference for the review to be developed (Myself, Akira and Kirk).
- Review panel membership to be determined and invitations solicited (Myself, Akira and Kirk):
  - Suggestions welcome from WP3 collaborators.
- Discussion of remaining requirements for all WP3 collaborators.

#### **CC** Design Parameters

- Propose standardised set of CC parameters for each design.
- This will become the basis for comparison at the Sept Down-selection review.

 No further feedback since Design Review meeting #1.

Parameter	Value	Units
Operating frequency		GHz
SOM		GHz
1 <sup>st</sup> Longitudinal HOM		GHz
1 <sup>st</sup> Transverse HOM		GHz
$E_p/E_t^*$		
$B_p/E_t^*$		mT/(MV/m)
$B_p/E_p$		mT/(MV/m)
G		Ω
R/Q		Ω
$R_tR_s$		$\Omega^2$
V <sub>t</sub> per cavity		MV
Ep		MV/m
Bp		mT
Total V <sub>t</sub>		MV
Total No. of cavities		
Active Cavity Length		mm
Flange-flange Cavity Length		
Number of cells		
Cavity Diameter		mm
Minimum Aperture		mm
FPC Q <sub>L</sub>		
Bandwidth		kHz
Cavity Input Power		kW
Horizontal Kick Factor k <sub>x</sub>		V/pC
Vertical Kick Factor k <sub>y</sub>		V/pC/m
Stored Energy W		J
HOM impedance (Longitudinal)		MΩ
HOM impedance (Transverse)		MΩ/m
First 3 multipole pararameters		



